



City of Tampa
Jane Castor, Mayor

Contract Administration
Michael W. Chucran, Director
306 East Jackson Street, 4N
Tampa, FL 33602
Office (813) 274-8116
Fax: (813) 274-7368

ADDENDUM 2
Via E-Mail
DATE: June 2, 2022

Contract: 22-C-00015; Kennedy Blvd Gravity Sewer Rehabilitation by CIPP

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: Replace Proposal page P-2R with the attached Proposal page P-2RR.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to ContractAdministration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Management Supervisor

**Kennedy Blvd Gravity Sewer Rehabilitation by CIPP
Contract 22-C-00015**

Item No.	Item	Quantity	Unit	Unit Price in Words	Unit Price	Total
100	Contingency	1	LS	One Hundred Thousand Dollars	\$100,000.00	\$100,000.00
102	Maintenance of Traffic	1	LS			
0408.2360	Cured in Place Pipe for 8" Dia. Gravity Sewer (.236 inch thick)	8,371	LF			
0410.2950	Cured in Place Pipe for 10" Dia. Gravity Sewer (.295 inch thick)	342	LF			
0415.2950	Cured in Place Pipe for 15" Dia. Gravity Sewer (.295 inch thick)	1,605	LF			
0601.08	Hydraulic Cleaning & Inspection of 8" Dia. Gravity Sewer	7,265	LF			
0601.10	Hydraulic Cleaning & Inspection of 10" Dia. Gravity Sewer	342	LF			
0601.15	Hydraulic Cleaning & Inspection of 15" Dia. Gravity Sewer	1,605	LF			
9000	Sewer Bypass with Tanker Truck	500	Hrs			
9050.08	Sewage Bypass Pumping for 8" Dia. Sewer	21,424	LF			
9050.10	Sewage Bypass Pumping for 10" Dia. Sewer	327	LF			
9050.15	Sewage Bypass Pumping for 15" Dia. Sewer	74	LF			
0621.08	Cleaning & Inspection of Tuberculated Cast Iron or Ductile Iron Sewer , 8" Dia.	1,106	LF			
0621.10	Cleaning & Inspection of Tuberculated Cast Iron or Ductile Iron Sewer , 10" Dia.	50	LF			
0621.15	Cleaning & Inspection of Tuberculated Cast Iron or Ductile Iron Sewer , 15" Dia.	50	LF			
0602.08	Additional Mechanical Cleaning & Inspection of 8" Dia. Gravity Sewer	50	LF			
0602.10	Additional Mechanical Cleaning & Inspection of 10" Dia. Gravity Sewer	50	LF			
0602.15	Additional Mechanical Cleaning & Inspection of 15" Dia. Gravity Sewer	50	LF			
2050	Reconnect Service Connections	173	EA			
2051.08	Chemical Grout Unit - chemical grout lateral post liner install - 8-inch gravity pipe diameter	160	EA			
2051.10	Chemical Grout Unit - chemical grout lateral post liner install - 10-inch gravity pipe diameter	10	EA			
2052.10	Chemical Grout Unit - chemical grout lateral post liner install - 15-inch gravity pipe diameter	10	EA			
4800	Manhole Rehabilitation by Coating System min. 250 mils thickness	2,400	SF			
4600	Cast Iron Frame and Cover	12	EA			
700	Disposal of Debris	50	CY			
Total					Total	