

Contract Administration Richard Mutterback, Director

306 East Jackson Street, 4N Tampa, FL 33602

> Office (813) 274-8116 Fax: (813) 274-7368

ADDENDUM 2 Via E-Mail DATE: May 5, 2025

Contract: 24-C-00002; E/W Green Spine Cycle Track PH 2A from Howard Ave to Rome Ave

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: The EOC Reporting number = 24-C-00002. All CONTRACTORS MUST enter their bid opportunity information in the Equal Opportunity Compliance (EOC) system within three business days of submission of the bid or proposal. The link to the EOC system is

https://fdotwp1.dot.state.fl.us/EqualOpportunityCompliance/Account.aspx/LogIn?ReturnUrl=%2fEqualOpportunityCompliance

Item 2: RFI - Does the City have a stockpile of granite curb that we can use on this project? Please refer to the specification for Removal of Existing Granite Curb. The first sentence states "excavate material from back of the granite curb". At Station 114+15 to station 114+61 it shows removal of existing granite curbing that is directly adjacent to sidewalk with no sod strip between the granite curb. The sidewalk at this location is not being called to be removed and replaced. How is the contractor to be paid for removal and replacement of this sidewalk?

RFI response: See SP-14.02. Since the existing sidewalk is to remain, contractor should use all care and remove the existing granite curb to be salvaged and reset, at this location from the front face/pavement side, since the pavement is to be removed at this location for the proposed bulb out. If it becomes absolutely necessary to remove and replace this 46LF of existing sidewalk, the City CEI can possibly authorize payment with the pay items for REMOVAL OF EXISTING CONCRETE and CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK. Existing granite curbs are to remain, with some to be reset. At this time, the City does have some stock for the small quantity of additional granite curb needed for this project.

- Item 3: 1. The 15% max for MOB & MOT Pay Items needs to be removed.
 - 2. You're missing a Clearing & Grubbing Pay Item.

RFI response: 1.) The Bid Proposal sheet P-2 does not contain 15% max for MOB & MOT LS Pay Items. The quantity for each of those pay items is 1 LS. (see pg 8)

2.) There are no C&G limits shown on the Typical Section for this project. Practically all work Is within the existing pavement or sidewalk except for drainage structures that would require construction outside of pavement limits. Please include any clearing and grubbing within the existing

– tampagov.net –	
------------------	--

appropriate pay items prices bid. Bidders to include any ancillary clearing and grubbing into the costs of associated work since there is no pay item for it directly. Pay items for concrete removal and sod are included so Note 5 of Sheet 6 covers restoration work without the need for a Clearing & Grubbing pay item.

Item 4: RFI - Can the intersection be under a full closure for storm work?

RFI response: Bidders should presume for their bid that the complete street/intersection closure is not permitted. The current design plans do not indicate any road closures, and the FDOT indexes included are for lane closures or shifts only. The City may consider contractor requests for full closure after bidding, with a customized MOT plan, including the proposed traffic detours and the required Portable Changeable Message Signs (PCMS), especially since W Cass St is a designated truck route road.

If the City allows closures, the Contractor will be responsible for providing a new Traffic Control Plan and obtaining any closure permits if needed. Construction work and associated lane and sidewalk closures within the City of Tampa right of way require a City Work Start (CWS) permit. CWS permits are applied for in Accela which can be accessed at the following link: https://aca-prod.accela.com/TAMPA/Default.aspx

The applicant must submit plans and appropriate MOT plans for all proposed work in the right of way. Please be sure to include the following in the online application:

- 1. City of Tampa project Manager Nina Mabilleau
- 2. A minimum of two project contacts

When filling out the worktable in Accela, each block with construction activity is to be listed by listing the "On" street and the intersecting street(s).

Item 5: RFI - Please note that one of the two contaminated sites is remediated and both locations are located farther than 500' from the proposed storm work. Does the dewatering for the storm work need to be treated? Please refer to SP-4.07 Identified Areas of Contamination. Please confirm all costs incurred with areas of contamination inclusive of the known contamination at 1702 W. Cass Street, Tampa, FL 33606 will be reimbursed by the owner through the work direct change/change order and that the contractor should not put any cost in our bid?

RFI response: Correct, costs incurred with areas of contamination will be reimbursed by the City from Contingency via Work Directed Change and you should not put any cost in your bid. This will be approved by the city engineer and the FDOT from contingency allowance, as encountered and needed. The Contamination Impact Certification, in the rear of the bid package specification book, states that the contamination "location/condition has no impact to the proposed project". In accordance with the specs: The Contractor shall employ a CAR Contractor to perform contamination assessment and remediation work, therefore if the dewatered groundwater is found contaminated, it will be the CAR's responsibility to remediate. See SP-4.07 IDENTIFIED AREAS OF CONTAMINATION. Furthermore, the contractor is responsible for all NPDES and/or other agency permits with regard to discharge. Contaminated dewatering may need to be tanked and disposed of properly per regulatory agency requirements. "Contractor to provide all invoicing (testing, permit fees, application for meter, metering by gallon, soil prep etc.). This will be approved by the City Engineer from the contingency allowance, as encountered and needed." See Contamination Impact Certification in bid package, .pdf sheet 282/286.

Item 6: RFI - Please confirm which class of RCP is required, the specs reference class three while the plans reference class two and four?

RFI response: All pipe to be RCP Class III.

Item 7: RFI - Please confirm that the storm is to flow to storm inlet S-103.

RFI response: Yes, runoff will flow to S-103 where it will fill up and then sheet flow down N Fremont Avenue.

Item 8: RFI - Please note that 12" RCP is no longer manufactured, should this be upsized to 15"?

RFI response: No. The 12" pipe cannot be upsized since it is connecting to an existing 12" pipe. Use Class III 12" RCP or connect the existing 12" pipe on N Fremont Avenue directly to S-102B.

Item 9: RFI -What class pipe is required for 15" RCP?

RFI response: Class III

Item 10: RFI - What class pipe is required for 18" RCP?

RFI response: Class III

Item 11: RFI - What class pipe is required for 24" RCP?

RFI response: Class III

Item 12: RFI - Please note there is a letter dated November 14th that states no existing drainage is being changed, so no environmental permit is required. Please clarify as we are tying into an existing storm system and adding new drainage.

RFI response: The project received an exemption (785609) from the SWFWMD on July 2, 2019, as stated in the 11/14/23 Final Design Memo for Environmental Permit. (see pg 10)

Item 13: RFI - Please confirm that the link provided on page SPT - 15 will take us to the correct City details for the proposed structures since no details were given in the plans.

RFI response: Refer to https://www.tampa.gov/document/stormwater-standard-details-25946 for City details.

Item 14: RFI - Please confirm that the 18" steel gas pipe is no longer active. Plan sheet 17 calls for its removal to accommodate the 18" storm run.

RFI response: TECO Peoples Gas provided greenlines during the project design indicating that the line is retired and out of service (see markup below). Per Specification G-1.03: "Contractor to make his own investigations to inform himself fully of the character, condition and extent of all such installations and structures as may be encountered and as may affect the construction operations." Per Specification SP-2.04: "The prime contractor is responsible for organizing the work of and coordination with any and all Utility Agency Owners involved within the project limits. The Utility Relocation Schedules submitted during the design phase have been provided." Utility Owner contact information is shown on General Notes, page 6 of the roadway plans.



Item 15: RFI - Is the existing 18" steel gas line grout filled? If not, is the contractor required to bulkhead the remaining lines?

RFI response: We do not know if the line is grouted but TECO Peoples Gas has provided information for the other Green Spine projects indicating that grouting is likely for out of service lines under pavement. The contractor may choose to bulkhead or grout the severed line, but it is not required. It is the prime contractor's responsibility to please coordinate with Utility Owners. The Utility Agency Owner contacts are listed on General Notes sheet 6 of the plans. There is a TECO Utility Relocation Schedule in the rear of the specifications.

Item 16: RFI - How thick is the existing asphalt?

RFI response: According the Geotech Report the existing pavement is about 4.5" thick.

Core ID	Approximate Location (Street, Lane, Distance)	Asphalt Thickness (in)	Paver Thickness (in)	Base Material and Thickness (in)	Subbase Material (AASHTO)	Approximate GWT Depth (ft)	
C-01	W. Cass Street, EB Lane, 350-ft. East of N. Albany Avenue Intersection	4 1/2	3	Shell – 4 ½	A-3	3	

Item 17: RFI - Is there a geotech report for this project, or one in the nearby area?

RFI response: See attached Geotechnical Report for this project. (see pg 14)

Item 18: RFI - Please confirm that S-102C requires a steel grate. It seems that this structure needs a cast iron grate that is traffic rated.

RFI response: S-102C can have the standard cast iron grate.

Item 19: RFI - If S-102C needs a steel grate, does it need to be galvanized and/or traffic rated?

RFI response: No steel grate is required.

Item 20: RFI - Does the contractor have to be certified with the Department of Transportation to bid the subject project?

RFI response: Paragraph 3 of the "Notice to Bidders" in the Specifications Package states, "A contractor must be pre-qualified in accordance with Rule Chapter 14-22 on the date of the Bid Opening or provide sufficient evidence of qualifications within ten (10 days thereof. All bidders must provide Certification of Current Capacity and Status of Contracts on Hand on the day of Bid Opening."

Item 21: RFI - Please refer to the Instructions to Bidders Section 1. Paragraph I-1.01 General reads The proposed work is the E/W Green Spine Cycle Track Ph 3b from 7th Ave to 13th Ave – Rebid and E/W Green Spine Cycle Track Ph 3c from 13th Ave to 21st Ave – Rebid. However, the advertisement and plans are for Ph 2a from Howard Ave. to Rome Ave. Please clarify. (see pg 6 & 7)

RFI response: As you can see by the page header of the Instructions to Bidder, this Contract 24-C-00002; is for E/W Green Spine Cycle Track - PH 2A from Howard Ave. to Rome Ave. In the first paragraph of Instructions to Bidders Section 1. Paragraph I-1.01 in the Division I specifications, page I-1a, replace "E/W Green Spine Cycle Track - PH 3B from 7th Ave to 13th Ave - ReBid and E/W Green Spine Cycle Track - PH 3C from 13th Ave to 21st Ave – ReBid" with "E/W Green Spine Cycle Track - PH 2A from Howard Ave. to Rome Ave." (see pg 6)

Item 22: RFI - Please refer to PDF page 80 of 178. The agreement on this page references the E/W Green Spine Cycle Track Ph 3b from 7th Ave to 13th Ave – Rebid and E/W Green Spine Cycle Track Ph 3c from 13th Ave to 21st Ave – Rebid. However, the advertisement and plans are for Ph 2a from Howard Ave. to Rome Ave. Please clarify.

RFI response: On AGREEMENT sheet A-1. PDF 85/286 replace "21-C-00022" with 24-C-00002". Also replace "Contract 21-C-00022; E/W Green Spine Cycle Track - PH 3B from 7th Ave to 13th Ave - ReBid and E/W Green Spine Cycle Track - PH 3C from 13th Ave to 21st Ave – ReBid" with "Contract 24-C-00002: E/W Green Spine Cycle Track - PH 2A from Howard Ave. to Rome Ave." The City Contract Specialist will include this correction on the revised Agreement once a bidder is selected. (see pg 7)

Item 23: To match the FPID, replace "21-C-00022" on PDF 118/286" with "24-C-00002" (see pg 9)

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to ContractAdministration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Management Supervisor

INSTRUCTIONS TO BIDDERS SECTION 1 - SPECIAL INSTRUCTIONS

I-1.01 GENERAL:

PH 2A from Howard Ave. to Rome Ave.

The proposed work is the E/W Green Spine Cycle Track - PH 3B from 7th Ave to 13th Ave - ReBid and E/W Green Spine Cycle Track - PH 3C from 13th Ave to 21st Ave - ReBid in the City of Tampa, as required for a complete project, as shown on the plans and detailed in the specifications. The work is located on land owned or controlled by the City of Tampa.

To be eligible to submit a proposal, a Bidder must hold the required and/or appropriate current license, certificate, or registration (e.g. DBPR license/certificate of authorization, etc.) in good standing at the time of receipt of Bids. Per Section 489.131, Florida Statutes, Proposals submitted for the construction, improvement, remodeling, or repair of public projects must be accompanied by evidence that the Bidder holds the required and/or appropriate current certificate or registration, unless the work to be performed is exempt under Section 489.103, Florida Statutes.

- I-1.02 FORM PREPARATION AND PRESENTATION OF PROPOSALS: Replace the second sentence with the following: Submission of the entire specification book is not required.
- I-1.03 ADDENDA Section I-2.03 is replaced with the following: No interpretation of the meaning of the Plans, Specifications, or other Contract Documents will be made to any Bidder orally.

Every request for such interpretation must be in writing, addressed to the City of Tampa, Contract Administration Department, 306 E. Jackson St., 4th Floor, Tampa, Florida 33602 and then emailed ContractAdministration@tampagov.net. To be given consideration, such request must be received at least seven (7) days prior to the date fixed for the opening of the Proposals. Any and all such interpretations and any supplemental instructions will be in the form of written addenda which, if issued, will be posted on DemandStar.Com and on the Department's web page. Failure of any Bidder to receive any such addenda shall not relieve said Bidder from any obligation under his Proposal as submitted. All addenda so issued shall become part of the Contract Documents.

I-1.04 INSTRUCTIONS TO BIDDERS

SECTION 2 – GENERAL INSTRUCTIONS. Section I-2.07 SIGNATURE AND QUALIFICATIONS OF BIDDERS is replaced with the following:

Proposals must be signed in ink by the Bidder with signature in full. When firm is a Bidder, the Proposal shall be signed in the name of the firm by one or more partners. When a corporation is a bidder the officer signing shall set out the corporate name in full beneath which he shall sign his name and give the title of his office.

If the bidder referred to in Section I-2.07 is a corporation, it must submit; upon request, a copy of its filed Articles of Incorporation. In addition, if the bidder was incorporated in another state, it must establish that it is authorized to do business in the State of Florida. If the bidder is using a fictitious name, it must submit upon request, proof of registration of such name with the Clerk of the Circuit Court of the County where its principal place of business is. Failure to submit what is required is grounds to reject the bid of that bidder.

SECTION 2 – GENERAL INSTRUCTIONS. Section I-2.14 NONDISCRIMINATION IN EMPLOYMENT is changed to add the following to the end of the existing text:

The following provisions are hereby incorporated into any contract executed by or on behalf of the City. Contractor shall comply with the following Statement of Assurance: During the performance of the Contract, the Contractor assures the City, that the Contractor is in compliance with Title VII of the 1964 Civil Rights Act, as amended, the Florida Civil Rights Act of 1992, and the City of Tampa Code of Ordinances, Chapter 12, in that Firm/Contractor does not on the grounds of race, color, national origin, religion, sex, sexual orientation, gender identity or expression, age, disability, familial status, or marital status, discriminate in any form or manner against said Firm's/Contractor's employees or applicants for employment. Contractor understands and agrees that the Contract is conditioned upon the veracity of this Statement of Assurance, and that violation of this condition shall be considered a material breach of the Award/Contract. Furthermore, Contractor herein assures the City that said Contractor will comply with Title VI of the Civil Rights Act of 1964 when federal grant(s) is/are

Contract 24-C-00002; E/W Green Spine Cycle Track - PH 2A from Howard Ave. to Rome Ave.

AGREEMENT

24-C-00002

for the performance of the work for the construction of Contract 21-C-00022 in accordance with your Proposal dated, amounting to a total of \$ as completed in accordance with subsections I-2.09 and I-2.10 of the Instruction to Bidders.
This AGREEMENT, made and entered into in triplicate, between the City of Tampa, Florida, hereinafter called the City, and hereinafter called the Contractor, as of the day of,
20 when the City Council of the City of Tampa, Florida adopted a Resolution authorizing, among other things, the Mayor's execution of this Agreement.
WITNESSETH that, in consideration of the mutual stipulations, agreements, and covenants herein contained, the parties hereto have agreed and hereby agree with each other, the Party of the First Part for itself, its successors and assigns, and the Party of the Second Part for itself, or himself, or themselves, and its successors and assigns, or his or their executors, administrators and assigns, as follows:
24-C-00002 PH 2A from Howard Ave. to Rome Ave. Contract 21-C-00022; E/W Green Spine Cycle Track - PH 3B from 7th Ave to 13th Ave - ReBid and E/W Green Spine Cycle
Track - PH 3C from 13th Ave to 21st Ave - ReBid, shall include, but not be limited to, maintenance of traffic, roadway, signing and pavement markings, signalization, utilities adjustments/relocations, landscape, hardscape, possible contanimation remediation with all associated work required for a complete project in accordance with the

Contract Documents referred to in Article 1.01 of this Agreement also includes this volume, applicable standard drawings, the plans and any provisions referred to whether actually attached or not.

Contract Documents.

Contract: 24-C-00002 E/W Green Spine Cycle Track -PH 2A from Howard Ave. to Rome Ave.

PAY ITEM #	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST IN WORDS	UNIT COST	UNIT COST TOTAL COST
0101 1	MOBILIZATION	S	1			
0102 1	MAINTENANCE OF TRAFFIC	ST	-			
0104 10 3	SEDIMENT BARRIER	Ч	213			
0104 18	INLET PROTECTION SYSTEM	EA	10			
0110 410	REMOVAL OF EXISTING CONCRETE	SY	105			
0120 6	EMBANKMENT	ζ	20			
0285701	OPTIONAL BASE, BASE GROUP 01	SY	194			
0327706	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SΥ	8564			
0337 783	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	N	902			
COT-T	INLETS, DITCH BOTTOM, TYPE T <10'	EA	2			
COT-E	INLETS, DITCH BOTTOM, TYPE E <10'	EA	1			
0425 271	MANHOLES, J-7, <10'	EA	1			
0425 5	MANHOLE, ADJUST	EA	3			
0430175112	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	H	4			
0430175118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	237			
0430175124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	20			
0520 2 4	CONCRETE CURB, TYPE D	LF	1990			
0520 7 1	GRANITE CURB, FURNISH & INSTALL	H	11			
0520 7 2	GRANITE CURB, RESET	LF	202			
0522 1	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	44			
0522 2	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	74			
0526 1	RED BRICK PAVERS, INSTALL	SY	94			
0526 1A	RED BRICK PAVERS, FURNISH AND INSTALL	SY	94			
0527 2	DETECTABLE WARNINGS	SF	98			
0570 1 2	PERFORMANCE TURF, SOD	SY	76			
COT-003	CITY INLET TYPE 3	EA	2			
EX - 9910	ADJUST VALVE BOX (HEIGHT)	EA	4			
EX-099925	Contingency	rs	1	Fifty One Thousand Six Hundred Fifty Dollars	\$51,650	DO NOT BID
ROADWAY				COMPONENT TOTAL		

PREPARED BY: Erin Lawson, P. E.,



SPECIFICATIONS PACKAGE Contract Number: 24-C-00002 FINANCIAL PROJECT ID(S).439476-5-58-01 FEDERAL FUNDS DISTRICT SEVEN HILLSBOROUGH COUNTY

The applicable Articles and Subarticles of the General Requirements & Covenants division (Division I) of the FY 2024-25 edition of the Florida Department of Transportation Standard Specifications for Road and Bridge Construction are added, and all of the Construction Details and Materials divisions (Division II & III) are revised, as follows:

I hereby certify that this specifications package has been properly prepared by me, or under my responsible charge, in accordance with procedures adopted by the Florida Department of Transportation.

This item has been digitally signed and sealed by Scott Samuels, PE on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Date: May 1, 2025

State of Florida.

Professional Engineer, License No.: 88738

Firm/Agency Name: <u>Kisinger, Campo & Associates, Inc.</u>
Firm/Agency Address: <u>201 North Franklin Street, Suite 900</u>

City, State, Zip Code: Tampa, Florida 33602

Page(s): <u>1-WM-128</u>

FPID(S): 439476-5-58-01





2379 Broad Street, Brooksville, Florida 34604-6899 (352) 796-7211 or 1-800-423-1476 (FL only) WaterMatters.org

Bartow Office

170 Century Boulevard Bartow, Florida 33830-7700 (863) 534-1448 or 1-800-492-7862 (FL only)

Sarasota Office

78 Sarasota Center Boulevard Sarasota, Florida 34240-9770 (941) 377-3722 or 1-800-320-3503 (FL only) Tampa Office

7601 U.S. 301 North (Fort King Highway) Tampa, Florida 33637-6759 (813) 985-7481 or 1-800-836-0797 (FL only)

May 21, 2020

City of Tampa Attn: Nina Mabilleau 306 East Jackson Street, MC 290A4E Tampa, FL 33602

Subject: Project Evaluation - Project Exempt

File Number:

Project Name: E. Floribraska Ave. From N. Tampa St. to N.

9th St. 800480 Hillsborough

County: Hillsborough Sec/Twp/Rge: S12/T29S/R18E

Reference: Rule 62-330, Florida Administrative Code (F.A.C.)

Dear Ms. Mabilleau:

The District has reviewed the information you submitted for the project referenced above and has determined that an Environmental Resource Permit (ERP) **will not be required** for the proposed resurfacing of Floribraska Ave. from N Tampa to N 9th Street, addition of a bike lane, and widening of the associated sidewalk [Rule 62-330.051(4)(e), F.A.C.]

The information received by the District will be kept on file to support the District's determination regarding your application. This information is available for viewing or downloading through the District's Application and Permit Search Tools located at www.WaterMatters.org/permits.

The District's determination that your project does not require an ERP is only applicable pursuant to the statutes and rules in effect at the time the information was submitted and may not be valid in the event subsequent changes occur in the applicable rules and statutes. Additionally, this notification does not mean that the District has determined that your project is permanently exempt from permitting requirements. Any subsequent change you make in the project's operation may necessitate further evaluation or permitting by the District. Therefore, you are advised to contact the District before beginning the project and before beginning any activity which is not specifically described in your submittal. Your timely pursuit of this activity is encouraged to avoid any potential rule changes that could affect your request.

This letter constitutes notice of Intended Agency Action of the project referenced above. The District's action in this matter only becomes closed to future legal challenges from members of the public if such persons have been properly notified of the District's action and no person objects to the District's action within the prescribed period of time following the notification. The District does not publish notices of agency action. If you wish to limit the time within which a person who does not receive actual written notice from the District may request an administrative hearing regarding this action, you are strongly encouraged to publish, at your own expense, a notice of agency action in the legal advertisement section of a newspaper of general circulation in the county or counties where the activity will occur. Publishing notice of agency action will close the window for filing a petition for hearing. Legal requirements and instructions for publishing notice of agency action, as well as a noticing form that can be used is available

from the District's website at www.WaterMatters.org/permits/noticing. If you publish notice of agency action, a copy of the affidavit of publishing provided by the newspaper should be sent to the Regulation Division at the District Service Office that services this permit or other agency action, for retention in the File of Record for this agency action.

If you have questions regarding this matter, please contact Brett Bjornberg in the Tampa Service Office, extension 2247. Please reference the Project Name and Inquiry/Permit Number in future communications concerning this project.

Sincerely,

David Kramer, P.E. Bureau Chief Environmental Resource Permit Bureau Regulation Division

Enclosures: Notice of Rights Calvin Hardie P.E.

Stantec Consulting Services Inc.

Notice of Rights

Administrative Hearing

- 1. You or any person whose substantial interests are or may be affected by the District's intended or proposed action may request an administrative hearing on that action by filing a written petition in accordance with Sections 120.569 and 120.57, Florida Statutes (F.S.), Uniform Rules of Procedure Chapter 28-106, Florida Administrative Code (F.A.C.) and District Rule 40D-1.1010, F.A.C. Unless otherwise provided by law, a petition for administrative hearing must be filed with (received by) the District within 21 days of receipt of written notice of agency action. "Written notice" means either actual written notice, or newspaper publication of notice, that the District has taken or intends to take agency action. "Receipt of written notice" is deemed to be the fifth day after the date on which actual notice is deposited in the United States mail, if notice is mailed to you, or the date that actual notice is issued, if sent to you by electronic mail or delivered to you, or the date that notice is published in a newspaper, for those persons to whom the District does not provide actual notice.
- 2. Pursuant to Subsection 373.427(2)(c), F.S., for notices of intended or proposed agency action on a consolidated application for an environmental resource permit and use of sovereignty submerged lands concurrently reviewed by the District, a petition for administrative hearing must be filed with (received by) the District within 14 days of receipt of written notice.
- 3. Pursuant to Rule 62-532.430, F.A.C., for notices of intent to deny a well construction permit, a petition for administrative hearing must be filed with (received by) the District within 30 days of receipt of written notice of intent to deny.
- 4. Any person who receives written notice of an agency decision and who fails to file a written request for a hearing within 21 days of receipt or other period as required by law waives the right to request a hearing on such matters.
- 5. Mediation pursuant to Section 120.573, F.S., to settle an administrative dispute regarding District intended or proposed action is not available prior to the filing of a petition for hearing.
- 6. A request or petition for administrative hearing must comply with the requirements set forth in Chapter 28-106, F.A.C.A petition for a hearing must: (1) explain how the substantial interests of each person requesting the hearing will be affected by the District's intended action or proposed action, (2) state all material facts disputed by the person requesting the hearing or state that there are no material facts in dispute, and (3) otherwise comply with Rules 28-106.201 and 28-106.301, F.A.C. Chapter 28-106, F.A.C., can be viewed at www.flrules.org or at the District's website at www.WaterMatters.org/permits/rules.
- 7. A petition for administrative hearing is deemed filed upon receipt of the complete petition by the District Agency Clerk at the District's Tampa Service Office during normal business hours, which are 8:00 a.m. to 5:00 p.m., Monday through Friday, excluding District holidays. Filings with the District Agency Clerk may be made by mail, hand-delivery or facsimile transfer (fax). The District does not accept petitions for administrative hearing by electronic mail. Mailed filings must be addressed to, and hand-delivered filings must be delivered to, the Agency Clerk, Southwest Florida Water Management District, 7601 US Hwy 301, Tampa, FL 33637-6759. Faxed filings must be transmitted to the District Agency Clerk at (813) 367-9776. Any petition not received during normal business hours shall be filed as of 8:00 a.m. on the next business day. The District's acceptance of faxed petitions for filing is subject to certain conditions set forth in the District's Statement of Agency Organization and Operation, available for viewing at www.WaterMatters.org/about.

Judicial Review

- 1. Pursuant to Sections 120.60(3) and 120.68, F.S., a party who is adversely affected by District action may seek judicial review of the District's action. Judicial review shall be sought in the Fifth District Court of Appeal or in the appellate district where a party resides or as otherwise provided by law.
- 2. All proceedings shall be instituted by filing an original notice of appeal with the District Agency Clerk within 30 days after the rendition of the order being appealed, and a copy of the notice of appeal, accompanied by any filing fees prescribed by law, with the clerk of the court, in accordance with Rules 9.110 and 9.190 of the Florida Rules of Appellate Procedure (Fla. R. App. P.). Pursuant to Fla. R. App. P. 9.020(h), an order is rendered when a signed written order is filed with the clerk of the lower tribunal.

Geotechnical Engineering Services Report

Green Spine Cycle Track
City of Tampa, Hillsborough County, Florida
City of Tampa Contract No.: 17-D-00022

Prepared for: Kisinger Campo & Associates

201 N. Franklin St., Suite 400 Tampa, Florida 33602

Prepared by: MC Squared, Inc.

5808-A Breckenridge Parkway Tampa, Florida 33610

Project No. T021705.031 June 14, 2018





June 14, 2018

Mr. Chris Meares, PE Civil Department Manager **Kisinger Campo & Associates** 201 N. Franklin St., Suite 400 Tampa, Florida 33602

Subject: Geotechnical Engineering Services Report

Green Spine Cycle Track

City of Tampa, Hillsborough County, Florida City of Tampa Contract No.: 17-D-00022

MC² Project No. T021705.031

Dear Mr. Meares:

MC Squared, Inc. (MC²) has performed the requested geotechnical engineering services, including a pavement condition survey, for the referenced project. This report presents the results of our fieldwork and laboratory testing, evaluation of the data generated, and our input recommendations for the design and construction of the project.

We appreciate the opportunity to be of service on this project. Should you have any questions and/or comments on the contents of this report, please do not hesitate to contact us.

Respectfully submitted,

MC²

Steven T. Nason, El

Staff Engineer

Bradley A. Crowson, El

Associate Project Manager

Winston L. Stewart, PE

Vice President/Chief Engineer

Florida PE No. 81643

Jeffery L. Hooks, PE

Project Engineer

Florida PE No. 67882

TABLE OF CONTENTS

1	INT	TRODUCTION	1
	1.1	Purpose	1
	1.2	PROJECT AUTHORIZATION	1
2	PRO	OJECT INFORMATION	1
	2.1	PROJECT DESCRIPTION	1
	2.2	SITE DESCRIPTION	1
	2.3	Scope of Services	3
3	SUI	BSURFACE EXPLORATION	4
	3.1	GENERAL	4
	3.2	Standard Penetration Test Borings	4
	3.3	PAVEMENT CORES	5
	3.4	HAND AUGER BORINGS	5
	3.5	Double-Ring Infiltrometer Tests	6
4	LAE	BORATORY TESTING	6
	4.1	SOIL CLASSIFICATION TESTING	6
	4.2	MOISTURE CONTENT	7
	4.3	PERCENT PASSING THE NO. 200 SIEVE	7
	4.4	ATTERBERG LIMITS	8
5	SIT	E AND SUBSURFACE CONDITIONS	8
	5.1	HILLSBOROUGH COUNTY SOIL SURVEY	8
	5.2	USGS TOPOGRAPHIC SURVEY	9
	5.3	Subsurface Conditions	9
	5.4	GROUNDWATER INFORMATION	10
	5.5	Infiltration Rates	11
	5.6	PAVEMENT CONDITION SURVEY	11
6	REC	COMMENDATIONS	20
	6.1	GENERAL	20
	6.2	MAST ARM POLE CONSIDERATIONS	21
	6.3	SITE PREPARATION	21
	6.4	SELECTION AND PLACEMENT OF FILL	22
	6.5	REUSE OF EXCAVATED SOILS AS STRUCTURAL FILL	22
7	REF	PORT LIMITATIONS	22

APPENDIX

Table 5: Summary of Soil Parameters

Table 6: Summary of Pavement Cores

Pavement Core Summary (10 pages)

Project Location Map - Sheet 1

Boring Location Map - Sheets 2 through 14

USDA Soil Survey/USGS Topographic Maps - Sheet 15

Subsurface Boring Profiles - Sheets 16 through 18

Report of Core Boring – Sheet 19

Individual Soil Profiles (17 Pages)

Double Ring Infiltrometer Test Results (5 pages)

Test Procedures

1 INTRODUCTION

1.1 Purpose

The purpose of the geotechnical services was to evaluate and explore the subsurface conditions for the proposed design of a cycle track, bio-swales and a signalization mast arm. This report describes the exploratory and testing procedures and includes the following items:

- (a) Scope of Services Performed
- (b) The Results of the Subsurface Exploration
- (c) The Results of the Laboratory Testing
- (d) Engineering Evaluations of the Data Gathered
- (e) Pavement Condition Survey
- (f) Design and Construction Considerations

1.2 Project Authorization

Authorization to proceed with this project was issued by Mr. Chris Meares, PE with **Kisinger Campo & Associates (KCA)** through a Subconsultant Agreement for Geotechnical Services dated March 15, 2018. The project was performed in general accordance with **MC²** Proposal No. T021705.031.

2 PROJECT INFORMATION

2.1 Project Description

Based on the information provided by Mr. Meares of **KCA** through e-mailed and verbal communications, it is our understanding that the project requires geotechnical services to support the design of a cycle track, bio-swales and a signalization mast arm. The segregated bi-directional cycle track is located along Cass Street, Nuccio Parkway, and N. 15th Street. The signal mast arm is to be installed at the intersection of N. Howard Avenue and W. Cass Street.

If any of this project's description is incorrect or has changed, please inform **MC**² so that we may amend, if appropriate, the information presented in this report.

2.2 Site Description

The project site is located along W. Cass Street from N. Howard Avenue to N. Nebraska, Nuccio Parkway from N. Nebraska Avenue to E. 13th Avenue and N. 15th Street from E. 13th Avenue to just past E. 19th Avenue in the City of Tampa, Florida (hereinafter "City"). The project alignment consists of a 2-lane, 4-lane undivided, and a 4-lane divided major collector urban roadway through the downtown area of the City.



Figure 1: Project Site (photographed on January 11, 2017, Google Earth)



Figure 2: Nuccio Pkwy facing East (photographed on June 1, 2018)

2.3 Scope of Services

Our scope of services consisted of the following:

- 1. Conducted a visual reconnaissance of the project site, and reviewed the USDA Soil Survey for Hillsborough County and the USGS Topographic Maps for the area.
- Cleared utilities with applicable utility companies in the area of proposed borings through coordination with Sunshine 811 and obtained required necessary permits to perform the fieldwork.
- 3. Performed ten (10) pavement cores, subsequent deepened with hand-auger (HA) borings through the subbase to approximately 5-ft. below the ground surface (bgs) or until the borehole collapsed or until refusal is met, whichever came first.
- 4. Performed five (5) individual HA borings to a depth of 5-ft. bgs or until borehole collapsed, along the shoulders of the project roadway.
- 5. Performed five (5) Double-Ring Infiltrometer tests (DRIT) at the requested locations that were conducted in the soils at a depth of approximately 1.5-ft. bgs.
- 6. Performed one (1) Standard Penetration Test (SPT) boring to an approximate depth of 26-ft. bgs, near the proposed signalization mast arm location at the intersection of N. Howard Avenue and W. Cass Street.
- 7. All SPT, HA, pavement cores and DRITs were performed at locations approved by KCA.
- 8. Performed a pavement condition survey (PCS) at each pavement core location, which included the crack and rutting ratings and overall condition of the pavement.
- 9. Visually examined all recovered soil samples in the laboratory and performed limited laboratory testing on selected representative samples to develop a soil legend for the project, using the Unified Soil Classification System (USCS) and the American Association of State Highway and Transportation Officials (AASHTO) Classification System, as appropriate. The laboratory testing consisted of percent passing the No. 200 sieve, natural moisture content determinations and Atterberg Limits testing.

The data collected from the subsurface exploration, along with the results of the laboratory testing, were used in the engineering evaluations and for developing geotechnical recommendations. Our geotechnical report contains the following:

1. General assessment of area geology based on our experience, study of geological literature and boring information.

- General location and description of potentially deleterious materials encountered in the borings, which may interfere with future construction or performance, including existing fills or surficial organics.
- 3. Critical design and/or construction considerations, based on the soil and groundwater conditions developed from the borings.
- 4. Groundwater levels in the borings, where encountered, and an estimate of the seasonal high groundwater table (SHWT).
- 5. Estimate of the soil infiltration rates based on the results of the DRITs performed within the proposed locations of the bio-swales.
- 6. Summary of the findings of the Pavement Condition Survey.

The scope of our services did not include an environmental assessment for determining the presence or absence of wetlands or hazardous or toxic materials in the soil, bedrock, groundwater, or air, on or below or around the roadway alignment. Any statements in this report or on the boring logs regarding odors, colors, unusual or suspicious items or conditions are strictly for the information of our client. Additionally, this was not a sinkhole investigation. Accordingly, our field exploration was not designed to address sinkhole-related issues. Any mention of geological characteristics in relation to karst conditions is for informational purposes only.

3 SUBSURFACE EXPLORATION

3.1 General

The field exploration program consisted of performing one (1) SPT boring, ten (10) pavement cores, five (5) HA borings and five (5) DRITs. The fieldwork was performed and supervised by **MC²'s** qualified staff geotechnical engineers. The fieldwork was performed from May 24, 2018 to June 5, 2018, after the appropriate required permits were attained. The field exploration services were overseen by one of **MC²'s** Florida State licensed professional geotechnical engineers.

3.2 Standard Penetration Test Borings

The SPT boring was completed at the site in general accordance with ASTM D1586 (Standard Test Method for Penetration Test and Split Barrel Sampling of Soils) by a truck-mounted drill rig using a wet-rotary procedure and a safety hammer. Representative soil samples were obtained using a 2-in. outer diameter split-barrel sampler driven into the soil by a 140-lb hammer operating freely over a drop of 30-inches. The number of blows required to drive the sampler through a 12-in. interval, after initial penetration of 6-in., is termed the Standard Penetration Resistance, or "N" value, and is indicated for each sample on the boring log. The "N" value may be taken as an indication of the empirical relative density (cohesionless soils) or consistency (cohesive soils) of soils in-situ.



Figure 3: Performing SPT-01 on N. Howard Ave. (photographed June 6, 2018)

The first four (4) feet in the boring was augered by hand in order to avoid potentially unmarked utilities and to help in the determining the SHWT.

Groundwater, if encountered, is normally measured during the advancement of our borings and prior to the introduction of bentonite to the drilling fluid. Once bentonite is added, an accurate groundwater level is difficult to measure at the time of drilling. Upon completion of our drilling, our test boring was backfilled using bentonite pellets. The groundwater conditions are discussed in **Section 5.4** herein.

3.3 Pavement Cores

The pavement cores were performed using a 4-in. diameter core barrel that was advanced through the asphalt layer. This was followed by HA borings through the base and subbase material to a depth of 5-ft. bgs or until the borehole collapsed, whichever occurred first. The boreholes were backfilled and compacted with soil cuttings and then patched to restore each core location. The pavement cores and soil samples were collected and transported to our Tampa, FL office.

3.4 Hand Auger Borings

The hand auger borings were completed at the site in general accordance with ASTM D1452 (Standard Practice for Soil Exploration and Sampling by Auger Borings) using a 3 ¼-in. diameter auger bucket. Samples were collected in 4 to 6-in. increments, classified and logged in the field, with confirmatory classifications by **MC**² professional geotechnical engineers at our Tampa, Florida laboratory location. Boreholes were backfilled and compacted with soil cuttings.



Figure 4: Performing C-04 on Nuccio Pkwy., facing southwest (photographed May 29, 2018)

3.5 Double-Ring Infiltrometer Tests

Prior to performing the DRITs in the proposed project areas, a HA boring was advanced to a depth of five (5) feet to determine the soil type and groundwater level. The soil classification and groundwater level encountered at these locations are discussed herein. The DRITs were performed at the locations labeled as DRI-01 through DRI-05 at an approximate depth of 1.5-ft. bgs. The approximate locations of the DRITs are shown in the **Appendix.**

The DRITs were performed in general accordance with ASTM test designation D-3385 using a 24-inch diameter outer ring and a 12-inch diameter inner ring. A minimum constant head of 4-in. was maintained in both rings with the volume necessary to maintain the head in both the inner ring and the annular space between the inner and outer rings measured over time. The volume of water infiltrated during timed intervals is calculated as the incremental infiltration rate.

4 LABORATORY TESTING

4.1 Soil Classification Testing

A representative set of soil samples were tested in the laboratory to assist in the classification and determination of engineering characteristics of the soils, based on their mechanical and physical behavior. Laboratory testing was accomplished in general accordance with applicable USCS and

AASHTO standards, as appropriate. Laboratory tests completed on representative soil samples retrieved for this project were:

- Four (4) moisture content determinations (ASTM D-2216),
- Four (4) percent passing the No. 200 US standard sieve tests (ASTM D-1140),
- Three (3) Atterberg limits test (ASTM D-4318), however, one sample was non-rollable and non-plastic, and
- Visual classification in general accordance with applicable procedures (ASTM D-2488).

Results for each of these laboratory tests are summarized in **Table 1** and are presented on the **Individual Soil Profile** logs provided in the **Appendix.**

Table 1: Summary of Laboratory Testing

Boring ID (Depth) (ft)	Moisture Content (%)	Percent Passing No. 200 Sieve (%)	Plastic Limit	Liquid Limit	Plasticity Index	Classification
C-10 (4.5-5)	17.1	21.4	16	28	12	A-2-6
HA-02 (1.5-3.5)	17.1	4.0	1	-	ı	A-3
HA-02 (3.5-4.5)	83.0	4.3	NR	NP	NP	A-3 (organic)
SPT-01 (18.5-20)	34.2	38.6	17	42	25	SC

NR = Non-Rollable, NP = Non-Plastic

4.2 Moisture Content

The laboratory moisture content test consists of the determination of the percentage of moisture contents in selected samples in general accordance with ASTM test designation D-2216 (Standard Test Methods for Laboratory Determination of Water Content of Soil and Rock by Mass). Briefly, natural moisture content is determined by weighing a sample of the selected material and then drying it in a warm oven. Care is taken to use gentle heat so as not to destroy any organics. The sample is then removed from the oven and reweighed. The difference between the two weights is the amount of moisture removed from the sample. The weight of the moisture divided by the weight of the dry soil sample is the percentage by weight of the moisture in the sample.

4.3 Percent Passing the No. 200 Sieve

The wash gradation test measures the percentage of a dry soil sample passing the No. 200 sieve. By definition in the Unified Soil Classification System, the percentage by weight passing the No. 200 sieve is the silt and clay content. The amount of silt and clay in a soil influences its properties, including permeability, workability and suitability as fill. This test was performed in general accordance with ASTM D-1140 (Standard Test Methods for Amount of Material Finer than the No. 200 (75 μ m) Sieve).

4.4 Atterberg Limits

The laboratory Atterberg limits test measures the liquid limit, plastic limit, and plastic index of soils in accordance with ASTM D4318 (Standard Test Methods for Liquid Limit, Plastic Limit and Plasticity Index of Soils). These characteristics are used in multiple engineering classification systems to specify the fine-grained fractions of soils. By classifying, other characteristics of soils can also be correlated with engineering behavior such as compressibility, permeability, compatibility, shrink-swell potential, and shear strength.

5 SITE AND SUBSURFACE CONDITIONS

5.1 Hillsborough County Soil Survey

The USDA Soil Conservation Service *Soil Survey of Hillsborough County, Florida* was reviewed for general information on the shallow soils in the site vicinity. The survey area data is Version 16 dated October 4, 2017, with aerial images taken from December 29, 2010 to January 17, 2014. The USDA Soil Conservation Service Soil Survey outlines approximate areas dominated by a particular shallow soil type. Small areas of other soils may occur within the mapping unit. We have concluded that the project site is within four (4) mapping units: Immokalee-Urban land complex (22), Myakka-Urban land complex (32) and Tavares-Urban land complex, 0 to 5 percent slopes (55) and Urban land (56).

Immokalee-Urban land complex (22) has a parent material of sandy marine deposits and a typical profile of fine sand from zero to 80-in. bgs. The material is poorly drained and has a moderately high to high capacity to transmit water. The depth to the groundwater table is about 6 to 18 inches.

Myakka-Urban land complex (32) has a parent material of sandy marine deposits and typical profile of fine sand from zero to 80-in. bgs. The material is poorly drained and has a moderately high to high capacity to transmit water. The depth to the groundwater table is about 6 to 18 inches.

Tavares-Urban land complex, 0 to 5 percent slopes (55) has a parent material of Eolian or sandy marine deposits and a typical profile of fine sand from zero to 80-in. bgs. The material is moderately well drained and has a very high capacity to transmit water. The depth to the groundwater table is about 42 to 72 inches.

Urban land (56) is heavily developed areas that consequentially have a high variability in soil types due to fill placement and movement. Because of this, soil characteristics are difficult to assign.

The USDA Soil Survey is not necessarily an exact representation of the soils on the site. The mapping is based on interpretation of aerial maps with scattered shallow borings for confirmation. Accordingly, borders between mapping units are approximate and the change may be transitional. Differences may also occur from the typical stratigraphy, and small areas of other

similar and dissimilar soils may occur within the soil-mapping unit. As such, there may be differences in the mapped description and the soil test boring descriptions presented in this report. The survey is, however, a good basis for evaluating the shallow soil conditions of the area. The **USDA Soil Survey Map** is included in the **Appendix** for information and reference, as necessary.

5.2 USGS Topographic Survey

The U.S. Geological Survey (USGS) maintains a database of historical topographic maps. Based upon our review of the USGS Topographic Maps, 7.5 Minute Series "Tampa Quadrangle" where datum is NGVD 1929, approximate elevation of the project alignment is 10 to 45 feet. No major changes in elevation within the project limits are evident in the USGS topographic maps over time. A **Topographic Map** is included in the **Appendix** for information and reference, as necessary.

5.3 Subsurface Conditions

The subsurface conditions described herein are of a generalized nature to highlight the major stratification features and material characteristics encountered during the field exploration. The soil profiles included in the **Appendix** should be reviewed for specific information at individual boring locations. These profiles include soil description, stratification and groundwater table depths where encountered. The stratification shown on the boring profiles represents the conditions only at the actual boring locations. Variations might occur and should be expected between the boring locations.

Pavement Cores (C-01 through C-10)

The subsurface soil conditions encountered at the pavement core locations consisted of poorly graded fine SAND to fine SAND with silt (A-3) throughout the boreholes. SAND with gravel (A-1-b) with shell fragments was encountered in C-02 from underneath the asphalt pavement and brick pavers to approximately 2.5-ft. bgs. Clayey SAND (A-2-6) was encountered in C-10 from 4.5 to 5-ft. bgs where the borehole was terminated. Except at C-03, the upper foot of the subbase material appeared to be stabilized in the boreholes. However, no laboratory testing has been performed to determine this.

Hand-Auger Borings (HA-01 through HA-05)

The subsurface conditions observed at the HA boring locations consisted of poorly graded fine SAND to fine SAND with silt (A-3) throughout the boreholes. SAND with some organic material was encountered in HA-02 from 3.5 to 4.5-ft. bgs where the borehole collapsed. Silty fine SAND (A-2-4) was encountered in HA-05 from 4.5 to 5-ft. bgs where the borehole was terminated.

<u>SPT Borings (SPT-01)</u>

The subsurface boring conditions revealed in the signal mast arm boring consisted of medium dense, poorly graded fine SAND to SAND with silt (SP-SM) from the surface to 8-ft. bgs. The surficial SAND was followed by very loose to medium dense, clayey SAND (SC) from 8 to 25-ft. bgs,

weathered to competent LIMESTONE was encountered at 25-ft. bgs. The boring was terminated in competent LIMESTONE at 26-ft. bgs.

In general, the shallow soil conditions encountered in the soil borings performed throughout the proposed development area appear to be relatively similar to the surveyed soil mapping units previously described, taking into consideration previous site work and grading operations.

5.4 Groundwater Information

The groundwater table was not encountered (GNE) in the majority of the pavement cores and two (2) of the HA borings. In C-01, C-04, HA-01, HA-02 and HA-03 the groundwater was encountered at 3, 5, 4, 4 and 5-ft. bgs, respectively. The groundwater table was also encountered at 3-ft. bgs in SPT-01. The depth to the groundwater table and estimated SHWT at each boring location are presented in **Table 2** below. The estimated SHWT values are based upon our review of available publications and our review of the soil profiles and samples collected in the field.

Table 2: Summary of Water Levels and SHWT Estimates

Boring ID	Encountered Water Table Depth (ft)	USDA Water Table Depth (ft)	Estimated SHWT Depth (ft)
C-01	3	0.5 to 1.5	2.5
C-02	GNE	N/A	3
C-03	GNE	N/A	3
C-04	5	N/A	3
C-05	GNE	N/A	4
C-06	GNE	N/A	4
C-07	GNE	3.5 to 6	4
C-08	GNE	3.5 to 6	4
C-09	GNE	3.5 to 6	4
C-10	GNE	3.5 to 6	2.5
HA-01	4	0.5 to 1.5	2
HA-02	4	N/A	2.5
HA-03	5	N/A	2.5
HA-04	GNE	N/A	3.5
HA-05	GNE	3.5 to 6	4
SPT-01	3	3.5 to 6	2.5

In general, groundwater levels tend to fluctuate during periods of prolonged drought and extended rainfall, and would likely be affected by tidal influences along the project's alignment. In addition, a seasonal effect will also occur in which higher groundwater levels are normally recorded in rainy seasons. If the groundwater level is critical to design or construction, temporary observation wells should be installed along the alignment to monitor groundwater fluctuations over an adequate period that permits more accurate determinations of wet and dry seasonal

levels.

Fluctuation of the groundwater levels is normal, and should be anticipated. We recommend that the Contractor determine the actual groundwater levels at the time of construction to determine groundwater impact on the construction activities.

5.5 Infiltration Rates

Prior to performing the DRITs in the proposed project area, a hand auger boring was performed to determine the soil type and groundwater level. The soils consisted of poorly graded fine SAND to fine SAND with silt (A-3) throughout the boreholes. SAND with some organic material was encountered in HA-02 from 3.5 to 4.5-ft. bgs where the borehole collapsed. Silty fine SAND (A-2-4) was encountered in HA-05 from 4.5 to 5-ft. bgs where the borehole was terminated. The groundwater level was encountered at 4-ft. bgs in HA-01 and HA-02, and 5-ft. bgs in HA-03. The groundwater table was not encountered at borings HA-04 and HS-05. The DRITs were performed at a depth of approximately 1.5-ft. bgs. The approximate locations of the DRITs are shown in the **Appendix**. The results of these tests are summarized in **Table 3** below.

Table 3: Summary of Double-Ring Infiltrometer Tests

DRIT ID	Approximate Depth	Measured Infiltration Rate	
	Performed (ft)	(in/hour)	
DRI-01	1.5	9.5	
DRI-02	1.5	4	
DRI-03	1.5	6	
DRI-04	1.5	8.5	
DRI-05	1.5	10.5	

Test results in the **Appendix** include a graphical representation of the elapsed time versus infiltration rate in inches/hour. The infiltration rates obtained are considered within the typical range for the sands identified at the test locations, but rates could possibly fluctuate depending on groundwater levels and soil density variations. The drainage area design should also consider the impact of silty sand and/or clayey sand soils, which could restrict vertical infiltration.

5.6 Pavement Condition Survey

MC² has completed a field review to evaluate the existing pavement conditions along West Cass Street, Nuccio Parkway, and N. 15th Street, including documentation on the roadway surface conditions, at each pavement core location. We noted pavement changes, distressed areas, roughness and patching. Photos are also included to provide examples of each distress type observed. The values for crack and rut rating provided were determined in general accordance with the FDOT 2017 Flexible Pavement Condition Survey Handbook.

C-01 along W. Cass Street (Eastbound Lane)

Longitudinal cracks (Class II), transverse cracks (Class II), pavement raveling and block cracking (Class II) are present throughout the roadway. These distresses are generally caused by deficiencies within the pavement and base materials.

Figures 3 & 5: Longitudinal Cracking (250-ft. West of N. Fremont Avenue)

Transverse Cracking (270-ft. west of N. Fremont Avenue)



Asphalt patches have been used in parking areas and locations where the pavement surface is weathered. Weathered asphalt patches are generally present due to the vehicle traffic load exceeding the design criteria of the roadway.

Figures 6 & 7: Block Cracking (300-ft. west of N. Fremont Avenue)
Asphalt Patches / Transverse Cracking (270-ft. west of N. Fremont Avenue)



The pavement condition at this site should be considered **Poor**. This assessment was determined from a crack rating of 3.5 and a rut rating of 8.

C-02 along W. Cass Street (Outside Eastbound Lane)

Longitudinal cracks (Class I), transverse cracks (Class I), pavement raveling, and block cracking (Class I) are present throughout the roadway. These distresses are generally caused by deficiencies within the pavement and base materials.

Figures 8 & 9: Longitudinal Cracking (330-ft. east of North Boulevard)

Transverse Cracking (280-ft. east of North Boulevard)



Figure 10: Block Cracking (335-ft. east of North Boulevard)



The pavement condition at this site should be considered **Poor**. This assessment was determined from a crack rating of 5.5 and a rut rating of 9.

C-03 along W. Cass Street (Paved Median)

Transverse cracks (Class I) and reflection cracks are present in the eastbound lane of West Cass Street. These distresses are generally caused by deficiencies within the pavement and base materials.

Figures 11 & 12: Transverse Cracking (200-ft. west of Doyle Carlton Drive)

Reflection Cracking (240-ft. west of Doyle Carlton Drive)



The pavement condition at this site should be considered **Fair**. This assessment was determined from a crack rating of 10 and a rut rating of 8.

C-04 along Nuccio Parkway (Outside Northbound Lane)

Longitudinal cracks (Class I), transverse cracks (Class I), pavement raveling are present throughout the roadway. These distresses are generally caused by deficiencies within the pavement and base materials.

Figure 13 & 14: Longitudinal Cracking (400-ft. northeast of N. Nebraska Ave.)

Transverse Cracking (430-ft. northeast of N. Nebraska Ave.)





Figure 15: Transverse Cracking and Raveling (370-ft. northeast of N. Nebraska Ave.)

The pavement condition at this site should be considered Fair. This assessment was determined from a crack rating of 8.5 and a rut rating of 9.

C-05 along Nuccio Parkway (Outside Northbound Lane)

Longitudinal cracks (Class II), and transverse cracks (Class II) are present throughout the roadway. These distresses are generally caused by deficiencies within the pavement and base materials.

> Figure 16 & 17: Longitudinal Cracking (30-ft. north of E. 6th Avenue) Transverse Cracking (80-ft. north of E. 6th Avenue)



15




Figure 18: Poor Drainage (20-ft. north of E. 6th Avenue)

The pavement condition at this site should be considered **Poor**. This assessment was determined from a crack rating of 6.5 and a rut rating of 9.

C-06 along Nuccio Parkway (Outside Northbound Lane)

Longitudinal cracks (Class I) and transverse cracks (Class I) are present throughout the roadway. These distresses are generally caused by deficiencies within the pavement and base materials.



Figure 19 & 20: Longitudinal Cracking (40-ft. north of E. 8th Avenue)

Transverse Cracking (150-ft. north of E. 8th Avenue)

The pavement condition at this site should be considered **Poor**. This assessment was determined from a crack rating of 7 and a rut rating of 9.

C-07 along Nuccio Parkway (Outside Northbound/Eastbound Lane)

Fatigue cracking (Class II) also known as alligator cracking is present in a few locations as seen in the figures above. Asphalt patches have been used in locations where the pavement surface is weathered or appears to be raveling. Asphalt patches as well as alligator cracking are generally present due to the vehicle traffic load exceeding the design criteria of the roadway.

Figure 21 & 22: Longitudinal Cracking (150-ft. west of N. 14th Street)

Transverse Cracking (80-ft. west of N. 14th Street)



Longitudinal cracks (Class I) and transverse cracks (Class I) are present throughout the roadway. These distresses are generally caused by deficiencies within the pavement and base materials.

Figure 23 & 24: Transverse Cracking / Fatigue (Alligator) Cracking (70-ft. west of N. 14th Street)

Alligator Cracking / Patching (70-ft. west of N. 14th Street)



rigure 23. Raveling (70-jt. west of N. 14 Street)

Figure 25: Raveling (70-ft. west of N. 14th Street)

The pavement condition at this site should be considered **Poor**. This assessment was determined from a crack rating of 5.5 and a rut rating of 8.

C-08 along Nuccio Parkway (Outside Northbound Lane)

Transverse cracks (Class I) are present in the roadway and are generally caused by deficiencies within the pavement and base materials.



Figure 26: Transverse Cracking (45-ft. south of E. 13th Avenue)

The pavement condition at this site should be considered **Good**. This assessment was determined from a crack rating of 10 and a rut rating of 10.

C-09 along N. 15th Street (Outside Northbound Lane)

Transverse cracks (Class I) are present in the roadway and are generally caused by deficiencies within the pavement and base materials.



Figure 27: Transverse Cracking (125-ft. north of E. 14th Avenue)

The pavement condition at this site should be considered **Good**. This assessment was determined from a crack rating of 10 and a rut rating of 10.

C-10 along N. 15th Street (Outside Northbound Lane)

Longitudinal cracks (Class I), transverse cracks (Class II), and block cracking (Class II) are present throughout the roadway. These distresses are generally caused by deficiencies within the pavement and base materials.

Figure 28 & 29: Transverse Cracking (160-ft. north of E. 17th Avenue)

Transverse Cracking (200-ft. north of E. 17th Avenue)



19

Figure 30 & 31: Longitudinal Cracking / Transverse Cracking / Block Cracking (240-ft. north of E. 17th Avenue)



Based upon the Pavement Condition Survey performed by **MC**², the pavement condition at this site should be considered <u>Poor</u>. This assessment was determined from a crack rating of 3.5 and a rut rating of 9.

The values for crack and rut rating provided were determined in general accordance with the FDOT 2017 Flexible Pavement Condition Survey Handbook and are summarized in the following **Table**.

Table 4: Summary of Pavement Condition Survey

Davament			Overall
Pavement Core ID	Crack Rating	Rut Rating	Roadway
Core iD			Condition
C-01	3.5	8	POOR
C-02	5.5	9	POOR
C-03	10	8	FAIR
C-04	8.5	9	FAIR
C-05	6.5	9	POOR
C-06	7	9	POOR
C-07	5.5	8	POOR
C-08	10	10	GOOD
C-09	10	10	GOOD
C-10	3.5	9	POOR

6 RECOMMENDATIONS

6.1 General

The following recommendations have been developed based on the previously described project characteristics, our review of published data, information provided by others, our site reconnaissance and the results of our subsurface exploration and associated laboratory testing. The

soils encountered throughout the project corridor at the locations explored are suitable for the proposed improvements provided the recommendations included in this report are followed.

6.2 Mast Arm Pole Considerations

Based on the SPT N-values and soil types at various depths, we have estimated the strength and unit weight parameters for design of the pole structure. These parameters were obtained from the SPT boring performed at the specified location. We used empirical correlations between the "N" value and the types of soils to arrive at the internal friction angle, cohesion, dry and wet densities, etc. The results are summarized on the **Table 5: Summary of Soil Parameters** in the **Appendix**. The soil parameters shown are for the different soil strata encountered at the boring location and categorized using the USCS soil classification system.

Once the final loads are known, the foundation system may be designed using the soil parameters provided in this report. The foundation design should also consider torsional loads created by wind action.

If the foundation system selected is a drilled shaft, its design and construction should be done in accordance with publication "FHWA-IF-99-025 Drilled Shafts: Construction Procedures and Design Methods" and the latest FDOT Structural Guidelines and Standard Specifications for Road and Bridge Construction.

We also recommend that this complete report be provided to the various design team members and the appropriate contractors. Potential contractors should be informed of this report prior to them providing pricing.

6.3 Site Preparation

Site preparation should include stripping and removal of surficial (topsoil) shallow organics and/or manmade obstructions (pavements, curbing, etc.) where present prior to replacing with properly compacted structural fill and/or pavement sections. If unstable soils are encountered during excavation that cannot be adequately densified in place, they should be removed and replaced under the recommendations of the MC² representative. The location of any existing underground utility lines, tanks, etc. within the construction corridor should be established, prior to construction. The contractor should exercise caution during construction and compaction of soils so as not to cause settlement of any nearby existing structures or utilities induced by vibrations. The Contractor must control and adjust the vibration to not disturb existing structures and/or subsurface utilities that may be near the project. In this regard, the Contractor may want to consider using non-vibratory compaction equipment. The contractor is solely responsible for any settlement caused by his actions.

The natural soil encountered directly underneath any roadway excavation should be compacted to 98% of the modified Proctor's maximum dry density within $\pm 2\%$ of the optimum moisture content. If compaction is not practical or the material encountered is unsuitable, then the material should be excavated an additional 6-in. and backfilled with either compacted fill, lean concrete or

course stone wrapped in a geotextile fabric to create a working platform for the roadway construction equipment.

6.4 Selection and Placement of Fill

After the stripped site has been accepted by the Geotechnical Engineer, the fill required to bring the site to final grade may be placed in properly compacted lifts. Fill material should be inorganic (less than 5%), non-plastic granular soil (clean to slightly silty SAND that classifies as A-3 and A-2-4) that is free of detrimental materials such as organics, clay clods, debris, roots, rocks larger than 1 inch in greatest dimension, etc. Careful evaluation should be made of any slightly organic to organic soils and clayey soils prior to use. The planned fill soils should be evaluated to determine that they meet the recommended material properties. The suitability of the soil for reuse should be evaluated against the project requirements.

In general, the shallow, on-site soils encountered in our boreholes meets the above criteria. This material may be used for grading, leveling, as general fill, structural fill and as backfill. The fill should be placed in level lifts not to exceed 12-in. loose thickness. Where fill is to be used in green areas, the soil should be compacted to at least 95% of the soil's modified Proctor maximum dry density and +/- 2% of the optimum moisture content, as determined by ASTM designation D1557. In any areas to be paved over, the soil should be compacted to 98% of the soil's modified Proctor maximum dry density and +/- 2% of the optimum moisture content. In-place density tests should be performed on each lift by an experienced engineering technician working under the direction of a licensed Geotechnical Engineer to verify that the recommended degree of compaction has been achieved. Within small excavations such as around utilities, we recommend the use of smaller hand or remote guided equipment. A maximum loose lift thickness of 4-in. is recommended when using such equipment.

6.5 Reuse of Excavated Soils as Structural Fill

Most of the near surface soils classified as SP, SP-SM/A-3, A-2-4 excavated during construction should, in our opinion, be suitable for reuse as fill material provided it meets our requirements and recommendations presented in this report. Routine adjustment of moisture content may be necessary to allow compaction in accordance with project specifications. The planned fill soils should be evaluated to determine that they meet the recommended material properties.

7 REPORT LIMITATIONS

The evaluations and recommendations detailed herein are based on the available limited soil information obtained by **MC**² and information provided by **KCA** for the Green Spine Cycle Track Project. If there are any revisions to the plans for this project or if deviations from the subsurface conditions noted in this report are encountered during construction, **MC**² should be notified immediately to determine if changes to our recommendations or additional testing are required for this project. In the event that **MC**² is not retained to address such revisions and/or changes, **MC**² cannot be held responsible for their potential impact on the performance of the project.

Green Spine Cycle Track
City of Tampa, Hillsborough County, Florida
MC2 Project No. T021705.031

MC² warrants that the findings or professional advice contained herein has been made in accordance with generally accepted professional geotechnical engineering practices in the local area. No other warranties are implied or expressed.

After the plans and specifications are more complete, MC² should be provided the opportunity to review the final design plans and specifications to assess that our findings have been properly incorporated into the design documents. At that time, it may be necessary to submit recommendations for supplementary information. This report has been prepared for the exclusive use of KCA and their client.

APPENDIX

Table 5: Summary of Soil Parameters
Table 6: Summary of Pavement Cores
Pavement Core Summary (10 pages)
Project Location Map - Sheet 1
Boring Location Map - Sheets 2 through 14
USDA Soil Survey/USGS Topographic Maps - Sheet 15
Subsurface Boring Profiles - Sheets 16 through 18
Report of Core Boring – Sheet 19
Individual Soil Profiles (17 Pages)
Double Ring Infiltrometer Test Results (5 pages)
Test Procedures

Table 5: Summary of Soil Parameters

Depth	N Value	Soil	•	Jnit Weight)**	Angle of Internal	Earth P Coeffic	ressure cients*	Average Undrained	Ultimate Shear	
(ft)	Range	Classification (USCS)	Saturated (pcf)	Submerged (pcf)	Friction	Active (K _a)	Passive (K _p)	Cohesion C _u ** (psf)	Strength (psf)	
				SPT-0	1					
0-8	11	SP-SM	110.0	47.6	30	0.333	3.00	0	-	
8-15	27	SC	115.0	52.6	0	1	1	2,700	-	
15-25	3	SC	100.0	37.6	0	1	1	300	-	
25-26	50+	LIMESTONE	135.0	72.6	0	1	1	0	15,000	

^{*}Values are for level (non-sloping) backfill; no surcharge loads on backfill

NOTE: Hand augers were performed in the top 4 feet to avoid utilities

^{**}Based on empirical correlations

Table 6: Summary of Pavement Cores

rune or our many of rune me cores							
Core ID	Approximate Location (Street, Lane, Distance)	Asphalt Thickness (in)	Paver Thickness (in)	Base Material and Thickness (in)	Subbase Material (AASHTO)	Approximate GWT Depth (ft)	
C-01	W. Cass Street, EB Lane, 350-ft. East of N. Albany Avenue Intersection	4 ½	3	Shell – 4 ½	A-3	3	
C-02	W. Cass Street, Outside EB Lane, 350-ft. East of North Blvd. Intersection	2 ½	2 ¾	Not Encountered	A-3	GNE	
C-03	W. Cass Street, Paved Median, 190-ft. West of W. Gasparilla Plaza Intersection	4 ¾	-	Limerock – 7 ¼	A-3	GNE	
C-04	Nuccio Parkway, Outside NB Lane, 590-ft. North of N. Nebraska Avenue Intersection	4	-	Limerock – 10	A-3	5	
C-05	Nuccio Pkwy, Outside NB Lane, 90-ft. North of E. 6 th Avenue Intersection	3 ½	-	Limerock – 8 ½ A-3	GNE		
C-06	Nuccio Pkwy, Outside NB Lane, 90-ft. South of E. 9 th Avenue Intersection	2 ¾	-	Limerock – 9 ¼	A-3	GNE	
C-07	Nuccio Pkwy, Outside NB Lane, 350-ft. South of E. 12 th Avenue Intersection	3 ¾	-	Limerock – 11 A-3		GNE	
C-08	Nuccio Pkwy, Outside NB Lane, 20-ft. South of N. 15 th Street Merger	3	-	Limerock – 11	A-3	GNE	
C-09	N. 15 th Street, Outside NB Lane, 50-ft. South of E. 15 th Avenue Intersection	3 ½	3 1/2	Not Encountered	A-3	GNE	
C-10	N. 15 th Street, Outside NB Lane, 40-ft. South of 18 th Avenue Intersection	6	-	Not Encountered	A-3	GNE	

NOTE: Photographs of the pavement cores are included in the Pavement Core Summaries. Photographs may or may not be representative of the thicknesses measured within the borehole.

GWT = Groundwater Table, GNE = Groundwater Table Not Encountered



Core C-01: 4 ½" Asphalt 3" Paver 4 ½" Shell Base SAND with silt (A-3) Subbase

W. Cass Street, EB Lane, 350-ft. East of N. Albany Avenue Intersection

MC ²	Green Spine Cycle Track City of Tampa, Hillsborough County, Florida COT Contract No.: 17-D-00022	For: Kisinger Campo & Associates	
GEOTECHNICAL • ENVIRONMENTAL	COT Contract No.: 17-D-00022	MC ² Project No. T021705.031	
MATERIALS TESTING	PAVEMENT CORE SUMMARY	Date: 5/24/18	



Core C-02: 2 ½" Asphalt 2 ¾" Paver No Base Encountered SAND with silt (A-3) Subbase

W. Cass Street, Outside EB Lane, 350-ft. East of North Blvd. Intersection



Green Spine Cycle Track
City of Tampa, Hillsborough
County, Florida
COT Contract No.: 17-D-00022

PAVEMENT CORE SUMMARY

For:

Kisinger Campo & Associates

MC² Project No. T021705.031

Date: 5/29/18



Core C-03: 4 ¾" Asphalt (cracked underneath as shown)
7 ¼" Limerock Base
SAND with silt (A-3) Subbase

W. Cass Street, Paved Median, 190-ft. West of W. Gasparilla Plaza Intersection



Green Spine Cycle Track
City of Tampa, Hillsborough
County, Florida
COT Contract No.: 17-D-00022

PAVEMENT CORE SUMMARY

For:

Kisinger Campo & Associates

MC² Project No. T021705.031

Date: 5/24/18



Core C-04: 4" Asphalt 10" Limerock Base SAND with silt (A-3) Subbase

Nuccio Parkway, Outside NB Lane, 590-ft. North of N. Nebraska Avenue Intersection



Green Spine Cycle Track
City of Tampa, Hillsborough
County, Florida
COT Contract No.: 17-D-00022

PAVEMENT CORE SUMMARY

For:

Kisinger Campo & Associates

MC² Project No. T021705.031

Date: 5/29/18



Core C-05: 3 ½" Asphalt 8 ½" Limerock Base SAND with silt (A-3) Subbase

Nuccio Pkwy, Outside NB Lane, 90-ft. North of E. 6th Avenue Intersection



Green Spine Cycle Track
City of Tampa, Hillsborough
County, Florida
COT Contract No.: 17-D-00022

PAVEMENT CORE SUMMARY

For:

Kisinger Campo & Associates

MC² Project No. T021705.031

Date: 5/31/18



Core C-06: 2 %" Asphalt 9 %" Limerock Base SAND with silt (A-3) Subbase

Nuccio Pkwy, Outside NB Lane, 90-ft. South of E. 9th Avenue Intersection

For: Kisinger Campo & Associa	MC ² Project No. T021705.031	Date: 5/31/18
Green Spine Cycle Track City of Tampa, Hillsborough County, Florida	COI CONTRACT NO.: I/-D-00022	PAVEMENT CORE SUMMARY
MC ²	GEOTECHNICAL • ENVIRONMENTAL	MATERIALS TESTING



Core C-07: 3 3/4" Asphalt 11" Limerock Base SAND with silt (A-3) Subbase

Nuccio Pkwy, Outside NB Lane, 350-ft. South of E. 12th Avenue Intersection



Green Spine Cycle Track
City of Tampa, Hillsborough
County, Florida
COT Contract No.: 17-D-00022

PAVEMENT CORE SUMMARY

For:

Kisinger Campo & Associates


MC² Project No. T021705.031

Date: 5/31/18



SAND with silt (A-3) Subbase Core C-08: 3" Asphalt 11" Limerock Base

Nuccio Pkwy, Outside NB Lane, 20-ft. South of N. 15th Street Merger



COT Contract No.: 17-D-00022 City of Tampa, Hillsborough **Green Spine Cycle Track** County, Florida

Kisinger Campo & Associates

For:

MC² Project No. T021705.031

Date: 6/1/18 PAVEMENT CORE SUMMARY



Core C-09: 3 ½" Asphalt 3 ½" Paver No Base Encountered SAND with silt (A-3) Subbase

N. 15th Street, Outside NB Lane, 50-ft. South of E. 15th Avenue Intersection



Green Spine Cycle Track
City of Tampa, Hillsborough
County, Florida
COT Contract No.: 17-D-00022

PAVEMENT CORE SUMMARY

For:

Kisinger Campo & Associates

MC² Project No. T021705.031


Date: 6/1/18



Core C-10: 6" Asphalt (saw cut captured in bottom layer as shown) SAND with silt (A-3) Subbase No Base Encountered

N. 15th Street, Outside NB Lane, 40-ft. South of 18th Avenue Intersection

For:	Kisinger Campo & Associates	MC ² Project No. T021705.031	Date: 6/1/18
Green Spine Cycle Track	City of Tampa, Hillsborough County, Florida	COI CONTRACT NO.: 17-D-00022	PAVEMENT CORE SUMMARY
	MC ²	GEOTECHNICAL • ENVIRONMENTAL	MATERIALS TESTING



DATE NAME REVISION APPROVED BY:

MC SQUARED, INC.
Geotechnical Consultants
5808-A Breckenridge Parkway
Tampa, FL 33610
Ph:813-623-3399 Fax:813-623-6636

FLORID - ENGINEERING CERTIFIC - TE C -UTHORIZ - TION No. 9191 Jeffery L. Hooks, P.E. FLORID - LICENSE No. 67882

		NAME	DATE
OF	DESIGNED BY:	TC	11/01/2017
	DRAWN BY:	KH	05/31/2018
	CHECKED BY:	JH	06/11/2018
	SUPERVISED BY:	WS	


Project Location Map

MC² PROJ. NO. SHEET NO.

Green Spine Cycle Track
Hillsborough County, Florida

T021705.031

1



Approximate SPT Location

Approximate Hand Auger Location

Approximate DRI Location


	APPROVED BY:	REVISION	NAME	DATE
N 102				
IVIC				
GEOTECHNICAL • ENVIRONMENTAL MATERIALS TESTING				

MC SQUARED, INC. Geotechnical Consultants 5808-A Breckenridge Parkway Tampa, FL 33610 Ph:813-623-3399 Fax:813-623-6636

ORID - ENGINEERING CERTIFIC - TE OF	DESIGNED
-UTHORIZ-TION No. 9191 Jeffery L. Hooks, P.E.	DRAWN BY
FLORID - LICENSE No. 67882	CHECKED

		NAME	DATE	Boring Location Map	MC ² PROJ. NO.	SHEET NO.	
OF	DESIGNED BY:	TC	11/01/2017		WIG 1 1100: 110:		
	DRAWN BY:	KH	05/31/2018	Green Spine Cycle Track	T021705.031		
	CHECKED BY:	JH	06/11/2018	Hillsborough County, Florida		2	
	SUPERVISED BY:	WS		i illioborough Sounty, i londa			

Graphic Scale (feet)



Approximate SPT Location

Approximate Hand Auger Location

Approximate DRI Location

APPROVED BY: DATE REVISION NAME MC²


MC SQUARED, INC. Geotechnical Consultants 5808-A Breckenridge Parkway Tampa, FL 33610 Ph:813-623-3399 Fax:813-623-6636

FLORID - ENGINEERING CERTIFIC -TE OF -UTHORIZ -TION No. 9191 Jeffery L. Hooks, P.E. FLORID - LICENSE No. 67882

		NAME	DATE	
-	DESIGNED BY:	TC	11/01/2017	
	DRAWN BY:	KH	05/31/2018	
	CHECKED BY:	JH	06/11/2018	
	SUPERVISED BY:	WS		

Boring Location Map	MC ² PROJ. NO.	SHEET NO.
Green Spine Cycle Track Hillsborough County, Florida	T021705.031	3

Graphic Scale (feet)



Approximate SPT Location

Approximate Hand Auger Location

Approximate DRI Location


Graphic Scale (feet) DATE NAME MC² PRO LNO SHEET NO Boring Location Man

	APPROVED BY:	REVISION	NAME	DATE
N/C2				
IVIC				
GEOTECHNICAL • ENVIRONMENTA MATERIALS TESTING				

MC SQUARED, INC. Geotechnical Consultants 5808-A Breckenridge Parkway Tampa, FL 33610 Ph:813-623-3399 Fax:813-623-6636

FLORID - ENGINEERING CERTIFIC-TE OF	DES
-UTHORIZ-TION No. 9191 Jeffery L. Hooks, P.E.	DRA
	CHE

	,		Boring Location Map	I MC ² PROJ. NO. I	I SHEET NO
DESIGNED BY:	TC	11/01/2017		me meetie	0.1.22.1.10
DRAWN BY:	KH	05/31/2018	Green Spine Cycle Track		
CHECKED BY:	JH	06/11/2018		T021705.031	4
SUPERVISED BY:	WS		Timoborough County, Florida		



LEGEND:

Approximate Pavement Core Location

Approximate SPT Location

Approximate Hand Auger Location

Approximate DRI Location

REVISION APPROVED BY: DATE NAME MC²


MC SQUARED, INC. Geotechnical Consultants 5808-A Breckenridge Parkway Tampa, FL 33610 Ph:813-623-3399 Fax:813-623-6636

FLORID - ENGINEERING CERTIFIC -TE OF -UTHORIZ -TION No. 9191 Jeffery L. Hooks, P.E. FLORID - LICENSE No. 67882

		NAME	DATE	
-	DESIGNED BY:	TC	11/01/2017	
	DRAWN BY:	KH	05/31/2018	
	CHECKED BY:	JH	06/11/2018	
	SUPERVISED BY:	WS		

Boring Location Map	MC ² PROJ. NO.	SHEET NO.
Green Spine Cycle Track illsborough County, Florida	T021705.031	5

Graphic Scale (feet)




Approximate SPT Location

Approximate Hand Auger Location

REVISION

DATE

NAME



MC SQUARED, INC. Geotechnical Consultants 5808-A Breckenridge Parkway Tampa, FL 33610 Ph:813-623-3399 Fax:813-623-6636

FLORID - ENGINEERING CERTIFIC - TE -UTHORIZ - TION No. 9191 Jeffery L. Hooks, P.E. FLORID - LICENSE No. 67882

		NAME	DATE	
OF	DESIGNED BY:	TC	11/01/2017	L
	DRAWN BY:	KH	05/31/2018	
	CHECKED BY:	JH	06/11/2018	
	SLIDED//ISED BV:	WS		

MC² PROJ. NO. SHEET NO. 6 T021705.031

Graphic Scale (feet)

Boring Location Map Green Spine Cycle Track Hillsborough County, Florida SUPERVISED BY: WS



DATE NAME REVISION APPROVED BY:

MC²
Ge
5808
Tam

MC SQUARED, INC. Geotechnical Consultants 5808-A Breckenridge Parkway Tampa, FL 33610 Ph:813-623-3399 Fax:813-623-6636

FLORID - ENGINEERING CERTIFIC - TE OF - UTHORIZ - TION No. 9191 Jeffery L. Hooks, P.E. FLORID - LICENSE No. 67882

		NAME	DATE	
)F	DESIGNED BY:	TC	11/01/2017	
	DRAWN BY:	KH	05/31/2018	
	CHECKED BY:	JH	06/11/2018	
	SUPERVISED BY:	WS		

Boring Location Map

MC² PROJ. NO. SHEET NO.

Green Spine Cycle Track
Hillsborough County, Florida

T021705.031

7





DATE NAME REVISION APPROVED BY:

MC SQUARED, INC.
Geotechnical Consultants
5808-A Breckenridge Parkway
Tampa, FL 33610
Ph:813-623-3399 Fax:813-623-6636

FLORID - ENGINEERING CERTIFIC - TE C -UTHORIZ - TION No. 9191 Jeffery L. Hooks, P.E. FLORID - LICENSE No. 67882


		NAME	DATE	
OF	DESIGNED BY:	TC	11/01/2017	L
	DRAWN BY:	KH	05/31/2018	
	CHECKED BY:	JH	06/11/2018	
	SUPERVISED BY:	WS		

Boring Location Map MC² PROJ. NO. SHEET NO.

Green Spine Cycle Track
Hillsborough County, Florida

T021705.031

9



Approximate Pavement Core Location Approximate Hand Auger Location

Approximate SPT Location

Approximate DRI Location

DATE REVISION APPROVED BY: NAME MC²


MC SQUARED, INC. Geotechnical Consultants 5808-A Breckenridge Parkway Tampa, FL 33610 Ph:813-623-3399 Fax:813-623-6636

FLORID - ENGINEERING CERTIFIC - TE C -UTHORIZ - TION No. 9191 Jeffery L. Hooks, P.E. FLORID - LICENSE No. 67882

		NAME	DATE	
OF	DESIGNED BY:	TC	11/01/2017	
	DRAWN BY:	KH	05/31/2018	
	CHECKED BY:	JH	06/11/2018	
	SUPERVISED BY:	ws		

Graphic Scale (feet) MC² PROJ. NO. SHEET NO. Green Spine Cycle Track Hillsborough County, Florida 10 T021705.031

Boring Location Map



DATE NAME REVISION APPROVED BY:

MC SQUARED, INC.
Geotechnical Consultants
5808-A Breckenridge Parkway
Tampa, FL 33610
Ph:813-623-3399 Fax:813-623-6636

FLORID- ENGINEERING CERTIFIC-TE OF -UTHORIZ-TION No. 9191 Jeffery L. Hooks, P.E. FLORID- LICENSE No. 67882


		NAME	DATE
OF	DESIGNED BY:	TC	11/01/2017
	DRAWN BY:	KH	05/31/2018
	CHECKED BY:	JH	06/11/2018
	SUPERVISED BY:	WS	

Boring Location Map MC² PROJ. NO. SHEET NO.

Green Spine Cycle Track
Hillsborough County, Florida

T021705.031

11



Approximate Hand Auger Location

Approximate DRI Location

APPROVED BY: DATE REVISION NAME MC²


MC SQUARED, INC. Geotechnical Consultants 5808-A Breckenridge Parkway Tampa, FL 33610 Ph:813-623-3399 Fax:813-623-6636

FLORID – ENGINEERING CERTIFIC – TE – UTHORIZ – TION No. 9191 Jeffery L. Hooks, P.E. FLORID – LICENSE No. 67882

		NAME	DATE
OF	DESIGNED BY:	TC	11/01/2017
	DRAWN BY:	KH	05/31/2018
	CHECKED BY:	JH	06/11/2018
	SUPERVISED BY:	WS	

Boring Location Map MC² PROJ. NO. SHEET NO. Green Spine Cycle Track Hillsborough County, Florida 12 T021705.031

Graphic Scale (feet)



REVISION

Approximate SPT Location

MC²

Approximate Hand Auger Location

DATE

NAME


Approximate DRI Location APPROVED BY:

MC SQUARED, INC. Geotechnical Consultants 5808-A Breckenridge Parkway Tampa, FL 33610 Ph:813-623-3399 Fax:813-623-6636

FLORID - ENGINEERING CERTIFIC-TE -UTHORIZ-TION No. 9191 Jeffery L. Hooks, P.E. FLORID - LICENSE No. 67882

		NAME	DATE
OF	DESIGNED BY:	TC	11/01/2017
	DRAWN BY:	KH	05/31/2018
	CHECKED BY:	JH	06/11/2018
	SUPERVISED BY:	WS	

Graphic scale (feet)				
Boring Location Map		MC ² PROJ. NO.	SHEET NO	
Green Spine Cycle Track Hillsborough County, Florida		T021705.031	13	



Approximate Hand Auger Location

Approximate SPT Location

Approximate DRI Location

DATE NAME REVISION APPROVED BY:


GEOTECHNICAL* ENVIRONME

MC SQUARED, INC. Geotechnical Consultants 5808-A Breckenridge Parkway Tampa, FL 33610 Ph:813-623-3399 Fax:813-623-6636

FLORID - ENGINEERING CERTIFIC - TE OF -UTHORIZ - TION No. 9191 Jeffery L. Hooks, P.E. FLORID - LICENSE No. 67882


		NAME	DATE
OF	DESIGNED BY:	TC	11/01/2017
	DRAWN BY:	KH	05/31/2018
	CHECKED BY:	JH	06/11/2018
	SLIDEB//ISED BV:	WS	


Graphic Scale (feet)




TAMPA QUADRANGLE FLORIDA-HILLSBOROUGH COUNTY 7.5 MINUTE SERIES TOPOGRAPHIC NGVD: 1929 - DATE: 1995 Source: United States Geological Survey

NAME DATE DATE NAME REVISION APPROVED BY: USDA Soil Survey/USGS Topographic Map MC² PROJ. NO. SHEET NO. MC SQUARED, INC. 11/01/201 DESIGNED BY: TC LORID - ENGINEERING CERTIFIC-TE -UTHORIZ-TION No. 9191 MC^2 Geotechnical Consultants DRAWN BY KH 05/31/2018 Jeffery L. Hooks, P.E. FLORID- LICENSE No. 67882 5808-A Breckenridge Parkway Green Spine Cycle Track 15 CHECKED BY: JH 06/11/2018 T021705.031 Tampa, FL 33610 Hillsborough County, Florida Ph:813-623-3399 Fax:813-623-6636 SUPERVISED BY:







WT: 3.0ft. N 0 0 HA 10 HA $\overline{\sum}$ 5 28 26 6 NMC -200 WOH 50+/5" 10 10 DEPTH (FEE 15 15 6 NMC:34.2% -200:38.6% 20 20 LL:42 PL:17 PI:25 25 25 30 30

BORING NO.SPT-01

DATE 5/18/18

LEGEND:



(SC) Clayey Sand



Limestone



(SP-SM) Poorly Graded Sand With Silt

NOTES:

 $\stackrel{ riangle}{=}$ WATER TABLE

HA HAND AUGER

NMC NATURAL MOISTURE CONTENT (%)

-200 FINES PASSING A NO. 200 SIEVE (%)

LL LIQUID LIMIT

PL PLASTIC LIMIT

PI PLASTICITY INDEX

GRANULAR MATERIALS- RELATIVE DENSITY	SPT (BLOWS/FT)					
VERY LOOSE	≤ 4					
LOOSE	5-10					
MEDIUM	11-30					
DENSE	31-50					
VERY DENSE	GREATER THAN 50					
SILTS AND CLAYS CONSISTENCY	SPT (BLOWS/FT)					
VERY SOFT	≤ 2					
SOFT	3-4					
FIRM	5-8					
STIFF	9-15					
VERY STIFF	16-30					
HARD	30-50					
VERY HARD	GREATER THAN 50					
SPT Spoon Inside Diameter 1 3/8" ASTM 9	Standard Dron Safety Hammer					

SPT Spoon Inside Diameter 1 3/8" ASTM Standard Drop Safety Hamme SPT Spoon Outside Diameter 2" Average Hammer Drop Height 30" Hammer Weight 140 lbs

LEGEND:



Approximate SPT Location

DATE	NAME	REVISION	APPROVED BY:		MC SOLIARED INC			NAME	DATE	REPORT OF CORE BORING	MC ² PROJ. NO.	SHEET NO.
				2		FLORIDA ENGINEERING CERTIFICATE OF	DESIGNED BY:	TC	11/01/2017	THE OTT OF COTTE BOTTING		
				MC^2	Geotechnical Consultants 5808-A Breckenridge Parkway Tampa, FL 33610 Ph:813-623-3399 Fax:813-623-6636	AUTHORIZATION No. 9191 Jeffery L. Hooks, P.E. FLORIDA LICENSE No. 67882	DRAWN BY:	KH	05/31/2018	Green Spine Cycle Track	T021705.031	19
				2120			CHECKED BY:	JH	06/11/2018			
			Geotechnical • Environmen Materials Testing	GEOTECHNICAL • ENVIRONMENTAL MATERIALS TESTING			SUPERVISED BY:	WS		riiiisborougii Oourity, riorida		



MC2 REPORT 117.031 GREEN SPINE CYCLE.GPJ MC2.GDT 6/13/18

Soil Profile

BORING ID: C-01

,	MA	ICAL+ENVIRONMI TERIALS TESTING	NTAL										
CLIENT Kisinger Campo and Associates, Corp. PROJECT NUMBER T021705.031													
					PROJECT LOCATION _Tampa, Hillsborough County, Florida								
DA	TE S	TARTE	5/24/18	COMPLETED <u>5/24/18</u>	_ GROUND ELEVATION			HOLE	SIZE	4 inc	hes		
DRI	LLIN	IG CON	TRACTOR MC Squa	ared, Inc.	- '								
DRI	LLIN	IG MET	HOD Wet Rotary		$_{\perp}$ $^{ extstyle ar{ar{ar{ar{ar{ar{ar{ar{ar{ar{$	LLING	3.0 ft						
LO	GGE	D BY _S	S. Nason	CHECKED BY J. Hooks	AT END OF DRILLING								
NO.	TES	W. Ca	ss Street, EB Lane, 3	350-ft. East of N. Albany Avenue	_ AFTER DRILLING	G							
	G					Ш		%	€	 € SPT	N VAI	LUE €	 }
(#	GRAPHIC LOG	요 -				SAMPLE TYPE NUMBER	VE)	7	⊕ OR	GANIC	MC MC	ITENT	· % ⊕
DEPTH (ft)	울	AASHTO Symbol		MATERIAL DESCRIPTION		LE .	BLOW COUNTS (N VALUE)	NG N		PL	MC	ĻĻ	
DE	₽.	\$ \oldots				AMF	SCB			NESC	ONTE	=NT (°	
0.0	g					S'		2	2	0 4	0 6	0 8	0
			4.5 inches of AS	PHALT		1							
			3 inches of PAVI	ER		PC 1							
			4.5 inches of SH	ELL base		 							
	1		Dark brown, poo	rly-graded fine SAND to fine SAND	with silt								
				, ,									
						K							
						$ \lambda $							
2.5	-]}]							
		A-3				HA 2							
			$ \nabla$			$ \cdot $							
						KI I							
-						$ \lambda $							
			Borehole collaps	se at 4.5 feet									
			,	Bottom of hole at 4.5 feet.		И							
													ı
													ı



Soil Profile

	Mai	ERIALS TESTING										
CLIE	ENT	Kising	er Campo and Associates, Corp.	PROJECT NAME Gre	en Spir	ne Cycle Tr	ack					
PRC	JE	CT NUM	BER _T021705.031	PROJECT LOCATION	_Tamp	a, Hillsboro	ugh C	ounty,	Florid	<u>a</u>		
DAT	ES	TARTE	D _5/29/18	_ GROUND ELEVATION			HOLE	SIZE	4 inc	hes		
DRII	LLIN	IG CON	TRACTOR MC Squared, Inc.	_ GROUND WATER LEV	ELS:							
DRII	LLIN	IG METI	HOD Wet Rotary	_ AT TIME OF DRI	LLING	GNE						
LOG	GE	DBY S	S. Gomez CHECKED BY J. Hooks	_ AT END OF DRIL	LING _							
TON	ES	W. Ca	ss Street, Outside EB Lane, 350-ft. East of North Blvd.	_ AFTER DRILLING	G							
	ני				ш		%	(∋ SPT	N VAI	LUE €	
(#	GRAPHIC LOG	2등			SAMPLE TYPE NUMBER	ZE)	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\			C CON		
DEPTH (ft)	ЭĦ	AASHTO Symbol	MATERIAL DESCRIPTION		MBI	BLOW COUNTS (N VALUE)	RECOVERY (RQD)		PL	MC	ĻĻ	
DEF	RAF	A (S)			A S	S S B			NES (CONTE	ENIT /0	
0.0	ত				Ś		₩.	2	0 4		_ 1 V 1 (/	
			2.5 inches ASPHALT		1							
			2.75 inches of PAVER Poorly-graded fine SAND to fine SAND with silt		PC							
		A-3	Footiy-graded line SAND to line SAND with siit		1 1							
			Very dark gray, poorly-graded fine SAND with shell									
			Very dark gray, poorly-graded line SAND with shell		K							
		A-1-b										
_					$\ \ $							
<u>2.5</u> 												
			Dark to grayish brown, poorly-graded fine SAND to t with hard nodules	ine SAND with silt,								
		A-3			KI.							
			Auger refusal at 3.5 feet									
			Bottom of hole at 3.5 feet.		NII -							



Soil Profile

	Ma	TERIALS TESTING										
CLI	ENT	Kising	ger Campo and Associates, Corp.									
			IBER <u>T021705.031</u>	_ PROJECT LOCATION				_				
			D <u>5/24/18</u> COMPLETED <u>5/24/18</u>				HOLE	SIZE	4 inc	hes		
			TRACTOR MC Squared, Inc.									
			HOD Wet Rotary									
			S. Nason CHECKED BY J. Hooks									
NO.	TES	W. Ca	ass St., Paved Median, 190-ft. W. of W. Gasparilla Pl.	AFTER DRILLIN	IG		•					
	F0G				Щ	_	%		∋ SPT	N VAI	_UE €)
DEPTH (ft)		은 <u>등</u>			T.Y	BLOW COUNTS (N VALUE)		⊕ OR			ITENT	. % ⊕
ΞPΤ	표	AASHTO Symbol	MATERIAL DESCRIPTION		P.E.	BLO OUN	S S		PL ├──	MC	LL 	
当 0.0	GRAPHIC	₹ ″			SAMPLE TYPE NUMBER	_0 <u>Z</u>	RECOVERY (RQD)	□ FI	NES C	CONTE 0 60		
0.0			4.75 inches of ASPHALT		1							
			7.25 inches of LIMEROCK base		PC 1							
	_		Grayish brown, poorly-graded fine SAND to fine SA aggregate	ND with silt, Limerock	HA							
2.5		A-3			2							
			Auger refusal at 3.5 feet									
			Bottom of hole at 3.5 feet.									



Soil Profile

-	GEOTECHN	ICAL+ENVIRONME TERIALS TESTING	NTAL									
CLI	ENT	Kising	er Campo and Associates, Corp.	PROJECT NAME Gre	en Spin	e Cycle Tr	ack					
PR	OJE	CT NUM	BER _T021705.031	PROJECT LOCATION	Tampa	a, Hillsboro	ugh C	ounty,	Florid	a		
			COMPLETED 5/29/18				HOLE	SIZE	4 inc	hes		
DR	ILLIN	IG CON	TRACTOR MC Squared, Inc.									
			HOD Wet Rotary									
			S. Nason CHECKED BY J. Hooks									
NO	TES	Nuccio	o Parkway, Outside NB Lane, 590-ft. N. of N. Nebraska A	venue AFTER DRILLING	G							
S DEPTH (ft)	GRAPHIC LOG	AASHTO Symbol	MATERIAL DESCRIPTION		SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	RECOVERY % (RQD)	⊕ OR	PL	MC	ITENT LL LL ENT (%	- % ⊕ %) □
<u></u>			4 inches of ASPHALT 10 inches of LIMEROCK base		PC 1			_				
2.5		A-3	Dark gray to very pale brown, poorly-graded fine SA silt	ND to fine SAND with	HA							
5.0	-		abla		2							
			Bottom of hole at 5.0 feet.									



Soil Profile

	Ma	ERIALS TESTING										
CLI	ENT	Kising	ger Campo and Associates, Corp.	PROJECT NAME Gree	n Spin	e Cycle Tra	ack					
			BER _T021705.031	PROJECT LOCATION _				-				
DA.	TE S	TARTE	D <u>5/31/18</u> COMPLETED <u>5/31/18</u>	GROUND ELEVATION _			HOLE	SIZE	4 incl	nes		
DR	ILLIN	IG CON	TRACTOR MC Squared, Inc.									
			HOD Wet Rotary									
			S. Nason CHECKED BY J. Hooks									
NO	TES	Nuccio	D Pkwy, Outside NB Lane, 90-ft. North of E. 6th Avenue	AFTER DRILLING								
	ပ္ထ				щ		%	€	SPT	N VAL	.UE €)
DEPTH (ft)	5075	70 10			SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)		⊕ OR	GANIC	CON	TENT	′%⊕
PŢ	불	AASHTO Symbol	MATERIAL DESCRIPTION		JAB	SLO SUN VAL	OVE RQI	ı	PL ├──	MC	LL —	
DE	GRAPHIC	∢տ			MA N	ωö∠	RECI	☐ FII	-	ONTE		6) 🗆
0.0					o,		Ъ.) 4(<u>)</u>	,
			3.5 inches of ASPHALT		[
			8.5 inches of LIMEROCK base		PC 1							
				;								
			Pale brown, dark gray to grayish brown, poorly-grade	d fine SAND to fine								
			SAND with silt		il I							
				{								
				{	<u>/</u>							
2.5	-				}							
					 HA							
		A-3		\\	2							
				{								
				Į								
	-				}							
					}							
					il I							
5.0				{								
			Bottom of hole at 5.0 feet.									



Soil Profile

	GEOTECHN MA	ICAL+ENVIRONMI TERIALS TESTING	VTAL										
CLI	ENT	Kising	er Campo and Associates, C	orp.	PROJECT NAME Gre	en Spin	e Cycle Tra	ack					
PR	OJE	CT NUM	BER _T021705.031		PROJECT LOCATION	Tampa	a, Hillsboro	ugh C	ounty,	Florid	a		
DA	TE S	TARTE	<u>5/31/18</u> COMI	PLETED <u>5/31/18</u>	GROUND ELEVATION			HOLE	SIZE	4 inc	hes		
DRI	LLIN	IG CON	TRACTOR MC Squared, Inc).	GROUND WATER LEV	ELS:							
DRI	LLIN	IG MET	HOD Wet Rotary		AT TIME OF DRI	LLING	GNE						
LO	GGE	DBY S	S. Nason CHEC	CKED BY J. Hooks	AT END OF DRIL	LING _							
NO.	TES	Nuccio	Pkwy, Outside NB Lane, 90-	-ft. South of E. 9th Avenue	AFTER DRILLING	G							
	ניו					Ш		%	€	€ SPT	N VA	LUE €	•
$\widehat{\mathbb{H}}$	90 ₁	요 등				SAMPLE TYPE NUMBER	ZS JE)	, , ,					
DEPTH (ft)	GRAPHIC	AASHTO Symbol	MA	TERIAL DESCRIPTION		LE -	BLOW COUNTS (N VALUE)	SEE CO	⊕ OR	PL	MC	LL	
DEF	₹	\$ છ				MP	S C B	N =		NES (CONT	ENIT (0	
0.0	ਹ					/S		₩.	2	0 4	0 6	0 8	₀, ⊔ 0
			2.75 inches of ASPHALT			1							
			9.25 inches of LIMEROC	CK base		PC							
	1		Dark brown, poorly-grade	ed fine SAND to fine SAND v	vith silt. with clav								
			nodules		•	KU							
						K							
						$ \lambda $							
2.5	1												
	1	A-3				HA 2							
						KI I							
_													
			Small brick fragment										
	1		Ç										
5.0						K							
0.0			E	Bottom of hole at 5.0 feet.									



Soil Profile

	Ma	TERIALS TESTING											
CLI	ENT	Kising	er Campo and Associates	, Corp.	PROJECT NAME Gre	en Spin	e Cycle Tra	ack					
					PROJECT LOCATION								
				DMPLETED <u>5/31/18</u>				HOLE	SIZE	4 inc	hes		
				Inc.									
				HECKED BY J. Hooks									
NO	TES	Nucci	Pkwy, Outside NB Lane,	350-ft. South of E. 12th Avenue	e AFTER DRILLING	G		ı					
_	106					Ж	_	%	€	∋ SPT	N VA	LUE €	€
DEPTH (ft)		오ᅙ				돗띘	BLOW COUNTS (N VALUE)	품()	⊕ OR	GANIC	CON	ITENT	- % ⊕
Ή	분	AASHTO Symbol		MATERIAL DESCRIPTION		Ш	SIC OUN VAL	N S		PL ├──	MC	ᄔ	
	GRAPHIC	₹ 00				SAMPLE TYPE NUMBER	os_	RECOVERY (RQD)		NES C	CONTE	ENT (9	
0.0			3.75 inches of ASPHA	ALT		1				0 4	0 6	8 0	U
			11 inches of LIMERO	CK base		1							
						PC 1							
			Doubte average by by	double brown and only are along the	CAND to fine	<u> </u>							
	-		SAND with silt	, dark brown, poorly-graded fine	e SAND to line	KI							
	1					$ \lambda $							
2.5													
						$\ \cdot\ _{HA}$							
		A-3				2							
	1												
						$ \lambda $							
	-												
						{							
5.0				Bottom of hole at 5.0 feet.									
	1	i	į.			1		i					



Soil Profile

	MA	ICAL+ENVIRONME TERIALS TESTING	NTAL										
CLI	ENT	Kising	er Campo and As	ssociates, Corp.	PROJECT NAME Gre	en Spir	ne Cycle Tr	ack					
PR	OJE	CT NUM	BER _T021705.03	31	PROJECT LOCATION	Tamp	a, Hillsboro	ugh C	ounty,	Florid	a		
DA	TE S	TARTE	6/1/18	COMPLETED 6/1/18	_ GROUND ELEVATION			HOLE	SIZE	4 inc	hes		
DRI	LLIN	IG CON	TRACTOR MCS	Squared, Inc.	_ GROUND WATER LEV	ELS:							
DRI	LLIN	IG METI	HOD Wet Rotary	1	_ AT TIME OF DRI	LLING	GNE						
LO	GGE	DBY S	S. Nason	CHECKED BY J. Hooks	_ AT END OF DRII	LING							
NO.	TES	Nuccio	Pkwy, Outside N	IB Lane, 20-ft. South of N. 15th St. Me	ger AFTER DRILLIN	G							
	ני					ш		%	(——— ∋ SPT	N VA	LUE €	 }
(#	LOG	0 5				문	ZE GE	° ≿ (⊕ OR	GANI	C CON	ITENT	- - % ⊕
DEPTH (ft)	呈	AASHTO Symbol		MATERIAL DESCRIPTION		LE -	A LO	S S S S S		PL	MC	ĻĻ	
DEF	GRAPHIC	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\				SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)			NES (CONT	LL LL ENT (%	
0.0						S)		2	2	0 4	0 6	0 8	0
			3 inches of A										
			11 inches of	LIMEROCK base		PC							
						 [1							
	1					1							
			Brown to pale	e brown, poorly-graded fine SAND to fi	ne SAND with silt								
		A-3				{ HA							
2.5	1	/ / /				2							
						$ \lambda $							
			Auger Refusa										
				Bottom of hole at 3.5 feet.									



Soil Profile

G	EOTECHN MA	ICAL+ENVIRONMI ERIALS TESTING	INTAL									
CLI	ENT	Kising	er Campo and Associates, Corp.	PROJECT NAME Gree	n Spin	e Cycle Tra	ack					
PRO)JE	CT NUM	BER _T021705.031	PROJECT LOCATION _	Tampa	a, Hillsboro	ugh C	ounty,	Florida	<u>a</u>		
DAT	E S	TARTE	O 6/1/18 COMPLETED 6/1/18	GROUND ELEVATION			HOLE	SIZE	4 incl	nes		
DRI	LLIN	IG CON	TRACTOR MC Squared, Inc.	GROUND WATER LEVE	LS:							
DRI	LLIN	IG METI	HOD Wet Rotary	AT TIME OF DRIL	LING	GNE						
LOC	GE	DBY _S	S. Nason CHECKED BY J. Hooks	AT END OF DRILL	LING _							
NO	ΓES	N. 15tl	h Street, Outside NB Lane, 50-ft. South of E. 15th Ave	enue AFTER DRILLING	i							
	ני)				ш		%	e	SPT	N VAI	LUE €	•
Œ	P00	0 -			SAMPLE TYPE NUMBER	ZS (E)	, , ,					
DЕРТН (ft)	GRAPHIC	AASHTO Symbol	MATERIAL DESCRIPTION		LE -	BLOW COUNTS (N VALUE)	SE SE	⊕ ORG	PL	MC	LĻL	
DEF	₹	A (S			M N	S C B	N.E.		JES C	ONITE	NIT /0	/\
0.0	9				<i>/</i> S		쮼	20	NES (0 60	1N 1 (7 0 8	%) ⊔ 0
0.0			3.5 inches of ASPHALT		PC							
			3.5 inches of PAVER		1 1							
			Dark gray, grayish brown to light brownish gray, v brown, poorly-graded fine SAND to fine SAND wi	ery pale brown to	$\overline{\mathbb{N}}$							
			brown, poorly-graded line SAND to line SAND wi	in Siit]}							
				(
				(
_				(KI 1							
					 							
2.5]}					\longrightarrow		
		A-3		(HA 2							
				({ [*]							
				(KI I							
]}							
				· ·]							
				($\left(\left\Vert \cdot \right\Vert \right)$							
- 0				·	KI							
5.0			Bottom of hole at 5.0 feet									



Soil Profile

1	GEOTECHN	ICAL+ENVIRONMI TERIALS TESTING	INTAL:									
CLI	ENT	Kising	ger Campo and Associates, Corp.	PROJECT NAME Gre	een Spir	ne Cycle Tr	ack					
PR	OJE	CT NUM	IBER _T021705.031	PROJECT LOCATION	Tamp	a, Hillsboro	ugh C	ounty,	Florida	a		
DA	TE S	TARTE	D 6/1/18 COMPLETED 6/1/18									
DR	LLIN	IG CON	TRACTOR MC Squared, Inc.	GROUND WATER LEV	/ELS:							
DR	LLIN	IG MET	HOD Wet Rotary	AT TIME OF DR	ILLING	GNE						
			S. Nason CHECKED BY J. Hooks									
NO	TES	N. 15t	h Street, NB Lane, 40-ft. South of 18th Avenue	AFTER DRILLIN	G							
	ניו				ш		%	€	SPT	N VAI	_UE €	•
$\widehat{\mathbb{H}}$	GRAPHIC LOG	2-5			SAMPLE TYPE NUMBER	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	 ≿	⊕ OR(GANIC	CON	ITENT	- % ⊕
DEPTH (ft)	을	AASHTO Symbol	MATERIAL DESCRIPTION	N	LE .	BLOW COUNTS (N VALUE)	SEF	⊕ ORG	P <u>L</u>	MC	LL	
DEF	₹	\$ 60°			M N S	S _{OB}			IES C	ONTE	NIT (0	
0.0					S		≅	20) 4) 6	. IVI (7	o, ⊔ 0
			6 inches of ASPHALT		PC							
	1				1							
			Dark to pinkish gray, dark grayish to light yellow fine SAND to fine SAND with silt with rock fragm	isn brown, poorly-graded ients	K							
	1											
	1											
					K							
					K							
2.5	1	A-3			<u> </u>							
					HA 2							
	1											
					K							
	1											
	+		Pinkish gray, silty, clayey fine SAND		-							
5.0		A-2-6						*				
5.0			Bottom of hole at 5.0 fee	et.	ТИТ							



Soil Profile

dio	MATERIALS TE	STING												
CLIE	NT Kis	singer Ca	ampo and Ass	sociates, Corp.		PROJECT NAME Gre	en Spin	e Cycle Tra	ack					
PROJ	IECT N	UMBER	T021705.03	1		PROJECT LOCATION	Tampa	a, Hillsboro	ugh C	ounty,	Florid	a		
DATE	STAR	TED _5/	24/18	COMPLETED _5/24	4/18	GROUND ELEVATION			HOLE	SIZE	4 inc	hes		
DRILI	LING C	ONTRA	CTOR MC Sc	quared, Inc.		GROUND WATER LEV								
			Hand Auger				LLING	4.0 ft						
LOGO	SED BY	S. Na	ison	CHECKED BY _J.	Hooks	AT END OF DRIL	LING _							
NOTE	S <u>SE</u>	Corner	of W. Cass St	and N. Albany Ave.		AFTER DRILLING	G							
(. J						ш		%	[€	∍SPT	N VA	LUE €	
	9	<u>_</u>					SAMPLE TYPE NUMBER	V JE)	7	⊕ OR	GANI	CON	ITENT	- % ⊕
DEPTH (ft)	AASHTO	gu		MATERIAL DES	CRIPTION		MBI MBI	BLOW COUNTS (N VALUE)	RECOVERY (RQD)		PL	MC	ĻĻ	
	<u></u> } ₹ '	છ.					A S	S C B			NES (ONTE	—— <u> </u> =NIT (0	
0.0	ت ت						S		22	2	0 4		0 8	
2.5	A-		Gray to very di	ark gray, poorly-graded f	ine SAND to fi	ne SAND with silt,	HA							
5.0				Bottom of hole	at 5.0 feet.									



Soil Profile

		TERIALS TESTING												
						_ PROJECT NAME _Gr								
			BER _T021705			_ PROJECT LOCATION								
					ED 5/24/18	_			HOLE	SIZE	4 inc	hes		
- 1														
- 1			HOD Hand Au			_								
					BY J. Hooks									
NO	TES	NE co	rner of W. Cass	s St. and N. Fremon	t Ave.	_ AFTER DRILLIN	IG							
	၂ဗ္						ᆔ	_	%	€	∋ SPT	N VAI	_UE €)
DEPTH (ft)	GRAPHIC LOG	오호					SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	RECOVERY (RQD)			C CON		- % ∈
<u>†</u>	불	AASHTO Symbol		MATERIA	AL DESCRIPTION		PLE JMB	SIC SUL VAL	OVE RQI		PL —	MC	LL —	
	3RA	₹ 00					NAW N	_ ZOZ	ZEC (□FI	NES (CONTE		6) 🗆
0.0			Dank to :	n, dorl, see,	aradad fire CAND (fine CAND with -!!!	10		_			0 60		
			Dark to ver	ry dark gray, poorly-(graded fine SAND to	TIME SAND WITH SIIT	K							
-	-						$ \mathcal{Y} $							
-	1													
		A-3					K							
ļ	-						Y							
							}}							
2.5	-													
							K							
L .														
			Black, poo	orly-graded fine SANI	D with silt and some	organics								
-	-	A-3	$\bar{\Delta}$											A
			Borehole o	collapse at 4.5 feet			$\ \ $							
			Doletiole (n of hole at 4.5 feet.		И							
13/18														
DT 6,														
C2.G														
E M														
LE.GF														
CYC														
PINE														
S EN S														
GRE														
MC2 REPORT 117.031 GREEN SPINE CYCLE.GPJ MC2.GDT 6/13/18														
14.														
POR														
2 RE														
MC														



Soil Profile

Č	GEOTECHN MAI	ICAL+ENVIRONMI TERIALS TESTING	ENTAL:									
CLI	ENT	Kising	ger Campo and Associates, Corp.	PROJECT NAME Gre	een Spir	ne Cycle Tr	ack					
PRO	OJE	CT NUM	BER _T021705.031	PROJECT LOCATION	Tamp	a, Hillsboro	ugh C	ounty,	Florid	<u>a</u>		
			D 5/29/18 COMPLETED 5/29/18				HOLE	SIZE	4 inc	hes		
DRI	LLIN	IG CON	TRACTOR MC Squared, Inc.									
			HOD Hand Auger									
LO	GGE	D BY _S	S. Nason CHECKED BY J. Hooks	AT END OF DRI	LLING _							
NO.	TES	East s	side of Nuccio Pkwy. and East of N. Nebraska Ave.	AFTER DRILLIN	IG							
	စ္ခ				Щ		%		∋ SPT	N VA	LUE €	€
DEPTH (ft)	5 LOG	으호			SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	RECOVERY (RQD)	⊕ OR	GANIC	CON	ITENT	- % ⊕
ËΡΤ	GRAPHIC	AASHTO Symbol	MATERIAL DESCRIPTIO	N	PLE	SEO VAL	RS E		PL —	MC	LL	
DE	3RA	₹ "			NAW NAW	_os	ZEC.	□FI	NES C			%) 🗆
0.0			Light to dark gray, dark to light grayish brown, p	poorly graded fine SAND	1131		_	2	0 4	0 6	8 0	0
			to fine SAND with silt	oony-graded line SAND	K							
	1											
-												
	1				K							
2.5												
		A-3			HA							
					$ \mathcal{U} $							
5.0			Bottom of hole at 5.0 fe	et.	<u> </u>							



Soil Profile

Ġ	GEOTECHN MAT	ICAL • ENVIRONM TERIALS TESTING	NTAL										
CLIENT Kisinger Campo and Associates, Corp.				PROJECT NAME Gre	een Spir	ne Cycle Tr	ack						
PROJECT NUMBER T021705.031			PROJECT LOCATION _Tampa, Hillsborough County, Florida										
DATE STARTED 5/29/18 COMPLETED 5/29/18													
DRI	LLIN	IG CON	TRACTOR MC Squ	uared, Inc.	GROUND WATER LEV	/ELS:							
DRI	LLIN	IG MET	HOD Hand Auger		AT TIME OF DR	ILLING	GNE						
LO	GGE	DBY _	S. Nason	CHECKED BY J. Hooks	AT END OF DRI	LLING							
NO.	TES	SE co	rner of E. 3rd Ave. a	nd Nuccio Pkwy	AFTER DRILLIN	IG							
	ניז					111		%	[€	⇒ SPT	N VA	I UF €	
(£	P00	0 5				F H	\SE(i)	, ₹					
DEPTH (ft)	GRAPHIC	AASHTO Symbol		MATERIAL DESCRIPTION		LE	AL SO	RECOVERY (RQD)		PL	МС	LL	
DEF	₹	₹ S		SAMPLE TYPE NUMBER NUMBER COUNTS (N VALUE)	N F		NEC (CONT		/\			
0.0						<i>\S</i>		2	2		CONTE 0 6	0 8	
				gray, light to very dark gray, poorl	y-graded fine SAND to	$ \lambda $							
			fine SAND with	SIII									
						K							
	1					$ \mathcal{U} $							
						$ \lambda $							
	1												
						$\ \ $							
2.5						X							
		A-3				HA							
						K							
	-					KI							
						$ \lambda $							
	1												
5.0						K							
				Bottom of hole at 5.0 fee	t.								
								1					



Soil Profile

	MAI	ERIALS TESTING													
CLI	ENT	Kising	er Campo an	d Associa	ates, Corp.		PROJECT NAME G	reen Spi	ne Cycle Tr	ack					
PR	OJE	CT NUM	BER _T0217	<u> </u>			PROJECT LOCATIO	N Tamp	a, Hillsbord	ugh C	ounty,	Florid	a		
DA	TE S	TARTE	6/1/18		COMPLETED	6/1/18	_ GROUND ELEVATIO	N		HOLE	SIZE	4 inc	hes		
DRI	LLIN	IG CON	TRACTOR _N	/IC Squar	red, Inc.		_ GROUND WATER LE	VELS:							
DRI	ILLIN	IG METI	HOD Hand A	luger			_ AT TIME OF D	RILLING	GNE						
LO	GGE	D BY _S	S. Nason		CHECKED BY	J. Hooks	_ AT END OF DE	RILLING							
NO.	TES	East S	ide of 15th S	t., N of 17	7th Ave.		_ AFTER DRILLI	NG							
	C							ш		%	(€ SPT	N VA	LUE €	
$(\!$	907 1	요 등						SAMPLE TYPE NUMBER	ZE (E)	\ <u>\</u>	⊕ OR	GANI	CON	ITENT	- % ⊕
DEPTH (ft)	GRAPHIC	AASHTO Symbol			MATERIAL	DESCRIPTION		MBE	BLOW COUNTS (N VALUE)	RECOVERY (RQD)		PL	MC	LĻL	
	₹	& ⊗				SCB			NES (CONT		/ \ □			
0.0								8		2	2	NES (0 4		= N 1 (3 0 8	
2.5		A-3	with silt			poorly-graded fine	SAND to fine SAND	HA							
		A-2-4	Pinkish g	ray, siity	fine SAND										
5.0		A-2-4		Tay, Sity		f hole at 5.0 feet.									

MC ²
GEOTECHNICAL • ENVIRONMENTAL

Soil Profile

BORING ID: SPT-01

GEOTECHNICAL • ENVIRONM MATERIALS TESTING	NTAL:					
CLIENT Kising	ger Campo and Associates, Corp.	OJECT NAME Green Spir	ne Cycle Tra	ack		
PROJECT NUM	BER	OJECT LOCATION Tampa	a, Hillsboro	ugh Co	ounty, Florid	a
DATE STARTE	D _5/18/18	OUND ELEVATION		HOLE	SIZE 4 inc	hes
DRILLING CON	TRACTOR MC Squared, Inc. GF	OUND WATER LEVELS:				
DRILLING MET	HOD Wet Rotary	$\overline{igspace}$ at time of drilling	3.0 ft			
LOGGED BY _	3. Crowson CHECKED BY J. Hooks	AT END OF DRILLING				
NOTES West	of N. Howard Ave. and W. Cass St.	AFTER DRILLING				
O -		Ш		%	⊕SPT	N VALUE ⊖
DEPTH (ft) GRAPHIC LOG USCS Group Symbol		SAMPLE TYPE NUMBER	ZE)	2	⊕ ORGANIO	CONTENT %
DEPTH (ft) RAPHIC LC SSCS Group Symbol	MATERIAL DESCRIPTION	LE.	BLOW COUNTS (N VALUE)	RECOVERY (RQD)	PL	MC LL
PEI RAF		AMP	m S Z			CONTENT (%)
0 0 5				2		0 60 80
	Loose to medium dense, gray to dark gray, brown to dark poorly-graded fine SAND with silt	brown,				
1 111	poonly graded line of the with one					
		\				
	∇	{ '				
7.111	*					
SP-SM						
5					⊕	
		2	(10)			
-			5-5-6-5 (11)			
		$//\sqrt{3}$	(11)			
	Loose to medium dense, gray, clayey fine SAND					
			7-10-18-10 (28)		😝	
			(- /			
		SS 5	8-12-14		 	
		/\ 5	(26)			
					/ /	
sc						
-//						
		\				
			4-4-2		6 1 A	.
<u>o</u>		6	(6)			
		h A				
-{//		SS 7	0-0-0		9 <≤	
5	Weight of Hammer (23.5'-25')	/\ 7	(0)			



Soil Profile

BORING ID: SPT-01

		CAL+ENVIRONME ERIALS TESTING	NTAL								
CLI	ENT	Kising	er Campo and Associates, Corp.	PROJECT NAME Green Spine Cycle Track							
	PROJECT NUMBER T021705.031				Tampa, Hillsborough County, Florida						
25 DEPTH (ft)	GRAPHIC LOG	USCS Group Symbol	MATERIAL DESCRIPTION		SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	RECOVERY % (RQD)	⊕ OF	PL INES (C CON	LUE
		LS	Competent LIMESTONE		SS 8	14-50/5"					7
MCZ REPORT 117.031 GREEN SPINE CTCLE.GPJ MCZ.GD1 6/13/18			Bottom of hole at 26.0 feet.								

5808-A Breckenridge Parkway Tampa, FL 33610

OFFICE: (813) 623-3399 FAX: (813) 623-6636



DOUBLE-RING INFILTROMETER TEST

Project: Green Spine Cycle Track **Location:** SE corner of Cass & Albany **Project No.:** T021705.031 **Surface Description:** Fine Sands (SP, SP-SM)

Client: Kisinger Campo & Assoc.

Performed By: DG

Date/Time: 6/5/18 @ 11:00 am


Test Depth: 1.5-ft. bgs
Ring Size: 12", 24"

Constant Head: 4"

Test No.: DRI-01

INNER RING FIELD TEST DATA

ELAPSED TIME (minutes)	QUANTITY H_20 (mL)	INFILTRATION RATE (in/hr)
15	4000	8.63
30	4400	9.49
45	4100	8.85
60	4450	9.60
90	8300	8.96
120	8500	9.17
180	17800	9.60
240	16550	8.93



Comments: Water Table at 4' bgs at time of test.

5808-A Breckenridge Parkway Tampa, FL 33610

OFFICE: (813) 623-3399 FAX: (813) 623-6636



DOUBLE-RING INFILTROMETER TEST

Project: Green Spine Cycle Track **Location:** NE corner of Cass & Fremont **Project No.:** T021705.031 **Surface Description:** Fine Sands (SP, SP-SM)

Client: Kisinger Campo & Assoc.

Test Depth: 1.5-ft. bgs
Performed By: DG


Ring Size: 12", 24"

Date/Time: 6/6/18 @ 9:15 am **Constant Head:** 4"

Test No.: DRI-02

INNER RING FIELD TEST DATA

		-
ELAPSED TIME (minutes)	QUANTITY H ₂ 0 (mL)	INFILTRATION RATE (in/hr)
(minates)	(****)	` ' '
15	2050	4.42
30	2200	4.75
45	1950	4.21
60	1650	3.56
90	3650	3.94
120	3550	3.83
180	7600	4.10
240	7150	3.86



Comments: Water Table at 4' bgs at time of test.

5808-A Breckenridge Parkway Tampa, FL 33610

OFFICE: (813) 623-3399 FAX: (813) 623-6636



DOUBLE-RING INFILTROMETER TEST

Project: Green Spine Cycle Track **Location:** NE corner of Cass & Rome **Project No.:** T021705.031 **Surface Description:** Fine Sands (SP, SP-SM)

Client: Kisinger Campo & Assoc.

Performed By: SG

Date/Time: 6/6/18 @ 10:30 am


Test Depth: 1.5-ft. bgs
Ring Size: 12", 24"

Constant Head: 4"

Test No.: DRI-03

INNER RING FIELD TEST DATA

ELAPSED TIME (minutes)	QUANTITY H_20 (mL)	INFILTRATION RATE (in/hr)
15	2500	5.39
30	2500	5.39
45	2500	5.39
60	2500	5.39
90	5000	5.39
120	5500	5.93
180	11000	5.93
240	10000	5.39



Comments: Water Table at 4' bgs at time of test.

5808-A Breckenridge Parkway Tampa, FL 33610

OFFICE: (813) 623-3399 FAX: (813) 623-6636



DOUBLE-RING INFILTROMETER TEST

Project: Green Spine Cycle Track **Location:** S corner of 3rd & Nuccio **Project No.:** T021705.031 **Surface Description:** Fine Sands (SP, SP-SM)

Client: Kisinger Campo & Assoc.

Performed By: DG

Date/Time: 6/7/18 @ 9:15 am


Test Depth: 1.5-ft. bgs
Ring Size: 12", 24"

Constant Head: 4"

Test No.: DRI-04

INNER RING FIELD TEST DATA

ELAPSED TIME (minutes)	QUANTITY H ₂ 0 (mL)	INFILTRATION RATE (in/hr)
15	3700	7.98
30	3100	6.69
45	3350	7.23
60	3350	7.23
90	7600	8.20
120	7750	8.36
180	16300	8.79
240	15900	8.58



Comments: Water Table greater than 5' bgs at time of test.

5808-A Breckenridge Parkway Tampa, FL 33610

OFFICE: (813) 623-3399 FAX: (813) 623-6636



DOUBLE-RING INFILTROMETER TEST

Project: Green Spine Cycle Track **Location:** E of 15th St., N of 17th Ave. **Project No.:** T021705.031 **Surface Description:** Fine Sands (SP, SP-SM)

Client: Kisinger Campo & Assoc.

Performed By: SG

Date/Time: 6/7/18 @ 11:00 am


Test Depth: 1.5-ft. bgs
Ring Size: 12", 24"

Constant Head: 4"

Test No.: DRI-05

INNER RING FIELD TEST DATA

ELAPSED TIME (minutes)	QUANTITY H ₂ 0 (mL)	INFILTRATION RATE (in/hr)
15	3500	7.55
30	4500	9.71
45	4000	8.63
60	4000	8.63
90	8500	9.17
120	8000	8.63
180	18000	9.71
240	19500	10.52



Comments: Water Table greater than 5' bgs at time of test. Moist clayey Sands at 5' bgs

TEST PROCEDURES

The general field procedures employed by MC Squared, Inc. (MC²) are summarized in the American Society for Testing and Materials (ASTM) Standard D420 which is entitled "Investigating and Sampling Soil and Rock". This recommended practice lists recognized methods for determining soil and rock distribution and groundwater conditions. These methods include geophysical and in-situ methods as well as boring.

Standard Drilling Techniques

To obtain subsurface samples, boring are drilled using one of several alternate techniques depending upon the subsurface conditions. Some of these techniques are:

In Soils:

- a) Continuous hollow stem augers.
- b) Rotary boring using roller cone bits or drag bits, and water or drilling mud to flush the hole.
- c) "Hand" augers.

In Rock:

- a) Core drilling with diamond-faced, double or triple tube core barrels.
- b) Core boring with roller cone bits.

<u>Hollow Stem Augering:</u> A hollow stem auger consists of a hollow steel tube with a continuous exterior spiral flange termed a flight. The auger is turned into the ground, returning the cuttings along the flights. The hollow center permits a variety of sampling and testing tools to be used without removing the auger.

<u>Mud Rotary:</u> In situations where unconsolidated materials are anticipated, the direct-rotary or "mud" rotary method may be used as a more effective method for obtaining soil samples. The fluid used, which is typically stored in an aluminum tub (also known as a "mudtub"), is a mix of water and bentonite, also known as a bentonite slurry or "mud". This fluid circulates into the borehole and then returns to the mudtub using a pump system. A loss of circulation, partially or otherwise, may signify a void at that sample depth. The key advantage of using this drilling method is that it stabilizes the borehole wall while drilling in unconsolidated formations, due to the buildup of a filter cake on the wall.

<u>Core Drilling</u>: Soil drilling methods are not normally capable of penetrating through hard cemented soil, weathered rock, coarse gravel or boulders, thin rock seams, or the upper surface of sound, continuous rock. Material which cannot be penetrated by auger or rotary soil-drilling methods at a reasonable rate is designated as "refusal material". Core drilling procedures are required to penetrate and sample refusal materials.

Prior to coring, casing may be set in the drilled hole through the overburden soils, to keep the hole from caving and to prevent excessive water loss. The refusal materials are then cored according to ASTM D-2113 using a diamond-studded bit fastened to the end of a hollow, double or triple tube core barrel. This device is rotated at high speeds, and the cuttings are brought to the surface by circulating water. Core samples of the material penetrated are protected and retained in the swivel-mounted inner tube. Upon completion of each drill run, the core barrel is brought to the surface, the core recovery is measured, and the core is placed, in sequence, in boxes for storage and transported to our laboratory.

Sampling and Testing in Boreholes

Several techniques are used to obtain samples and data in soils in the field; however the most common methods in this area are:

- a) Standard Penetrating Testing
- b) Undisturbed Sampling
- c) Dynamic Cone Penetrometer Testing
- d) Water Level Readings

The procedures utilized for this project are presented below.

Standard Penetration Testing: At regular intervals, the drilling tools are removed and soil samples obtained with a standard 2-inch diameter split tube sampler connected to an A or N-size rod. The sampler is first seated 6 inches to penetrate any loose cuttings, and then driven an additional 12 inches with blows of a 140-pound safety hammer falling 30 inches. Generally, the number of hammer blows required to drive the sampler the final 12 inches is designated the "penetration resistance" or "N" value, in blows per foot (bpf). The split barrel sampler is designed to retain the soil penetrated, so that it may be returned to the surface for observation. Representative portions of the soil samples obtained from each split barrel sample are placed in jars, sealed and transported to our laboratory.

The standard penetration test, when properly evaluated, provides an indication of the soil strength and compressibility. The tests are conducted according to ASTM Standard D1586. The depths and N-values of standard penetration tests are shown on the Boring Logs. Split barrel samples are suitable for visual observation and classification tests but are not sufficiently intact for quantitative laboratory testing.

<u>Water Level Readings:</u> Water level readings are normally taken in the boring and are recorded on the Boring Records. In sandy soils, these readings indicate the approximate location of the hydrostatic water level at the time of our field exploration. In clayey soils, the rate of water seepage into the boring is low and it is generally not possible to establish the location of the hydrostatic water level through short-term water level readings. Also, fluctuation in the water level should be expected with variations in precipitation, surface run-off, evaporation, and other factors. For long-term monitoring of water levels, it is necessary to install piezometers.

The water levels reported on the Boring Logs are determined by field crews immediately after the drilling tools are removed, and several hours after the boring are completed, if possible. The time lag is intended to permit stabilization of the groundwater level that may have been disrupted by the drilling operation.

Occasionally the boring will cave-in, preventing water level readings from being obtained or trapping drilling water above the cave-in zone.

BORING LOGS

The subsurface conditions encountered during drilling are reported on a field boring log prepared by the Driller. The log contains information concerning the boring method, samples attempted and recovered, indications of the presence of coarse gravel, cobbles, etc., and observations of groundwater. It also contains the driller's interpretation of the soil conditions between samples. Therefore, these boring records contain both factual and interpretive information. The field boring records are kept on file in our office.

After the drilling is completed a geotechnical professional classifies the soil samples and prepares the final Boring Logs, which are the basis for our evaluations and recommendations.

SOIL CLASSIFICATION

Soil classifications provide a general guide to the engineering properties of various soil types and enable the engineer to apply his past experience to current problems. In our investigations, samples obtained during drilling operations are examined in our laboratory and visually classified by an engineer. The soils are classified according to consistency (based on number of blows from standard penetration tests), color and texture. These classification descriptions are included on our Boring Logs.

The classification system discussed above is primarily qualitative and for detailed soil classification two laboratory tests are necessary; grain size tests and plasticity tests. Using these test results the soil can be classified according to the AASHTO or Unified Classification Systems (ASTM D-2487). Each of these classification systems and the in-place physical soil properties provides an index for estimating the soil's behavior. The soil classification and physical properties are presented in this report.

The following table presents criteria that are typically utilized in the classification and description of soil and rock samples for preparation of the Boring Logs.

Relative Density From Standard Pe	of Cohesionless Soils netration Test	Consistency of Cohesive Soils				
Very Loose	≤ 4 bpf	Very Soft	≤ 2 bpf			
Loose	5 - 10 bpf	Soft	3 - 4 bpf			
Medium Dense	11 - 30 bpf	Firm	5 - 8 bpf			
Dense	31 - 50 bpf	Stiff	9 - 15 bpf			
Very Dense	> 50 bpf	Very Stiff	16 - 30 bpf			
		Hard	30 – 50 bpf			
(bpf= blows	s per foot, ASTM D 1586)	Very Hard	> 50 bpf			
Relative Hardn	ess of Rock	Particle Size Ident	ification			
Very Soft	Very soft rock disintegrates or easily compresses to touch; can be hard	Boulders	Larger than 12"			
	to very hard soil.	Cobbles	3" - 12"			
Soft	May be broken with fingers.	Gravel Coarse	3/4" - 3"			
Moderately Soft	May be scratched with a nail, corners and edges may be	Fine	4.76mm - 3/4"			
	broken with fingers.	Sand Coarse	2.0 - 4.76 mm			
Moderately Hard	Light blow of hammer required	Medium	0.42 - 2.00 mm			
	to break samples.	Fine	0.42 - 0.074 mm			
Hard	Hard blow of hammer required to break sample.	Fines (Silt or Clay)	Smaller than 0.074 mm			
Rock Continuit	·					
NOCK COILLIIUIL	<u> </u>	Relative Quality of Rocks				
	Length of Core x 100 % ogth of Core Run		nting only pieces > 4" long x 100 % of Core Run			
<u>Description</u>	Core Recovery %	<u>Description</u>	RQD %			
Incompetent	Less than 40	Very Poor	0 - 25 %			
Competent	40 - 70	Poor	25 - 50 %			
Fairly Continuous	71 - 90	Fair	50 - 75 %			
Continuous	91 - 100	Good	75 - 90 %			
		Excellent	90 - 100 %			