

ADDENDUM 1

Via E-Mail

DATE: December 03, 2025

Contract: 26-C-00006; Citywide Resurfacing Contract

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1 – Replace Page P-4 with P-4R

Item 2 – Sheet SPT-32 (pg 101/113):

1. Revise: scrivener error on title of SPT-21.6: “Methold” to Method
2. Revise the following language under SPT-21.7 BASIS OF PAYMENT:
 - a. REMOVE:

Full Depth Reclamation pay items will be classified within four tier groups based on the size of the project.

- SP-01: Full Depth Reclamation Tier 1 (5,000 – 15,000 SY)
- SP-02: Full Depth Reclamation Tier 2 (15,000 – 25,000 SY)
- SP-03: Full Depth Reclamation Tier 3 (25,000 – 50,000 SY)
- SP-04: Full Depth Reclamation Tier 4 (50,000+ SY)

Payment shall be determined according to the designated tier. For example, if Corridor A is anticipated to undergo Full Depth Reclamation and is quantified at 20,000 SY, then the cost to reclaim Corridor A will be the product of SP-02 x 20,000 SY

- b. ADD:

Full Depth Reclamation shall be paid at a single unit price per square yard, regardless of project size. The total payment will be calculated as: $\text{Payment} = \text{Contract Unit Price (per SY)} \times \text{Total Square Yards Reclaimed}$

Item 3 – Responses are provided for the following RFI’s:

1. Pay item 0710-90 “Painted Pavement Markings – Final Surface” has a quantity of 1 LS. How can there be a work order driven contract that doesn’t have any provided plans or streets at bid time with a Lump Sum unit for striping? I feel like the “paint” striping would either need to be paid under the thermoplastic pay items at the same quantities, or we need more information to give a price for final surface paint. Please clarify how we are to bid this item.

City of Tampa Addendum

Response - This pay item is to include all painted pavement markings that are placed prior to permanent thermoplastic markings under the contract, NOT INCLUDING preformed thermoplastic pay items as outlined in the FDOT basis of estimates. This means that under this bid the Lump Sum cost should reflect the paint that must be placed in connection with pay items 0711-16-101, 0711-16-102, 0711-16131, 0711-16201, 0711-16202, and 0711-16231 which are all measured in Gross Miles.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to ContractAdministration@tampagov.net.

Jim Greiner, P.E., Contract Management Supervisor

Contract 26-C-00006 Citywide Resurfacing Contract

0711 11170	THERMO., STD., WHITE ARROWS	EA	50.0			
0711 11180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	100.0			
0711 11224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRONS	LF	600.0			
0711 11241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6- 10 DOTTED EXTENSION LINE, 6"	LF	2,500.0			
0711 12123	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 12" FOR CROSS WALK OR ROUNDABOUT	LF	100.0			
0711 14123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	4,100.0			
0711 14125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	5,000.0			
0711 14160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	67.0			
0711 14170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	84.0			
0711 16101	THERMOPLASTIC, STANDARD, OTHER SURFACES, WHITE, SOLID, 6"	GM	20.0			
0711 16102	THERMOPLASTIC, STANDARD, OTHER SURFACES, WHITE, SOLID, 8"	GM	0.1			
0711 16131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	6.0			
0711 16201	THERMOPLASTIC, STANDARD, OTHER SURFACES, YELLOW, SOLID, 6"	GM	23.0			
0711 16202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.1			
0711 16231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	7.0			
0714 10	GREEN-COLORED PAVEMENT MARKINGS, BIKE LANE	SF	10,000.0			
SPT-10.02.1	TREE REMOVAL 4 TO 12"	EA	4.0			
SPT-10.02.2	TREE REMOVAL >12 TO 18"	EA	4.0			
SPT-10.02.3	TREE REMOVAL >18 TO 24"	EA	4.0			
SPT-10.02.4	TREE REMOVAL >24 TO 36"	EA	4.0			
SP-8.06.1	INLET, COT, CURB, TYPE 1	EA	4.0			
SP-8.06.2	INLET, COT, CURB, TYPE 2	EA	4.0			
SP-8.06.4	INLET, COT, GRATE, TYPE T	EA	4.0			
SP-8.06.5	INLET, COT, GRATE, TYPE E	EA	4.0			
SP-921-703-200	BIKE LANE SEPARATOR, FURNISH AND INSTALL	EA	350.0			
SP-21	FULL DEPTH RECLAMATION	SY	25,000			
	Sub Total					
	Mobilization (10% of Sub Total)	L.S.	1.0	\$	-	
	Maintenance of Traffic (10% of Sub Total)	L.S.	1.0	\$	-	
	Contingency Allowance	L.S.	1.0	\$	1,200,000.00	\$1,200,000.00
					TOTAL	\$1,200,000.00