



CITY OF TAMPA

Bob Buckhorn, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 1

DATE: January 13, 2014

Contract 14-C-00002; Forest Hills Collection System CIPP Rehabilitation – FY14

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

- Item 1: Replace Proposal page P-3 with attached Proposal page P-3R.
- Item 2: Contract Items, Contract Item 102 Series – Maintenance of Traffic: Last paragraph first sentence, delete 'Day'. The first sentence should read payment for Maintenance of Traffic will be made at the appropriate Contract Lump Sum Price.
- Item 3: Replace Plan Sheet 2, Forest Hills Collection System CIPP Rehabilitation Note and Index with the attached revised Plan Sheet 2.
- Item 4: Attached for reference is a copy of the pre-bid meeting sign-in sheet.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to ContractAdministration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Management Supervisor

Item No.	Description	Unit	Approx. Quantity	Unit Price in Words	Unit Price	Total Computed Price
100	Contingency	LS	1	Fifty Thousand Dollars and No Cents	\$ 50,000.00	\$ 50,000.00
102	Maintenance of Traffic	LS	1		\$	\$
0408.2360	Cured-in-Place Pipe for 8" Diameter Gravity Sewer (.236 inchThick)	LF	21,759		\$	\$
0410.2950	Cured-in-Place Pipe for 10" Diameter Gravity Sewer (.295 inch Thick)	LF	4,073		\$	\$
0601.08	Hydraulic Cleaning & Inspection of 8" Diameter Gravity Sewer	LF	21,759		\$	\$
0601.10	Hydraulic Cleaning & Inspection of 10" Diameter Gravity Sewer	LF	4,073		\$	\$
0700	Disposal of Debris	CY	40		\$	\$
2050	Reconnect Service Connections	EA	398		\$	\$
9000	Sewer Bypass with Tanker Truck	E.D.	10		\$	\$
9050.08	Sewage Bypass Pumping for 8" Diameter Sewer	LF	21,759		\$	\$
9050.10	Sewage Bypass Pumping for 10" Diameter Sewer	LF	4,073		\$	\$
				TOTAL	\$	\$

PLOTTED BY Greg Peoples
PLOT DATE: Thursday, January 09, 2014 11:31:55 AM
DRAWING FILE K:\WWL_Projects\2013\2013_WO_FOREST_HILLS_COLLECTION\Drawings\General\Cover.dwg
CTB - WW-TOSHIBA.CTB
LAST SAVED BY ssh5

GENERAL NOTES

1. THE SCOPE OF THIS PROJECT SHALL CONSIST OF REHABILITATION OF 8" and 10" DIA WASTEWATER PIPELINE BY INSTALLATION OF CURED IN PLACE PIPE LINER AND ALL APPURTENANCE ASSOCIATED WITH COMPLETION OF THE PROJECT.
2. SHEETS 04-32 ARE THE EXISTING RECORD DRAWINGS OF THE SEWER PIPE TO BE REHABILITATED.
3. CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR OBTAINING THE NECESSARY ROAD CLOSURE AND RIGHT-OF-WAY PERMITS FROM THE APPROPRIATE GOVERNMENT AGENCIES HAVING JURISDICTION OVER THE SPECIFIC ROADWAYS. THE TABLE ON THIS SHEET, LISTS THE CONTACT NAMES AND PHONE NUMBERS FOR THE AGENCIES WITH JURISDICTION OVER THE VARIOUS LOCATIONS THROUGHOUT THIS PROJECT.
4. IN ORDER TO OBTAIN ROADWAY CLOSURE OR RIGHT-OF WAY PERMITS, AT MINIMUM, THE CONTRACTOR MUST SUBMIT DETAILED MAINTENANCE OF TRAFFIC (MOT) PLANS ALONG WITH APPLICATIONS TO THE APPROPRIATE AGENCY. THE MOT(S) SHALL CONFORM TO APPLICABLE FLORIDA DEPARTMENT OF TRANSPORTATION (FDOT) INDEX DRAWINGS (MOST CURRENT EDITION). THE GOVERNING AGENCIES MAY REQUIRE ADDITIONAL INFORMATION AND DICTATE SPECIFIC WORK TIMES DURING NON-PEAK TRAFFIC HOURS. REFER TO SPECIFIC PROVISIONS FOR SPECIFIC TRAFFIC CONTROL REQUIREMENTS.
- ⚠

5. BYPASS PUMPS SHALL BE CAPABLE OF DELIVERING 300 GPM FOR 8" DIA PIPE AND 600 GPM FOR 10" DIA PIPE. THE BYPASS PUMPS SHALL BE OF THE SELF PRIMING QUITE FLOW TYPE PUMP. BYPASS PUMP NOISE SHALL STRICTLY COMPLY TO ALL LOCAL REGULATIONS AND ORDINANCES COVERING NOISE CONTROL. THIS MAY REQUIRE CONSTRUCTING SOUND ATTENUATING ENCLOSURE AROUND PUMPS. BYPASS METHOD SHALL BE SUBMITTED AND APPROVED BY THE ENGINEER.
6. THE PROPOSED LINER THICKNESS FOR THE 8" SEWER SHALL BE 6.0 MM THICKNESS AND 10" SEWER SHALL BE 7.5 MM THICKNESS.
7. CONTRACTOR SHALL RESTORE ALL LANDSCAPING, SODDING, SPRINKLER SYSTEM PIPING AND PAVEMENT THAT MAY HAVE BEEN DAMAGED DURING CONSTRUCTION TO ITS ORIGINAL CONDITION OR BETTER.
8. CONTRACTOR SHALL COORDINATE ALL CONSTRUCTION ACTIVITIES WITH WASTEWATER PERSONNEL AND PUMPING STATION OPERATIONS.
9. OSHA STANDARD EQUIPMENT SUCH AS SAFETY HARNESES, GAS MONITORS, LOWER EXPLOSIVE LIMIT (LEL) DETECTORS, BREATHING APPARATUS, ETC. SHALL BE UTILIZED WHERE THE WORK DICTATES THEIR USE.

TRAFFIC OPERATIONS - CONTACTS NAMES			
Location	(Jurisdiction)	Contact Name	Phone Number
North Blvd.,Forest Hills Dr., Oregon Cir. and including all other streets not mentioned	(City of Tampa)	David Houseman	274-5656
Armenia Ave.	(County)	Amos Castillo	628-5025

Index	
Sheet Number	Description
GENERAL	
01	COVER SHEET
02	NOTE AND INDEX
PROJECT PLANS	
03	Proposed Plan
PROJECT DETAILS	
04	Asbuilt 092-004 Newport Circle
05	Asbuilt 092-004 Bogie Drive
06	Asbuilt 092-005 Cliff Circle
07	Asbuilt 092-006 Newport Circle
08	Asbuilt 092-007 Oregon Ave
09	Asbuilt 092-008 Angeline Drive
10	Asbuilt 092-009 Divot Lane
11	Asbuilt 092-010 Edgewater Lane
12	Asbuilt 092-010 Fore Drive
13	Asbuilt 092-010 Oregon Ave
14	Asbuilt 092-011 Edgewater Lane and Oregon Circle
15	Asbuilt 092-012 Oregon Circle and Oakleaf Ave
16	Asbuilt 092-012 Oakleaf Ave
17	Asbuilt 092-012 Waterhole Place
18	Asbuilt 092-013 Rome Ave
19	Asbuilt 092-013 Rome Ave and Fairway
20	Asbuilt 092-014 Valle Dr
21	Asbuilt 092-014 Valle Dr and Par Two Pl
22	Asbuilt 092-015 Fleetwood Drive and Valle Drive
23	Asbuilt 092-016 Oakleaf Ave
24	Asbuilt 092-017 Armenia Ave
25	Asbuilt 092-017 Armenia Ave Sta 15+00
26	Asbuilt 093-010 North Blvd
27	Asbuilt 093-011 Cliff Circle
28	Asbuilt 093-012 Forest Hills
29	Asbuilt 093-013 Oregon Ave
30	Asbuilt 120-019 Oregon Ave
31	Asbuilt 112-006 Forest Hills Dr
32	Asbuilt 117-17a N Armenia Ave

CONTRACT 14-C-00002; Forest Hills Collection System Rehab. By C.I.P.P. - Pre-Bid Conf. 01/07/14.

E-Mail to Register as a Plan Holder and E-Mail All Questions to: ContractAdministration@tampagov.net

Sign-In Sheet ☐ Please Print

City of Tampa, Contract Administration Department

	Name	Organization	E-Mail OR Phone
1	Jim Greiner, PE	Tampa Contract Administration Dept.	Jim.Greiner@tampagov.net
2	Jim T. Velitschka	J.T.V. Inc.	J+V INCORPORATED@AOL.COM
3	Mike Keenan	Holland pump	M.KeK@Hollandpump.com
4	Jed Church	Goddwin Pumps	jed.church@xylemms.com
5	John Sunderman	Layne Inliner	john.sunderman@layne.com
6	Terry Adderholt	SAK CONSTRUCTION	TADDERHOLD@SAKON.COM
7	Cassidy Barrett	COT WW Design	cassidy.Barrett@tampagov.net
8	JACK FERRAS	COT WW DESIGN	JACK.FERRAS@TAMPAGOV.NET
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			