CITY OF TAMPA

Bob Buckhorn, Mayor **CONTRACT ADMINISTRATION DEPARTMENT**

David L. Vaughn, AIA, Director

ADDENDUM NO.3
DATE: July 16, 2014

Contract: 14-C-00009; Krause Pump Station Rehabilitation

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: SP-21 Bypass Pumping, replace last 2 sentences of the 13th paragraph as follows:

Delete:

"The Contractor shall be responsible from obtaining and removing a temporary power drop and meter from TECO and all associated cost with the installation. The contractor shall also be responsible for costs required to supply and maintain power needed to continuously operate the bypass system."

Add:

"Refer to SP-99 in regard to the Temporary Electric Service Connections for the bypass system."

Item 2: Add SP-99 Temporary Electric Service Connections

SP-99 Temporary Electric Service Connections
Due to the location of the existing transformers, it will not be feasible to use the proposed permanent transformers as a temporary power source for the bypass pumping system. If electric pumps are used for the bypass system, temporary electric service connections must be provided.

The following conditions will apply to the temporary electrical service connections:

1. The City will reimburse the Contractor the cost for the installation of the temporary service connections, provided by Tampa Electric Company (TEC), using the contingency funds for the project. Cost of the temporary service connections, provided by TEC, shall not be included in the lump sum bid cost for the project. The amount of reimbursement shall be based on the actual invoice(s) provided by Tampa Electric Company and no additional mark-up will be permitted.

2. The City will only provide reimbursement of TEC costs for a maximum of two temporary electrical service connections with two temporary transformers. It is anticipated that one temporary power supply will be required for the bypass pumps located on the west side of Ashley St. and a second power supply will be required for the pumps located on the east side of the road. The cost of any additional temporary service connections shall be the Contractor's responsibility. The use of additional temporary power supplies in lieu of a back-up generator system shall not be permitted.

3. All costs associated with connecting the bypass pumping system's electrical components to the temporary service connections/transformers and the costs of electrical power usage shall be the Contractor's responsibility.

4. The Contractor shall be responsible for coordinating, arranging, and scheduling the installation of the temporary service connections.

5. The Contractor shall submit information on the temporary service connections for review and approval by the City. This information shall not be submitted until the bypass system has been approved.

Temporary service connections shall be sized to (a) operate the bypass pumping system and (b) maintain existing building functions such as ventilation, lighting, crane operation, etc. to facilitate a safe working environment during the rehabilitation.

Item 3: Add SP-100 Permanent Electrical Service

The City has made preliminary arrangements with Tampa Electric Company (TEC) and will compensate the utility directly for any Contribution In Aid of Construction (CIAC) required for TEC to provide the permanent electrical service as shown on the Plans. The Contractor shall coordinate electrical service requirements and responsibilities with TEC prior to performing any electrical demolition or construction work.

Item 4: SP-30 Water and Electric Services, delete the last sentence in Paragraph 2 in its entirety.

Item 5: SP-60 Contingency, revise the first sentence to read:

"The Contractor shall include a One Hundred Fifty Thousand Dollar ($150,000) contingency sum, to be included as part of the total bid amount for this contract. "

Item 6: Table of Contents: Change the Proposal pages to read: P-1 thru P-6.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect.

Questions are to be e-mailed to Contract Administration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Management Supervisor