



CITY OF TAMPA

Bob Buckhorn, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 1

DATE: April 14, 2014

Contract 14-C-00036; Straz Center Panel Replacement – Sheltered Market

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: Precast Panel Submittal Requirement:

- Provide shop drawings detailing fabrication and installation of architectural precast concrete units. Indicate size, location, plans, elevations, dimensions, cross section, types of reinforcement and panel finish. Also include locations and details of hoisting points and lifting devices for handling and erection.
- Finish of precast panel shall be as indicated on documents. The contractor shall provide sufficient evidence for panel finish including, but not limited to, providing a of 24-inch by 24-inch by 12-inch thick mockup indicating proposed finish, color and texture of exposed surfaces to match the existing precast panels of the facility. The 2ft x 2ft mock up shall be taken to the site to compare to the existing panels and, when approved, used as the reference panel for fabrication. If, in the opinion of the Engineer, that mock up panel is not compatible with the existing building finish, the contractor shall replace the mock up panel until the compatibility is satisfactory to the Engineer.

Item 2: Section 1040; page 4, Special Construction Activity; Replace with the following:

Work shall be sequenced such that the following occurs:

1. Work to be performed is to be scheduled so as not to interfere with events that have been scheduled at the facility. Coordinate with facility prior to work being performed.
2. Contractor is responsible for leaving an area as found so as not to cause any additional cleaning for facility staff. Clean up necessitated by facility personnel shall be compensated at contractor's expense and will be back-charged to the contract.
3. Parking spaces will be identified by the Straz Center subject to actual center schedules. Additional parking as needed will occur as identified in the Supplementary General Provisions.

306 E. Jackson Street, 4N • Tampa, Florida 33602 • (813) 274-8456 • FAX: (813) 274-8080

4. Straz Center Activities/Events will be ongoing. For schedule of events refer to Section 01041. After May 27, 2014 is the required minimum start time for this project. There shall be no work on July 19, and 26; and, September 13 and 20, 2014. The Straz Center may consider other windows of construction time dependent upon the Contractor's actual schedule in coordination with Straz Center's schedule.

Item 3: Attached for reference is the pre-bid meeting sign-in sheet.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to Contract Administration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Management Supervisor

CONTRACT 14-c-00036; STRAZ CENTER PANEL REPLACEMENT - PRE-BID CONF. 4/8/2014

E-Mail to Register as a Plan Holder and E-Mail All Questions to; ContractAdministration@tampagov.net

Sign-In Sheet Please Print

City of Tampa, Contract Administration Department

	Name	Organization	E-Mail OR Phone
1	Jim Greiner, PE	Tampa Contract Administration Dept.	Jim.Greiner@tampagov.net
2	James Jackson	" " "	
3	Marisela Linares	JVA Construction Inc.	jva@jvaconstruction.com
4	Imran Shaukh	Laqali & Associate.	LAEQALI@HOTMAIL.COM
5			
6		NOTE:	
7		DURA STRESS	813.639.1142
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			