



CITY OF TAMPA

Bob Buckhorn, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

Michael W. Chucran, Director

ADDENDUM NO. 2

DATE: September 16, 2016

Contract 15-C-00059; Upper Peninsula Stormwater Improvements Phase 2 (Vasconia Outfall) – Rebid

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

- Item 1: Replace proposal pages P-2 through P-8 with the attached pages P-2 through P-8.
- Item 2: SP-40 Concrete Requirements, change “400” to read: 346 except 346.6.1
- Item 3: SP-51 City Testing, replace the first sentence with the following: All testing will be the responsibility of the Contractor.
- Item 4: SP-60 Contingent Items, Delete the first sentence in its entirety.
- Item 5: S-20.01 Asbestos Removal, Delete this provision in its entirety.
- Item 6: Insert the following Contract Item 327:

CONTRACT ITEM 327 – 1” MECHANICAL MILLING

The Contractor shall furnish all materials, equipment, and labor to mill 1” of existing asphalt material shown on the Plans, specified, and directed by the Engineer.

Items included in this Contract Item include, but are not limited to, the material, equipment and labor necessary to mill a Superpave Asphalt Concrete pavement as specified on the Plans and shall conform to the latest version of the FDOT Standard Specifications – Workmanship and Materials Section 334 – Superpave Asphaltic Concrete.

Payment for Superpave Asphaltic Concrete, Traffic B will be made at the appropriate Contract Square yards per inch (SY / IN) Price.

- Item 7: Replace plan sheet nos. 11 and WW112 with the attached plan sheet nos. 11 and WW112.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to ContractAdministration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Management Supervisor

306 E. Jackson Street, 4N • Tampa, Florida 33602 • (813) 274-8456 • FAX: (813) 274-8080



Item No.	Description	Unit	Quantity	Unit Price in Words		Unit Price	Total Computed Price
Schedule A- Stormwater							
100	CONTINGENCY - STORMWATER	EA	1	Five Hundred Thousand Dollars and No Cents	\$	500,000.00	\$ 500,000.00
101	MOBILIZATION	LS	1		\$		\$
102	MAINTENANCE OF TRAFFIC	LS	1		\$		\$
104-1	SILT FENCE & EROSION CONTROL	LF	10,562		\$		\$
104-18	INLET PROTECTION SYSTEM	EA	38		\$		\$
105-1	ROOT PRUNING	LF	740		\$		\$
105-2-1	TREE REMOVAL UNDER 24"	EA	71		\$		\$
105-2-2	TREE REMOVAL UNDER 24" and UP	EA	8		\$		\$
105-3	TREE TRIMMING	EA	20		\$		\$
105-4	TREE BARRICADES	LF	4,250		\$		\$
110-2	DEMOLITION OF EX. STORM PIPE AND STRUCTURES	LF	424		\$		\$
110-3	GROUTING OF STORM PIPES	CY	1,035		\$		\$
120	REGULAR SUBSOIL EXCAVATION	CY	12,206		\$		\$
120-2	REMOVAL OF UNSUITABLE MATERIAL	CY	3,600		\$		\$
120-3	EXCAVATION AND REMOVAL OF ROCK MATERIAL	CY	1,000		\$		\$
160	TYPE B STABILIZATION	SY	17,734		\$		\$
285	OPTIONAL BASE, BASE GROUP 06	SY	17,734		\$		\$
327	1" MECHANICAL MILLING	SY/IN	6,533		\$		\$
334	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	2,140		\$		\$

Item No.	Description	Unit	Quantity	Unit Price in Words	Unit Price	Total Computed Price
400	COLLAR CONNECTION	EA	32			
410-1	PRECAST BOX CULVERT 9'X6'	LF	1,204			
410-2	PRECAST BOX CULVERT 10'X5'	LF	158			
410-3	PRECAST BOX CULVERT 9'X5'	LF	1,497			
410-4	PRECAST BOX CULVERT 6'X5'	LF	525			
410-5	PRECAST BOX CULVERT Double 5'X4'	LF	299			
410-6	PRECAST BOX CULVERT Double 5'X3'	LF	287			
425-1-1	TYPE J JUNCTION BOX 4x4	EA	1			
425-1-2	TYPE J JUNCTION BOX 4x6	EA	3			
425-1-3	TYPE J JUNCTION BOX 4x13	EA	1			
425-1-4	TYPE J JUNCTION BOX 5x5	EA	3			
425-1-5	TYPE J JUNCTION BOX 5x8	EA	2			
425-1-6	TYPE J JUNCTION BOX 6x5	EA	1			
425-1-7	TYPE J JUNCTION BOX 6x7	EA	1			
425-1-8	TYPE J JUNCTION BOX 8x13	EA	1			
425-1-9	TYPE J JUNCTION BOX 9x4	EA	1			
425-1-10	TYPE J JUNCTION BOX 10x10	EA	1			
425-1-11	TYPE J JUNCTION BOX 13x14	EA	3			
425-1-1A	CUSTOM JUNCTION BOX / CONFLICT STRUCTURE	EA	7			
425-1-1B	TYPE J JUNCTION BOX / CONFLICT STRUCTURE 13x14	EA	1			
425-2-41	MANHOLE RISER, P-7, <10'	EA	15			
425-2-42	TYPE P JUNCTION BOX 3.5x3.5	EA	2			

Item No.	Description	Unit	Quantity	Unit Price in Words	Unit Price	Total Computed Price
425-9-1	INLET, COT CURB TYPE 1, <10'	EA	19	\$	\$	
425-9-1A	INLET, COT CURB TYPE 1 MODIFIED, <10'	EA	1	\$	\$	
425-9-2A	INLET, COT CURB TYPE BS-1, <10	EA	11	\$	\$	
425-9-4	INLET, COT CURB TYPE BV-1, <10	EA	13	\$	\$	
425-9-5	INLET, COT CURB TYPE BR-2, <10	EA	1	\$	\$	
425-9-6	INLET, COT GRATE TYPE T, <10'	EA	3	\$	\$	
425-9-8	INLET, COT GRATE TYPE H, <10'	EA	2	\$	\$	
425-9-2A	INLET, COT CURB TYPE BR-1, <10	EA	2	\$	\$	
425-9-2A	INLET, COT CURB TYPE BR-2, <10	EA	1	\$	\$	
430-174-115	15" ROUND STORMWATER PIPE (RCP)	LF	480	\$	\$	
430-174-115A	15" ROUND STORMWATER PIPE (CLASS IV) (RCP)	LF	102	\$	\$	
430-174-118	18" ROUND STORMWATER PIPE (RCP)	LF	280	\$	\$	
430-174-124	24" ROUND STORMWATER PIPE (RCP)	LF	645	\$	\$	
430-174-124A	24" ROUND STORMWATER PIPE (CLASS IV) (RCP)	LF	82	\$	\$	
430-174-130	30" ROUND STORMWATER PIPE (RCP)	LF	44	\$	\$	
430-174-136	36" ROUND STORMWATER PIPE (RCP)	LF	27	\$	\$	
430-174-148	48" ROUND STORMWATER PIPE (RCP)	LF	164	\$	\$	
430-174-154	54" ROUND STORMWATER PIPE (RCP)	LF	60	\$	\$	
430-174-114-123	14"x23" ELLIPTICAL STORMWATER PIPE, (ERCP)	LF	92	\$	\$	
430-174-119-130	19"x30" ELLIPTICAL STORMWATER PIPE, (ERCP)	LF	162	\$	\$	
430-174-119-130A	19"x30" ELLIPTICAL STORMWATER PIPE, (CROSS DRAIN) (CLASS IV) (ERCP)	LF	155	\$	\$	
430-174-124-138	24"x38" ELLIPTICAL STORMWATER PIPE, (ERCP)	LF	95	\$	\$	
430-174-124-138A	24"x38" ELLIPTICAL STORMWATER PIPE, (CLASS IV) (ERCP)	LF	155	\$	\$	
430-174-129-145	29"x45" ELLIPTICAL STORMWATER PIPE, (ERCP)	LF	153	\$	\$	

Item No.	Description	Unit	Quantity	Unit Price in Words	Unit Price	Total Computed Price
430-174-129-145A	29"x45" ELLIPTICAL STORMWATER PIPE, (CLASS IV) (ERCP)	LF	79	\$	\$	
520-1-1	CONCRETE CURB & GUTTER, TYPE D	LF	1,736	\$	\$	
520-1-7	CONCRETE CURB & GUTTER, DROP CURB	LF	2,483	\$	\$	
520-1-10	CONCRETE CURB & GUTTER, TYPE F	LF	6,886	\$	\$	
522-1	SIDEWALK CONCRETE, 4" THICK (SIDEWALKS)	SY	708	\$	\$	
522-2	SIDEWALK CONCRETE, 6" THICK (DRIVEWAYS)	SY	2,635	\$	\$	
522-3	BRICK DRIVEWAYS REPLACEMENT	SF	8,000	\$	\$	
522-4	CURB RAMPS W/ DETECTABLE WARNINGS	EA	17	\$	\$	
535	WINGWALL PER FDOT INDEX 289	CY	50	\$	\$	
530	RUBBLE RIP RAP	TN	59	\$	\$	
548-1	RETAILING WALL SYSTEM (INTERLOCKING BLOCK WALL)	SF	145	\$	\$	
711-11-111	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	2,858	\$	\$	
711-11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	LF	531	\$	\$	
711-11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	LF	124	\$	\$	
711-11-131	THERMOPLASTIC, STANDARD, WHITE, SKIP 6"	LF	2,831	\$	\$	
711-11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE	EA	1	\$	\$	
711-11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	6	\$	\$	
711-11-211	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	956	\$	\$	
908	8" DIA. PVC PIPE (C-900, DR-18)	LF	3,694	\$	\$	
924	24" DIA. PVC PIPE (C-900, DR-18)	LF	45	\$	\$	
1706	6-INCH DIA. PVC PIPE HOUSE LATERAL (SDR-35)	LF	3,338	\$	\$	
1707	6-INCH DIA. PVC PIPE HOUSE LATERAL (SDR-35) THROUGH BOX CULVERT	EA	15	\$	\$	
1708	6-INCH DIA. PVC PIPE HOUSE LATERAL(SDR-35) UNDER BOX CULVERT	EA	2	\$	\$	
2700	8"x6" PVC WYE	EA	86	\$	\$	

Item No.	Description	Unit	Quantity	Unit Price in Words		Unit Price	Total Computed Price
3508	8-INCH FLEXIBLE CONNECTOR	EA	2		\$		\$
3524	24-INCH FLEXIBLE CONNECTOR	EA	1		\$		\$
4000	PRECAST CONCRETE STANDARD OR DOGHOUSE MANHOLE BASE	EA	20		\$		\$
4100	PRECAST CONCRETE MANHOLE BARREL	VF	167		\$		\$
4200	PRECAST CONCRETE MANHOLE CONE	EA	20		\$		\$
4300	STANDARD SEWER MANHOLE SHALLOW TYPE	EA	2		\$		\$
4301	DROP MANHOLE	EA	1		\$		\$
4600	CAST IRON MANHOLE FRAME AND COVER	EA	23		\$		\$
4660	6-INCH DIAMETER PVC CLEANOUT AND COVER	EA	86		\$		\$
4900	CONNECT TO EXISTING MANHOLE	EA	1		\$		\$
5000	SECURITY SERVICES	HR	3,240		\$		\$
8901-1	LAWN REPLACEMENT AND SODDING (BAHIA)	SF	30,462		\$		\$
8901-2	LAWN REPLACEMENT AND SODDING (ZOYSA)	SF	12,661		\$		\$
8901-3	LAWN REPLACEMENT AND SODDING (ST AUGUSTINE)	SF	70,472		\$		\$
						TOTAL SCH. A	\$

Item No.	Description	Unit	Quantity	Unit Price in Words	Unit Price	Total Computed Price
SCHEDULE B - WATER PAY ITEMS						
2102	F&I 6" DUCTILE IRON PIPE	LF	4,598	\$	\$	
2104	F&I 8" DUCTILE IRON PIPE	LF	200	\$	\$	
2200	F&I 2" HDPE TUBING BY HDD w/HDPE ADAPTERS AND HDPE FITTINGS AT VARIOUS DEPTHS	LF	30	\$	\$	
2500	REMOVAL OF ABANDONED PIPE 3" AND SMALLER IN DIAMETER	LF	340	\$	\$	
2501	REMOVAL OF ABANDONED PIPE 4" - 10" IN DIAMETER	LF	910	\$	\$	
2600	CUT AND PLUG 3" AND SMALLER IN DIAMETER PIPE	EA	7	\$	\$	
2601	CUT AND PUG 4", 6" and 8" DIAMETER PIPE	EA	2	\$	\$	
2800	MAKE AND TAP FURNISH MATERIALS TO CONNECT 3" AND SMALLER WATER MAINS TO NEW/ EXITING MAINS (0-15 ft. IN LENGTH)	EA	2	\$	\$	
3041	FURNISH & INSTALL 6" BELL RESTRAINT ON EXISTING PIPE	EA	8	\$	\$	
3042	FURNISH & INSTALL 8" BELL RESTRAINT ON EXISTING PIPE	EA	4	\$	\$	
3071	FURNISH 6" PUSH-ON RESTRAIN GASKETS	EA	62	\$	\$	
3072	FURNISH 8" PUSH-ON RESTRAIN GASKETS	EA	5	\$	\$	
4004	F&I 6" DUCTILE IRON PLUG OR CAP W/ DIP, CIP or PVC	EA	1	\$	\$	
4005	F&I 6" DUCTILE IRON BENDS, OFFSET, SLEEVES OR REDUCERS W/ DIP, CIP or PVC	EA	104	\$	\$	
4006	F&I 6" DUCTILE IRON TEE W/ DIP, CIP or PVC	EA	15	\$	\$	
4009	F&I 8" DUCTILE IRON BENDS, OFFSETS, SLEEVES OR REDUCERS W/ DIP, CIP or PVC	EA	10	\$	\$	
4010	F&I 8" DUCTILE IRON TEE W DIP, CIP or PVC	EA	2	\$	\$	
5000	F&I FULL FIRE HYDRANT ASSEMBLY	EA	8	\$	\$	
5200	REMOVE AND SALVAGE OF FIRE HYDRANT	EA	2	\$	\$	
6000	F&I 2" GATE VALVE WITH BOX ON DIP, CIP or PVC	EA	2	\$	\$	
6002	F&I 6" GATE VALVE OR TAPPING VALVE WITH BOX ON DIP, CIP or PVC	EA	28	\$	\$	
6003	F&I 8" GATE VALVE OR TAPPING VALVE WITH BOX ON DIP, CIP or PVC	EA	1	\$	\$	
6080	F&I 2' LONG VALVE NUT EXTENSION	EA	5	\$	\$	

Item No.	Description	Unit	Quantity	Unit Price in Words	Unit Price	Total Computed Price
6081	F&I 3' LONG VALVE NUT EXTENSION	EA	5		\$	\$
6104	F&I 8" Linestop on Existing Water Main	EA	1		\$	\$
6205	F&I 8" TEAM Insertion Valves on Existing Water Main	EA	2		\$	\$
7002	F&I 8" TAPPING SLEEVE AND MAKE TAP	EA	1		\$	\$
7003	F&I 12" TAPPING SLEEVE AND MAKE TAP	EA	1		\$	\$
8100	FURNISH TAP AND INSTALL 3/4" or 1" METER SERVICE ON PVC, DIP, or CIP (0-15')	EA	42		\$	\$
8101	FURNISH, TAP AND INSTAL 3/4" METER SERVICE ON PVC, DIP or CIP (+15-80')	EA	25		\$	\$
9200	FURNISH, PLACE AND COMPACT LIMEROCK BASE	CY	170		\$	\$
9980	CONTINGENCY ALLOWANCE- WATER	EA	1	Eighty Seven Thousand Dollars and No Cents	\$ 87,000.00	\$ 87,000.00
					TOTAL SCH. B	\$
				TOTAL SCH. A & SCH. B		

G:\Projects\14-041 - Spring Lake Basin\Drawings\Design&Construction\14-041-PP-OUTFALL.dwg - Printed Sep 13, 2016-3:09pm by: Abdulla



