



CITY OF TAMPA

Bob Buckhorn, Mayor

Contract Administration Department

Michael W. Chucran, Director

ADDENDUM 1

October 11, 2018

Contract 18-C-00041; Stormwater Construction Citywide FY18

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: Replace existing pages with the attached P-2, 3, & 4 attached.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to ContractAdministration@tampagov.net.

Jim Greiner

Jim Greiner, P.E. Contract Management Supervisor

Item No.	Description	Unit	Est Qty	Unit Price in Words	Unit Price	Total Price
105.2B	TREE REMOVAL - 9"-18"	EA	22		\$	\$
110.1	CLEARING & GRUBBING POND SITE	AC	2		\$	\$
120	REGULAR EXCAVATION AND DISPOSAL	CY	2,100		\$	\$
130	CLEAN FILL	CY	7,600		\$	\$
135	GRADE DITCH	LF	85		\$	\$
110.3	GROUT EX. STORMWATER PIPE LATERALS	CY	10		\$	\$
425.1	INLETS, DT BOT, TYPE E, <10'	EA	15		\$	\$
425.2	MANHOLES, P-7, <10' deep (3.5')	EA	12		\$	\$
425.3	MANHOLES, J-7, <10' deep (4')	EA	3		\$	\$
425.4	INLET, COT CURB TYPE 1, <10'	EA	1		\$	\$
425.5.2	INLET, COT CURB TYPE 2, MODIFIED TYPE H BOTTOM	EA	1		\$	\$
425.7	INLET, COT CURB TYPE BR-1, <10'	EA	1		\$	\$
425.8	INLET, COT GRATE TYPE T, <10'	EA	47		\$	\$
430.15	15" ROUND STORMWATER PIPE (RCP)	LF	1,200		\$	\$
430.1	18" ROUND STORMWATER PIPE (RCP)	LF	1,000		\$	\$
430.11	19"x30" MITERED END SECTION	EA	3		\$	\$
430.12A	CONNECT STORMWATER PIPE TO EXISTING STRUCTURE (0-24")	EA	18		\$	\$
430.12B	CONNECT STORMWATER PIPE TO EXISTING STRUCTURE (30-60")	EA	1		\$	\$
430.2	24" ROUND STORMWATER PIPE (RCP)	LF	500		\$	\$
430.30A	30" ROUND STORMWATER PIPE (RCP)	LF	400		\$	\$
430.60A	60" ROUND STORMWATER PIPE (RCP)	LF	1,000		\$	\$
430.4	12"x18" ELLIPTICAL STORMWATER PIPE (CLASS IV) (RCP)	LF	1,093		\$	\$

Item No.	Description	Unit	Est Qty	Unit Price in Words	Unit Price	Total Price
430.5	14"x23" ELLIPTICAL STORMWATER PIPE (ERCP)	LF	299		\$	\$
430.6	19"x30" ELLIPTICAL STORMWATER PIPE (ERCP)	LF	1,298		\$	\$
530	Rip Rap - (2' deep)	CY	89		\$	\$
550.1	REMOVE AND RESET FENCE	LF	1,255		\$	\$
8901	SOD - AUGUSTINE	SY	9,500		\$	\$
8902	SOD - BAHIA	SY	8,056		\$	\$
8903	Hydroseeding	SY	2,900		\$	\$
285.2	BEDDING	TN	237		\$	\$
334	SUPERPAVE ASPHALTIC CONC, SP12.5 (2")	TN	936		\$	\$
520.6	F&I Type "D" concrete curb	LF	100		\$	\$
520.8	F&I CURB, DROP	LF	130		\$	\$
520.110	CONCRETE CURB AND GUTTER TYPE "F"	LF	785		\$	\$
522.1	SIDEWALK CONCRETE, 6" THICK (3000 psi)	SY	573		\$	\$
522.2	CONCRETE, 6" THICK (DRIVEWAYS) (3000psi)	SY	2,586		\$	\$
9250	ADA Compliant Ramps	EA	25		\$	\$
2103	F&I 8" ductile iron pipe offset - all inclusive with tap (<30' in length)	EA	1		\$	\$
2103.12	F&I 12" ductile iron pipe offset - all inclusive with tap (<30' in length)	EA	2		\$	\$
2106	F&I 10" DIP - polywrap w fittings and restraints - all inclusive	LF	3,040		\$	\$
2107.PS	Installation of Flygt pump, control panel, floats and internal piping (for stormwater pump station, pump and electrical panel materials provided by City)	LS	1		\$	\$
2200	F&I 2" HDPE tubing by HDD w/HDPE adapters and HDPE fittings at various depths - all inclusive with tap (20' in length)	EA	2		\$	\$
6004	F&I 10" gate or tapping valve with box on DIP, CIP or PVC	EA	6		\$	\$

Item No.	Description	Unit	Est Qty	Unit Price in Words	Unit Price	Total Price
6005	F&I 10" air release valve	EA	2		\$	\$
6104	F&I 8" Linestop on Existing Water Main	EA	1		\$	\$
900.1	8" Dia. PVC Pipe (C-900, DR-18)	LF	25		\$	\$
900.2	24" Dia. PVC Pipe (C-900, DR-18)	LF	20		\$	\$
1706	6-Inch Diameter PVC Pipe House Lateral (SDR-35) (<30' in length)	EA	25		\$	\$
1707	6" Dia. PVC Pipe (SDR-26)	LF	30		\$	\$
1708	8" Dia. PVC Pipe (SDR-26)	LF	80		\$	\$
1709	10" Dia. PVC Pipe (SDR-26)	LF	20		\$	\$
4660	6-Inch Diameter, SDR-35, PVC Clean-out and cover	EA	25		\$	\$
100	CONTINGENCY	LS	1		\$ 250,000	\$ 250,000.00
				Sub Total		
101	MOBILIZATION - 8% of Subtotal	LS	1		\$	\$
102	MAINTENANCE OF TRAFFIC - 10% of Subtotal	LS	1		\$	\$
				Total		