City of Tampa
Jane Castor, Mayor

Contract Administration
Michael W. Chucran, Director
306 East Jackson Street, 4N
Tampa, FL 33602

Office (813) 274-8116
Fax: (813) 274-7368

ADDENDUM 1
Via E-Mail
DATE: August 9, 2019

Contract: 19-C-00007 Mariner Pump Station Rehabilitation

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1. The Bid Opening Date is hereby changed to August 20, 2019.

Item 2. Add to Sheet 3, G- 26. ALL CONCRETE SURFACES OF THE EXISTING WET WELL AND PROPOSED TOP SLAB TO BE EXPOSED TO SEWER GASES SHALL BE COATED WITH A MINIMUM OF 125 MILS EPOXING COATING SYSTEM

Item 3. Add to Sheet 3, G-27. Contractor is required to match existing pavers and installation pattern in-kind. The original brick pavers at this location were installed by BCU Border Creations, Inc., Lutz, Florida (813-926-2700). The pavers used are interlocking pavers (60 mm) manufactured by Old Castle with a Holland Stone 4" x 8" style and slate color. The pavers are to be installed in a 90 degree running bond pattern and on top of a 4" crush concrete base. After pavers are installed, sand joints with course sand as per ASTM C-144 requirement.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to Contract Administration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Management Supervisor