



## FY 22 Stormwater Service Assessment Program Report

**Tampa City Council Update No. 22 - May 2022**

Maintenance activities are reported based on service level frequency. Below is a list of the primary maintenance categories that are being tracked. Along with service level cycle times, we have also provided maintenance statistics for the quarter.

Operations and Maintenance Activities	Pre Fee Service Levels	Fee Target Service Levels	2 <sup>nd</sup> Quarter FY22 & Year-to-Date Service Levels
Ditches	10-Year Cycle	7-Year Cycle	13.6-Year Cycle (2 <sup>nd</sup> Qtr.) 8.9-Year Cycle (Y.T.D)
Ponds	Minimal	3-Year Cycle	3-Year Cycle (2 <sup>nd</sup> Qtr.) 3-Year Cycle (Y.T.D)
Pipes	10-Year Cycle	7-Year Cycle	6.8-Year Cycle (2 <sup>nd</sup> Qtr.) 8.7-Year Cycle (Y.T.D)
Outfalls	15-Year Cycle	5-Year Cycle	3.8-Year Cycle (2 <sup>nd</sup> Qtr.) 4.8-Year Cycle (Y.T.D)
Pumps	Low Preventative Maintenance	Annual Preventative Maintenance	1-Year Cycle
Street Sweeping	90-Day Cycle	60-Day Cycle	59-Day Cycle (2 <sup>nd</sup> Qtr.) 53-Day Cycle (Y.T.D)
Operations and Maintenance Activities	2 <sup>nd</sup> Quarter Maintenance Statistics		
Ditches	18,248 linear feet of ditches maintained with 1,267 tons removed, 8 fallen trees removed, 441,765 linear feet of ditch mowed monthly with 13.63 tons of trash removed. Productivities should improve due to some organizational adjustments.		
Ponds	7.82 tons of trash and illegal dumping have been disposed of, there have been 116 herbicide treatments to various ponds, 126 stormwater ponds mowed monthly. 2,777 linear feet of pond fencing replaced.		
Pipes	101,431 linear feet of storm drainage pipe inspected and maintained, 2,323 storm drain inlets and manholes inspected and maintained with 337 tons of debris removed. 26 cave-ins and 27 inlet tops repaired. Productivities have improved due to some organizational adjustments.		
Outfalls	59 outfalls were inspected and maintained.		
Pumps	Preventative Maintenance provided to all thirteen (13) stormwater pump stations. Proactive maintenance and inspections totaled 270.5 Manhours.		
Street Sweeping	7,104 curb miles were swept, approximately 1,452 tons of debris removed.		

## Hoover Right of Way Ditch



**Before**



**After**



**Hoover Right of Way Ditch (cont'd)**



**Before**



**After**



**6802 S. Sheridan Rd**



**Before**



**After**