



FY 22

Stormwater Service Assessment Program Report

Tampa City Council Update No. 21 - February 2022

Maintenance activities are reported based on service level frequency. Below is a list of the primary maintenance categories that are being tracked. Along with service level cycle times, we have also provided maintenance statistics for the quarter.

Operations and Maintenance Activities	Pre Fee Service Levels	Fee Target Service Levels	1 st Quarter FY22 & Year-to-Date Service Levels
Ditches	10-Year Cycle	7-Year Cycle	13.6-Year Cycle (1 st Qtr.) 8.7-Year Cycle (Y.T.D)
Ponds	Minimal	3-Year Cycle	3-Year Cycle (1 st Qtr.) 3-Year Cycle (Y.T.D)
Pipes	10-Year Cycle	7-Year Cycle	11.6-Year Cycle (1 st Qtr.) 9.8-Year Cycle (Y.T.D)
Outfalls	15-Year Cycle	5-Year Cycle	N/A-Year Cycle (1 st Qtr.) 6.9-Year Cycle (Y.T.D)
Pumps	Low Preventative Maintenance	Annual Preventative Maintenance	1-Year Cycle
Street Sweeping	90-Day Cycle	60-Day Cycle	48-Day Cycle (1 st Qtr.) 54-Day Cycle (Y.T.D)
Operations and Maintenance Activities	1 st Quarter Maintenance Statistics		
Ditches	18,198 linear feet of ditches maintained with 1,620 tons removed, 42 fallen trees removed, 441,765 linear feet of ditch mowed monthly with 18.7 tons of trash removed. Productivities should improve due to some organizational adjustments.		
Ponds	12.44 tons of trash and illegal dumping have been disposed of, there have been 116 herbicide treatments to various ponds, 126 stormwater ponds mowed monthly. 1,497 linear feet of pond fencing replaced. Productivities should improve due to some organizational adjustments.		
Pipes	59,548 linear feet of storm drainage pipe inspected and maintained, 1,264 storm drain inlets and manholes inspected and maintained with 475 tons of debris removed. 31 cave-ins and 4 inlet tops repaired. Productivities should improve due to some organizational adjustments.		
Outfalls	There were no outfalls inspected or maintained this quarter due to the fact that we were in between contracts.		
Pumps	Preventative Maintenance provided to all thirteen (13) stormwater pump stations. Proactive maintenance and inspections totaled 115 Manhours.		
Street Sweeping	6,111 curb miles were swept, approximately 1,101 tons of debris removed.		

Wall Street Canal



Before



After

Bradley Street Ditch



Before



After