

Anita Subdivision PH I Drainage Improvements

Flooding Relief FY2020, District 4

Estimated cost: \$540K

- **Project Description:**

Consultant will evaluate the current drainage patterns and identify areas where ponding occurs. City crews will reestablish the relic ditches and correct the driveway culverts.

- **Justification:**

This neighborhood was developed with ditches draining to a collection system that discharged the stormwater to a system on Westshore Blvd. Over the years the ditches have been filled and driveway culverts have been installed improperly.

Project Map

