



**STORMWATER DEPARTMENT  
ETAILS GENERAL NOTES**

ANHOLES, INLETS, OUTFALL STRUCTURES AND OTHERS)  
PACTED #57 AGGREGATE FOUNDATION, WRAPPED COMPLETELY  
OT STANDARD SPECIFICATIONS 441-2.3

PTICAL AND BOX CULVERTS) SHALL BE WRAPPED COMPLETELY  
OT STANDARD SPECIFICATIONS 441-2.3. FABRIC SHALL  
PIPE SECTION (JOINT) AND SHALL OVERLAP A MINIMUM OF  
ABRIC SHALL BE HELD IN PLACE WITH RUST-PROOF METAL

LL BE CONSISTENT WITH FDOT INDEX 200 AND AS APPROVED

INDEX

Sheet No.	Description
1	Cover
2	Index & General Notes
3 - 4	Type 1 Inlet
5 - 7	Type 2 Inlet
8 - 10	Type 3 Inlet
11	Type 1 Inlet Modified
12 - 13	Type BS-1 Curb Inlet
14 - 15	Type BV-1 Curb Inlet
16 - 19	Type BR-1 Curb Inlet
20 - 23	Type BR-2 Curb Inlet
24-25	Grate Inlet Details
26-27	Manhole & INLET Covers
28	Guidelines For Conflict Manholes
29	Open Bottom Inlet (Type "E")
30	Temporary Force Main & Pumping Standards
31	Pipe Bedding Details
32	Payment limits & Jacked Crossing Details
33-35	Miscellaneous Details
36-40	Residential Driveway Details


D DETAILS	
r)	USF 1190 (85 lb.)
g)	USF 1190
)	USF Type -0 (160 lb.)
Ring)	USF 575
Ring)	USF 1175
	USF 6289
s	USF 6286
s	USF 6288
	USF 7100
	bove or equal.
	City Of Tampa ROW or easements shall <u>not</u> include
	sa" nor the ship logo.
	include the text "Stormwater" as shown in the

No.	DATE	REVISIONS
6		
5		
4		

DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03


**CITY of TAMPA**  
Mobility Department  
Stormwater Engineering Division

**INDEX & GENERAL NOTES**




**PLAN**  
Scale: 1/2" = 1'-0"

SCHEDULE OF REINFORCING STEEL B-RS (FOR INLET TOP -ND -PRON ONLY)					
M-RK	SIZE	COUNT	LENGTH	WT E-CH	TOT-L WT
T6-1	No 6	6	3' 5"	5.132	30.794
T6-6	No 6	2	1' 1"	1.627	3.253
L4-1	No 4	3	4' 11"	3.285	9.854
L6-1	No 6	4	4' 11"	7.385	29.541
L6-2	No 6	2	2' 5 1/2"	3.692	7.384
L7-1	No 7	1	4' 11"	10.050	10.050
-4-1	No 4	4	1' 9"	1.169	4.676
-4-2	No 4	2	2' 9 1/4"	1.851	3.702
P4-1	No 4	4	1' 1 1/2"	0.752	3.006
TOT-L WEIGHT IN POUNDS					102.261



**PLAN - TOP SLAB REINFORCEMENT**  
Scale: 1/2" = 1'-0"




**PLAN - APRON REINFORCEMENT**  
Scale: 1/2" = 1'-0"

No.	DATE	REVISIONS
6		
5		
4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

**CITY of TAMPA**  
Mobility Department  
Stormwater Engineering Division


**STANDARD INLET DETAILS**  
TYPE I INLET



**SECTION A-A**  
Scale: 1/2" = 1'-0"



**SECTION C-C**  
Scale: 1/2" = 1'-0"



**SECTION B-B**  
Scale: 1/2" = 1'-0"


\*LOCATION OF THROAT ELEVATION

No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1			4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

**CITY of TAMPA**  
Mobility Department  
Stormwater Engineering Division

**STANDARD INLET DETAILS**  
TYPE I INLET




**PLAN**  
Scale: 1/2" = 1'-0"




**PLAN - TOP SLAB REINFORCEMENT**  
Scale: 1/2" = 1'-0"

No.	DATE	REVISIONS	DES: STORM	<p><b>CITY of TAMPA</b> Mobility Department Stormwater Engineering Division</p>	<p><b>STANDARD INLET DETAILS</b> TYPE 2 INLET</p>	<p>SHEET <b>5</b> OF 40</p>
6			DRN: STORM			
5			CKD:			
4			DATE: 7/03			




PLAN - APRON REINFORCEMENT

Scale: 1/2" = 1'-0"



SECTION A-A  
Scale: 1/2" = 1'-0"




SECTION B-B  
Scale: 1/2" = 1'-0"

No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1			4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division

STANDARD INLET DETAILS  
TYPE 2 INLET



SECTION C-C  
Scale: 1/2" = 1'-0"



SECTION D-D  
Not To Scale


SCHEDULE OF REINFORCING STEEL B-RS (FOR INLET TOP -ND -PRON ONLY)					
M-RK	SIZE	COUNT	LENGTH	WT E-CH	TOT-L WT
T6-1	No 6	6	3' 4"	5.007	30.040
T6-2	No 6	1	2' 10 1/2"	4.318	4.318
T6-3	No 6	1	2' 5 1/2"	3.692	3.692
T6-4	No 6	1	2' 1/2"	3.067	3.067
T6-5	No 6	1	10"	1.252	1.252
T6-6	No 6	2	1' 1"	1.627	3.254
T6-7	No 6	1	1' 7 1/2"	2.441	2.441
T6-8	No 6	1	1' 2 1/2"	1.815	1.815
L6-1	No 6	2	4' 9"	7.135	14.269
L6-3	No 6	1	9' 4"	14.019	14.019
L6-4	No 6	1	8' 10 1/2"	13.330	13.330
L6-5	No 6	1	5' 1 3/4"	7.729	7.729
L6-9	No 6	1	3' 9 3/4"	5.726	5.726
L7-2	No 7	1	9' 4"	19.077	19.077
L4-3	No 4	3	9' 4"	6.235	18.704
-4-1	No 4	8	1' 9"	1.169	9.352
-4-2	No 4	3	2' 9 1/4"	1.851	5.553
P4-1	No 4	5	1' 1 1/2"	0.752	3.758
B6-1	No 6	2	3' 8 1/2"	5.570	11.140
X6-1	No 6	1	5' 8 1/2"	8.574	8.574
TOT-L WEIGHT IN POUNDS					181.109

No.	DATE	REVISIONS
6		
5		
4		

DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03


CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division

STANDARD INLET DETAILS  
TYPE 2 INLET




PLAN - APRON REINFORCEMENT

Scale: 1/2" = 1'-0"



SECTION A-A

Scale: 1/2" = 1'-0"



SECTION B-B

Scale: 1/2" = 1'-0"


No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1			4		

DES: STORM  
 DRN: STORM  
 CKD:  
 DATE: 7/03


CITY of TAMPA  
 Mobility Department  
 Stormwater Engineering Division

STANDARD INLET DETAILS  
 TYPE 3 INLET





SECTION C-C  
Scale: 1/2" = 1'-0"



SECTION D-D  
Not To Scale


EINFORCING STEEL B-RS (OP -ND -PRON ONLY)		
LENGTH	WT E-CH	TOT-L WT
3' 4"	5.007	30.040
2' 10 1/2"	4.318	8.637
2' 5 1/2"	3.692	7.385
2' 1/2"	3.067	6.133
10"	1.252	2.503
1' 1"	1.627	3.254
1' 7 1/2"	2.441	4.882
1' 2 1/2"	1.815	3.630
4' 9"	7.135	14.269
5' 1 3/4"	7.729	7.729
13' 11"	20.903	20.903
13' 1/4"	19.557	19.557
2' 11"	4.381	4.381
3' 9 3/4"	5.726	5.726
13' 11"	28.446	28.446
13' 11"	9.296	9.296
1' 9"	1.169	14.028
2' 9 1/4"	1.851	7.404
1' 1 1/2"	0.752	4.509
3' 8 1/2"	5.570	22.279
5' 8 1/2"	8.574	17.148
		242.138

No.	DATE	REVISIONS
6		
5		
4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division

STANDARD INLET DETAILS  
TYPE 3 INLET




PLAN



SECTION A-A

TYPE 1 INLET (OFFSET)

Scale: 1/2" = 1'-0"



TYPE 1 INLET (OFFSET)  
WITH SIDE AND/OR BACK OPENINGS

Scale: 1/2" = 1'-0"

**TYPE 1 INLET (OFFSET)**

In cases where a curb inlet is used but no barrier curb is present, the Type 1 inlet shall be offset as shown herein. Preferably, Miami curb shall be used to convey runoff along the edge of pavement to the inlet.

In cases where no Miami curb is used, the offset shall remain as shown herein and the concrete apron shall be extended on a 1.5-to-1 horizontal angle to meet the edge of pavement. The concrete apron shall be reinforced with Number 4 steel bars at 11" on center. (Disregard the A4-designated bar counts and lengths in the Schedule of Reinforcing.)

Payment for the concrete apron, curb transitions and all other work incidental to offsetting the inlet shall be made under the Type 1 Inlet contract pay item and no separate nor additional payment shall be made for this modification to the standard.

**TYPE 1 INLET WITH TYPE D CURB**

In cases where a curb inlet is used with Type D Curb, the Type 1 Inlet may be offset as shown in "Type 1 Inlet (Offset)" or may be constructed in the same alignment as the standard detail; i.e. with the face of the inlet top aligned with the face of curb.

If the standard alignment is used, the concrete inlet throat shall be constructed as shown in the standard. A 2'-6" long concrete transition section shall be constructed on each side of the concrete inlet throat. This section shall transition from the Type D Curb (no gutter) to the 1'-6" wide concrete inlet throat.

Payment for the concrete apron or concrete inlet throat, curb transitions and all other work incidental to offsetting the inlet or adapting the inlet to a Type D Curb shall be made under the Type 1 Inlet contract pay item and no separate nor additional payment shall be made for this modification to the standard.

**TYPE 1 INLET WITH SIDE AND/OR BACK OPENINGS**

If side and/or back openings are called for in the project plans, dimensions of the openings shall be as shown in the detail included herein. Additional P4-1 reinforcing bars shall be used at the rate of four (4) per post section, as applicable. Six (6) inch thick concrete apron(s) as shown in the project plans shall be constructed at each side and back opening.


Payment for concrete aprons and all other work incidental to constructing inlets with side and/or back openings shall be made under the Inlet contract pay item and no separate nor additional payment shall be made for this modification to the standard.

No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1			4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division


STANDARD INLET DETAILS  
TYPE 1 INLET MODIFIED



**PLAN**  
Scale: 1/2" = 1'-0"



**PLAN - TOP SLAB REINFORCEMENT**  
Scale: 1/2" = 1'-0"






**PLAN - APRON REINFORCEMENT**  
Scale: 1/2" = 1'-0"

No.	DATE	REVISIONS
6		
5		
4		

DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

**CITY of TAMPA**  
Mobility Department  
Stormwater Engineering Division

**STANDARD INLET DETAILS**  
TYPE BS-I CURB INLET




SCHEDULE OF REINFORCING STEEL BARS (FOR INLET TOP AND APRON ONLY)					
MARK	SIZE	COUNT	LENGTH	WT EACH	TOTAL WT
A4-1	No 4	1	3' 11 3/4"	2.658	2.658
A4-2	No 4	1	4' 11"	3.285	3.285
A4-3	No 4	3	7' 4"	4.898	4.898
B4-1	No 4	2	2' 9"	1.837	3.674
B4-2	No 4	2	3' 7 3/4"	2.436	4.871
B4-3	No 4	2	5' 0 3/4"	3.382	6.764
B4-4	No 4	3	3' 6 3/4"	2.380	7.140
S6-1	No 6	5	5' 3"	7.886	39.428
S6-2	No 6	2	2' 11"	4.381	8.763
S6-3	No 6	1	1' 2 1/2"	1.814	1.814
S6-4	No 6	4	3' 11 3/4"	5.976	23.906
S6-5	No 6	1	4' 10 1/2"	7.322	7.322
S6-6	No 6	1	6' 8"	10.014	10.014
S6-8	No 6	2	1' 7 1/2"	29.289	58.578
S7-1	No 7	1	7' 4"	14.989	14.989
V4-1	No 4	2	1' 8 1/2"	1.141	2.282
W4-1	No 4	2	3' 6"	2.338	4.676
W4-2	No 4	2	2' 1"	1.391	2.783
TOTAL WEIGHT IN POUNDS					217.641

No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1			4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division


STANDARD INLET DETAILS  
TYPE BS-I CURB INLET



**PLAN**  
Scale: 1/2" = 1'-0"



**PLAN - TOP SLAB REINFORCEMENT**  
Scale: 1/2" = 1'-0"



**PLAN - APRON REINFORCEMENT**  
Scale: 1/2" = 1'-0"


No.	DATE	REVISIONS
6		
5		
4		

DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03


**CITY of TAMPA**  
Mobility Department  
Stormwater Engineering Division

**STANDARD INLET DETAILS**  
TYPE BV-I CURB INLET


\*LOCATION OF THROAT ELEVATION



SECTION A-A  
Scale: 1/2" = 1'-0"



SECTION B-B  
Scale: 3/4" = 1'-0"



SECTION C-C  
Scale: 1/2" = 1'-0"

SCHEDULE OF REINFORCING STEEL BARS (FOR INLET TOP AND APRON ONLY)											
MARK	SIZE	COUNT	LENGTH	WT EACH	TOTAL WT	MARK	SIZE	COUNT	LENGTH	WT EACH	TOTAL WT
A4-4	No 4	1	4' 11 1/2"	3.312	3.312	S6-2	No 6	5	2' 11"	4.381	8.763
A4-5	No 4	1	6' 7"	4.397	4.397	S6-3	No 6	2	1' 2 1/2"	1.814	3.629
A4-6	No 4	3	9' 7 3/4"	6.444	19.331	S6-6	No 6	1	6' 8"	10.014	10.014
B4-1	No 4	2	2' 9"	1.837	3.674	S6-7	No 6	1	9' 7 3/4"	14.488	14.488
B4-2	No 4	2	3' 7 3/4"	2.436	4.871	S6-9	No 6	4	4' 11 1/2"	7.447	29.788
B4-3	No 4	2	3' 6 3/4"	2.380	4.760	S6-10	No 6	2	2' 6"	3.755	7.510
B4-4	No 4	4	3' 6 3/4"	2.380	9.520	S7-2	No 7	1	9' 7 3/4"	19.716	19.716
P4-1	No 4	4	1' 3"	0.835	3.340	V4-1	No 4	2	1' 8 1/2"	1.141	2.282
S6-1	No 6	6	5' 3"	7.886	47.313	W4-1	No 4	4	3' 6"	2.338	9.352
TOTAL WEIGHT IN POUNDS										208.064	

No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1			4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division

STANDARD INLET DETAILS  
TYPE BV-I CURB INLET




SW




**SECTION A-A**  
Scale: 1/2" = 1'-0"

\*LOCATION OF THROAT ELEVATION



**SECTION B-B**  
Scale: 3/4" = 1'-0"



**SECTION C-C**  
Scale: 1/2" = 1'-0"

SCHEDULE OF REINFORCING STEEL BARS (FOR INLET TOP AND APRON ONLY)											
MARK	SIZE	COUNT	LENGTH	WT EACH	TOTAL WT	MARK	SIZE	COUNT	LENGTH	WT EACH	TOTAL WT
A4-7	No 4	1	5' 4"	3.562	3.562	S6-1	No 6	3	5' 3"	7.886	23.657
A4-8	No 4	1	10' 3 1/2"	6.875	6.875	S6-2	No 6	2	2' 11"	4.381	8.763
A4-9	No 4	1	10' 9 1/2"	7.209	7.209	S6-3	No 6	2	1' 2 1/2"	1.814	3.629
A4-10	No 4	1	11' 2 1/2"	7.487	7.487	S6-9	No 6	4	4' 11 1/2"	7.447	29.788
B4-1	No 4	2	2' 9"	1.837	3.674	S6-10	No 6	2	2' 6"	3.755	7.510
B4-4	No 4	4	3' 6 3/4"	2.380	9.520	S6-11	No 6	1	9' 7"	14.394	14.394
B4-5	No 4	2	3' 3 1/2"	2.199	4.398	S6-12	No 6	1	10' 2"	15.271	15.271
B4-6	No 4	2	4' 0 3/4"	2.714	5.428	S6-13	No 6	2	5' 1 1/2"	7.698	15.396
B4-7	No 4	2	4' 10 1/2"	3.257	6.513	S6-14	No 6	1	5' 2 1/2"	7.822	7.822
P4-1	No 4	4	1' 3"	0.835	3.340	S7-3	No 7	1	10' 4 3/4"	21.249	21.249
						W4-1	No 4	4	3' 6"	2.338	9.352
<b>TOTAL WEIGHT IN POUNDS</b>										<b>214.837</b>	


No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1			4		

DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03


**CITY of TAMPA**  
Mobility Department  
Stormwater Engineering Division

**STANDARD INLET DETAILS**  
**TYPE BR-I CURB INLET**

SHEET  
**17**  
OF 40



PLAN - EXIST. INLET  
Scale: 1/2" = 1'-0"



PLAN - NEW TOP SLAB REINFORCEMENT

Scale: 1/2" = 1'-0"

Note:  
-LL B-RS SH-LL H-VE  
180 DEGREE HOOKS  
(TYPIC-L)

No.	DATE	REVISIONS
6		
5		
4		

DES: STORM  
DRN: STORM  
CKD:  
DATE: 9/23/13


CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division

STANDARD INLET DETAILS  
HS-20 RATED TYPE BR-I CURB INLET

SCHEDULE OF REINFORCING #6 STEEL BARS (INLET TOP ONLY)					
MARK	SIZE	COUNT	LENGTH	WT EACH	TOTAL WT
A5-1	No 5	2	7 15/16"	.69	1.38
A5-2	No 5	2	1'-0 3/4"	1.15	2.30
A5-3	No 5	2	4'-11 1/4"	5.19	10.38
A5-4	No 5	1	5'-0 1/8"	5.23	5.23
A5-5	No 5	1	5'-0 11/16"	5.29	5.29
A5-6	No 5	2	5'-1"	5.31	10.62
A5-7	No 5	1	2'-6 7/8"	2.69	2.69
A5-8	No 5	1	2'-6 3/8"	2.65	2.65
A5-9	No 5	1	4'-11 9/16"	5.16	5.16
A5-10	No 5	2	2'-8"	2.78	5.56
A5-11	No 5	5	4'-10 1/2"	5.09	25.45
A5-12	No 5	2	2'-4 1/2"	2.48	4.96
A5-13	No 5	1	7'-3"	7.56	7.56
A5-14	No 5	1	10'-1 7/8"	10.60	10.60
A5-15	No 5	1	10'-3 7/16"	10.73	10.73
TOTAL WEIGHT IN POUNDS FOR TOP BARS					110.56


SCHEDULE OF REINFORCING #6 STEEL BARS (INLET TOP ONLY)					
MARK	SIZE	COUNT	LENGTH	WT EACH	TOTAL WT
A6-1	No 6	2	7 15/16"	1.0	2.0
A6-2	No 6	2	1'-0 3/4"	1.65	3.30
A6-3	No 6	2	4'-11 1/4"	7.5	15
A6-4	No 6	1	5'-0 1/8"	7.53	7.53
A6-5	No 6	1	5'-0 11/16"	7.61	7.61
A6-6	No 6	2	5'-1"	7.66	15.32
A6-7	No 6	1	2'-6 7/8"	3.91	3.91
A6-8	No 6	1	2'-6 3/8"	3.88	3.88
A6-9	No 6	1	4'-11 9/16"	7.51	7.51
A6-10	No 6	2	2'-8"	4.13	8.26
A6-11	No 6	5	4'-10 1/2"	7.36	36.8
A6-12	No 6	2	2'-4 1/2"	3.75	7.5
A6-13	No 6	1	7'-3"	10.81	10.81
A6-14	No 6	1	10'-1 7/8"	15.17	15.17
A6-15	No 6	1	10'-3 7/16"	15.51	15.51
TOTAL WEIGHT IN POUNDS FOR BOTTOM BARS					160.11

NOTE 1)




NOTE 2)

BAR LENGTH AND ASSOCIATED WEIGHT PROVIDED DOES NOT INCLUDE THE BAR HOOK LENGTH AND WEIGHT.



SECTION B-B  
Scale: 1/2" = 1'-0"



SECTION A-A  
Scale: 1/2" = 1'-0"

#5 - 180 DEGREE HOOK DETAIL  
Scale: 1/2" = 1'-0"


#7 - 180 DEGREE HOOK DETAIL  
Scale: 1/2" = 1'-0"

No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
△	03/31/16	NEW SHEET	4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 9/23/13

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division


STANDARD INLET DETAILS  
HS-20 RATED TYPE BR-I CURB INLET



**PLAN**  
Scale: 1/2" = 1'-0"



**PLAN - TOP SLAB REINFORCEMENT**  
Scale: 1/2" = 1'-0"



**PLAN - APRON REINFORCEMENT**  
Scale: 1/2" = 1'-0"


No.	DATE	REVISIONS
6		
5		
4		

DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

**CITY of TAMPA**  
Mobility Department  
Stormwater Engineering Division


**STANDARD INLET DETAILS**  
TYPE BR-2 CURB INLET





PLAN - EXIST. INLET

Scale: 1/2" = 1'-0"



PLAN - NEW TOP SLAB REINFORCEMENT

Scale: 1/2" = 1'-0"

Note:  
-LL B-RS SH-LL H-VE  
180 DEGREE HOOKS  
(TYPIC-L)

No.	DATE	REVISIONS
6		
5		
4		

DES: STORM  
DRN: STORM  
CKD:  
DATE: 9/23/13


CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division

STANDARD INLET DETAILS  
HS-20 RATED TYPE BR-2 CURB INLET

SCHEDULE OF REINFORCING #5 STEEL BARS (INLET TOP ONLY)					
MARK	SIZE	COUNT	LENGTH	WT EACH	TOTAL WT
A5-1	No 5	6	5'-1 1/4"	5.424	32.544
A5-2	No 5	5	3'-11 3/4"	4.172	20.86
A5-3	No 5	1	5'-1 1/2"	5.5	5.5
A5-4	No 5	1	6'-11"	7.3	7.3
A5-5	No 5	1	7'-0 1/2"	7.40	7.40
A5-6	No 5	2	2'-6 7/8"	2.72	5.44
A5-7	No 5	1	1'-1"	1.147	1.147
A5-8	No 5	1	8 1/2"	.78	.78
A5-9	No 5	1	2'-5 7/8"	2.575	2.575
A5-10	No 5	1	11"	.956	.956
A5-11	No 5	2	1'-5 1/2"	1.56	3.12
TOTAL WEIGHT IN POUNDS FOR TOP BARS					87.622




SCHEDULE OF REINFORCING #7 STEEL BARS (INLET TOP ONLY)					
MARK	SIZE	COUNT	LENGTH	WT EACH	TOTAL WT
A7-1	No 7	6	5'-1 1/4"	10.25	61.5
A7-2	No 7	5	3'-11 3/4"	8.176	40.88
A7-3	No 7	1	5'-1 1/2"	10.25	10.25
A7-4	No 7	1	6'-11"	14.3	14.3
A7-5	No 7	1	7'-0 1/2"	14.5	14.5
A7-6	No 7	2	2'-6 7/8"	5.32	10.64
A7-7	No 7	1	1'-1"	2.25	2.25
A7-8	No 7	1	8 1/2"	1.65	1.65
A7-9	No 7	1	2'-5 7/8"	5.11	5.11
A7-10	No 7	1	11"	1.874	1.874
A7-11	No 7	2	1'-5 1/2"	3.0	6.0
TOTAL WEIGHT IN POUNDS FOR BOTTOM BARS					168.954

NOTE 1)



NOTE 2)

BAR LENGTH AND ASSOCIATED WEIGHT PROVIDED DOES NOT INCLUDE THE BAR HOOK LENGTH AND WEIGHT.




No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
△	03/31/16	NEW SHEET	4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 9/23/13

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division

STANDARD INLET DETAILS  
HS-20 RATED TYPE BR-2 CURB INLET




PLAN




SECTION


TYPE "T" GRATE INLET  
Scale: 1/2" = 1'-0"



CAST IRON GRATING  
Traffic Bearing




PLAN



SECTION

TYPE "E" GRATE INLET  
Scale: 1/2" = 1'-0"




CAST IRON GRATING  
Traffic Bearing

No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1			4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division

STANDARD INLET DETAILS  
TYPE "T" & "E" GRATE INLET




PLAN



SECTION

\* WHEREVER POSSIBLE, 6'-2"x3'-0" INSIDE DIMENSION BOX MAY BE USED WITH THE ENGINEER'S APPROVAL.



CAST IRON GRATING  
Traffic Bearing

NOTE:  
IF SIDE OPENINGS (SLOTS) ARE DESIRED IN GRATE INLETS, OPENINGS SHALL BE DESIGNED ON A CASE-BY-CASE BASIS, AND SHALL ACCOUNT FOR SUPPORT OF THE CAST IRON GRATE ABOVE THE OPENING.


TYPE "H" GRATE INLET  
Scale: 1/2" = 1'-0"

No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1			4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division


STANDARD INLET DETAILS  
TYPE H GRATE INLET




COVER SECTION




COVER B-CK



COVER F-CE



ST-ND-RD FR-ME SECTION



INVERTED FR-ME SECTION

MANHOLE FRAMES & COVER

Not To Scale

NOTE: Manhole structures shall be per FDOT Standard Index #200.

FOR CLOSED BASINS

No.	DATE	REVISIONS	DES: STORM	CITY of TAMPA Mobility Department Stormwater Engineering Division	STANDARD MANHOLE DETAILS	SHEET 26 OF 40
6			DRN: STORM			
5			CKD:			
4			DATE: 7/03			

**CURB INLET CONSTRUCTION NOTES**  
 TYPES 1,2,3 AND BS-1, BV-1, BR-1, BR-2

1. Concrete for top slabs, bottom slabs, walls, aprons and curb-and-gutter transition sections shall be Class II Concrete, conforming to Section 346 of the project specifications, with reinforcing bars placement and spacing as indicated herein. Top slabs shall not be poured until all reinforcing bars have been placed, inspected and approval obtained.

2. Curb inlets are typically designed with the outlet pipe at the front wall of the structure. Otherwise, maximum pipe size that will fit the side wall of any standard curb inlet is 24 inches. Larger pipe sizes and 24-inch pipes meeting the side wall at an angle other than 90 degrees require a larger substructure. Curb inlets may be modified to utilize inlet risers and tops meeting City inlet standards with substructures meeting FDOT standards for structure bottoms (Index #200). Design of these non-standard inlet structures shall be on case-specific basis.

3. Refer to FDOT Standard Index #200 for reinforcing steel requirements at pipe openings. Any portion of the pipe protruding beyond the inside wall surface of the box shall be broken off and mortared to a smooth finish flush with the inside wall surface.

4. At the discretion of the Engineer, boxes may be constructed of solid clay or portland cement concrete brick and mortar. The inside surface of all brick walls shall be plastered with one-half inch minimum thickness of 1:2 mix sand-cement mortar and left with a smooth finish.

5. Minimum brick wall thickness shall be 7½ inches when the distance (depth) from the rim of the cast ring and cover to the top of the bottom slab does not exceed 8 feet, and shall be 12 inches when such depth exceeds 8 feet. Brick shall be laid in stretcher courses with every sixth course a header course.

6. Minimum clearance for all reinforcing bars shall be 1½ inches from the nearest surface of the concrete member. Top slab reinforcement shall be 2 inches from the bottom of the slab. Other minimum clearances are as shown in drawings.

7. Wing for inlet Types 2, BS-1 and BR-2 shall be placed on the upstream side of the center of box, with plan reversed if necessary because of the direction of gutter flow.

8. Curb transition sections shall be included in the contract price of the inlet, and no separate payment shall be made.

9. Top slab of all curb inlets shall be sloped at 2 percent toward the street.

10. Dimensions shown for inlet types BR-1 and BR-2 are for the indicated curb radius only. Chord dimensions at the curb shall remain constant for other curb radii. Contractor shall adjust other inlet dimensions and reinforcing steel quantities to fit actual curb radius shown in the project plans.

11. Reinforcing steel shall be ASTM Grade 60. Ring and cover material shall be ASTM-A48 Class 30 B Gray Iron.

12. Inlet cover weight is 85 lbs. (approximate).



13. All construction joints shall follow FDOT Standard Index #201.

14. Side openings (slots) for curb inlets are to be used on Type 1 inlets (offset) only. Rear openings (slots) may be used on any curb inlet type. Refer to Sheet 10 for guidance.


15. Refer to Section 425 of the project specifications for additional requirements.

**NOTE TO ENGINEER:**

Inlet types BS-1 and BV-1 shall be the preferred types for application on tangents. Inlet types 1, 2 and 3 shall only be used when dictated by conditions that would preclude the use of types BS-1 and BV-1.





PLAN




SECTION

**STANDARD CAST IRON INLET RING AND COVER**


Scale: 1" = 1'-0"



A4-2



B6-1



T6-5

**BENDING DIAGRAMS**


Not To Scale

No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
△	12/09/04	REVISED COVER DIMENSIONS	4		


DES: STORM  
 DRN: STORM  
 CKD:  
 DATE: 7/03

**CITY of TAMPA**  
 Mobility Department  
 Stormwater Engineering Division


**STANDARD INLET DETAILS WITH NP (SNOOK) LID**




$B=C$   
 $C=1'-6"$  Minimum  
 (Use the greater of the two)  
**CONFLICT AT MID-POINT**  
 Not To Scale



$B_2=B_1$   
 $C=1'-6"$  Minimum  
 (Use the greater of the two)  
**CONFLICT AT CROWN**  
 Not To Scale



$B_4=B_3$   
 $C=1'-6"$  Minimum  
 (Use the greater of the two)  
**CONFLICT AT FLOWLINE**  
 Not To Scale



$C=B$   
**CONFLICT BELOW FLOWLINE WITH INSUFFICIENT CLEARANCE**  
 Not To Scale

be submitted to the  
 ation or beginning of  
  
 tent with FDOT Index  
 er.  
 be sleeved in  
  
 ved if a joint in the  
 ture.  
 rd Specification 441-2.3.  
  
 utility line or sleeve.  
 ter.

No.	DATE	REVISIONS
6		
5		
4		




DES: STORM  
 DRN: STORM  
 CKD:  
 DATE: 7/03

CITY of TAMPA  
 Mobility Department  
 Stormwater Engineering Division

GUIDELINES FOR CONFLICT MANHOLES

NOTE:

1. Open-bottom inlet shown herein is intended to be used at portable-pump locations (see temporary force main and pumping standards). For other open-bottom inlet applications, refer to FDOT Index #201 for guidance.
2. Follow Type "E" grate inlet standard for steel reinforcement of concrete.
3. For grate type and dimensions see Type "E" grate inlet standard.
4. A similar open-bottom substructure may be used in conjunction with City of Tampa curb type open-bottom inlets.
5. River gravel shall be clean and conform to D.O.T. specifications under Section 901-2 and shall meet ASTM size no. 4 gradation (1-1/2" to 3/4" size).
6. All exposed concrete corners and edges shall be chamfered 3/4".
7. Filter fabric shall meet FDOT Standard Specification 441-2.3.




No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1			4		

DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division

STANDARD INLET DETAILS  
OPEN BOTTOM INLET (TYPE "E")



**SECTION**  
Scale: 1/2" = 1'-0"

No.	DATE	REVISIONS
6		
5		
4		


DES: STORM  
DRN: STORM  
CKD:  
DATE:

**CITY of TAMPA**  
Mobility Department  
Stormwater Engineering Division


**TEMPORARY FORCE MAIN AND PUMPING STANDARDS**

Notes:


1. All types of pipe bedding shall extend to undisturbed earth at sides and bottom of the trench.
2. Sand and crushed stone pipe bedding shall be placed and compacted in accordance with specifications.
3. Bedding materials shall meet project specifications for Class B and Class C Bedding.
4. Filter fabric shall meet FDOT Standard Specification 441-2.3.



CLASS B-1 BEDDING



CLASS B BEDDING




CLASS C BEDDING

No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1	12/09/04	NEW SHEET	4		

DES: STORM  
 DRN: STORM  
 CKD:  
 DATE:

CITY of TAMPA  
 Mobility Department  
 Stormwater Engineering Division

BEDDING DETAILS



PAYMENT LIMITS FOR ADDITIONAL SAND OR CRUSHED STONE ABOVE THE PIPE BEDDING (SEE NOTE 4 REGARDING SAND)

PIPE BEDDING (SEE DETAIL)

As Ordered In Writing By The Engineer


PAYMENT LIMITS FOR ADDITIONAL SAND OR CRUSHED STONE BELOW THE PIPE BEDDING (SEE NOTE 4 REGARDING SAND)

**PAYMENT LIMITS FOR SURFACE RESTORATION AND ADDITIONAL SAND OR CRUSHED STONE FOR TRENCH STABILIZATION**  
Not To Scale

**Notes:**

1. Payment for additional crushed stone of Class D concrete pipe bedding materials will be made only for pipe bedding not shown in the plans and ordered in writing by the engineer.
2. Payment for surface restoration will be made for the actual quantities, as determined by the engineer, of surface restored within the payment limits shown.
3. Payment for additional sand or crushed stone for trench stabilization, ordered in writing by the engineer, will be made for the actual compacted volume, as determined by the engineer, of sand or crushed stone placed within the payment limits shown.
4. Contractor shall use all surplus sand, approved as suitable, from excavations in this contract prior to supplying sand from other sources. Payment for additional sand will be made only for sand supplied from sources other than excavations in this contract. See specifications for materials requirements.

QUANTITIES FOR PAYMENT FOR ADDITIONAL PIPE BEDDING MATERIALS ORDERED IN WRITING BY THE ENGINEER											
NOMINAL INSIDE DIAMETER (INCHES)	15	18	24	30	36	42	48	54	60	66	72
CUBIC YARDS OF CONCRETE PER LINEAR FOOT OF PIPE IN CONCRETE ENCASEMENT	0.258	0.299	0.383	0.472	0.588	0.690	0.797	0.909	1.027	1.150	1.279
CUBIC YARDS OF CONCRETE PER LINEAR FOOT OF PIPE IN CLASS A BEDDING (CONCRETE CRADLE)	0.128	0.150	0.192	0.236	0.294	0.345	0.399	0.455	0.514	0.514	0.640
CUBIC YARDS OF CRUSHED STONE PER LINEAR FOOT OF PIPE IN CLASS B-1 BEDDING	0.304	0.362	0.479	0.608	0.781	0.936	1.103	1.281	1.471	1.673	1.887
CUBIC YARDS OF CRUSHED STONE PER LINEAR FOOT OF PIPE IN CLASS B BEDDING	0.111	0.143	0.207	0.280	0.381	0.475	0.578	0.590	0.810	0.939	1.078



**Notes:**

1. Stainless steel casing spacers as manufactured by Cascade or equal may be used rather than a timber skid system.
2. All casing pipes shall be welded steel pipe conforming to ASTM DES A139 Grade B or ASTMDES A53 Grade B, having a minimum inside diameter as indicated on plans. The minimum wall thickness shall be 3/8" or thicker if so indicated on the plan and profile drawings.

CORRESPONDING CARRIER AND CASING PIPE SIZES											
NOMINAL INSIDE DIAMETER OF CARRIER PIPE (INCHES)	15	18	24	30	36	42	48	54	60	66	72
MINIMUM INSIDE DIAMETER OF CASING PIPE (INCHES)	30	36	48	60	60	66	78	84	90	96	102



DETAIL OF JACKED CROSSINGS  
Not To Scale

No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1	12/09/04	NEW SHEET	4		


DES: STORM  
DRN: STORM  
CKD:  
DATE:

**CITY of TAMPA**  
Mobility Department  
Stormwater Engineering Division

**PAYMENT LIMITS & JACKED CROSSINGS**




Note:  
Guards to be constructed only at locations specified in detail plans



CRETE COLLAR FOR EXTENSION OF EXISTING PIPE CULVERT

Not To Scale

Note:  
Stormwater Engineering does not allow blind conections to existing or proposed pipes.



GUARD AT PIPE ENDS


Not To Scale

No.	DATE	REVISIONS
6		
5		
4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 6/19

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division


MISCELLANEOUS DETAILS



PIPE PLUG  
Not To Scale



THRUST BLOCK  
Not To Scale



Notes:



1. Concrete shall be kept at sufficient distance from joints for removal of all joint accessories including bolts.
2. All bearing surfaces are to be carried to undisturbed soil.
3. Poor soil (silty soils, clay, muck or peat) will require larger thrust blocks.

No.	DATE	REVISIONS
6		
5		
4		


DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division

MISCELLANEOUS DETAILS




PIPE SECTION



CONCRETE JACKET FOR CONNECTING DISSIMILAR TYPES OF PIPES

Not To Scale



JOINT SECTION (BEFORE PULL-UP)

ELLIPTICAL CONCRETE PIPE JOINTS


Not To Scale

concrete jacket shall be provided at any

be provided at least at the last two joints if the pipe is not secured by an end ecify concrete jacket at other joints.

et and filter fabric jacket are to be included il pipe culverts.

t FDOT Standard Specification 441-2.3.



ELLIPTICAL CONCRETE PIPE JACKET


Not To Scale

No.	DATE	REVISIONS
6		
5		
4		

DES: STORM  
DRN: STORM  
CKD:  
DATE: 7/03

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division


MISCELLANEOUS DETAILS



**CONCRETE APRON \***

CULVERT PIPE	MINIMUM COVER
Class III RCP	12"
Class IV RCP	9"
Corrugated HDPE	12"
C-900 PVC	12"


ROUND PIPE TO ELLIPTICAL PIPE CONVERSION	
ROUND PIPE	ELLIPTICAL PIPE (Concrete Only)
15"	12" x 18"
18"	14" x 23"
24"	19" x 30"
30"	24" x 38"



**ASPHALT APRON \***

CULVERT PIPE	MINIMUM COVER
Class III RCP	15"
Class IV RCP	12"
Corrugated HDPE	15"
C-900 PVC	15"

ROUND PIPE TO TRENCH DRAIN CONVERSION	
ROUND PIPE	CROSS-SECTIONAL AREA (For Trench Drain Conversions)
15"	1.2 S.F.
18"	1.8 S.F.
24"	3.1 S.F.
30"	4.9 S.F.



**UNPAVED APRON \***

CULVERT PIPE	MINIMUM COVER
Class III RCP	15"
Class IV RCP	12"
Corrugated HDPE	15"
C-900 PVC	15"

\* WHEN MINIMUM COVER COULD NOT BE ACHIEVED; TRENCH DRAIN MUST BE USED. (NO SWALED D/W'S)

MINIMUM COVER FOR CULVERT SIZES UP TO 30" ROUND AND 24" X 38" ELLIPTICAL PIPE  
(Larger Sizes Require Stormwater Department Approval)

No.	DATE	REVISIONS
6		
5		
4		


DES: STORM  
DRN: STORM  
CKD:  
DATE:

CITY of TAMPA  
Mobility Department  
Stormwater Engineering Division


RESIDENTIAL DRIVEWAY  
CULVERT STANDARDS

SW

PROVIDE  
NORTH ARROW



Not To Scale



PROP - PROPOSED  
 EX - EXISTING  
 EOP - EDGE OF PAVEMENT  
 $\mathcal{P}$  - PROPERTY LINE  
 $\mathcal{C}$  - CENTERLINE  
 TOB - TOP OF BANK  
 INV - INVERT ELEVATION  
 ELEV - ELEVATION  
 DIA - DIAMETER OF PIPE/CULVERT  
 DIRECTION OF DRAINAGE FLOW


No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
$\Delta$	12/09/04	NEW SHEET	4		

DES: STORM  
 DRN: STORM  
 CKD:  
 DATE:


CITY of TAMPA  
 Mobility Department  
 Stormwater Engineering Division

RESIDENTIAL DRIVEWAY  
 CULVERT STANDARDS


SHEET  
**37**  
 OF 40



**TYPICAL TRENCH DRAIN**  
Not to Scale




**LARGER THROAT EXAMPLE**  
Not to Scale



**12" MIN THROAT EXAMPLE**  
Not to Scale

**TRENCH DRAIN SUBSTITUTION FOR  
CULVERT IN LOW-COVER CONDITIONS**

Use Cross-Sectional Area Chart to convert from pipe size  
Swaled driveways are not permitted - use trench drains



**DRIVEWAY CROSSING DETAIL**

SCALE: 1/8" = 1'-0"

**NOTE:**



FOR DRIVEWAYS WITH WIDTH OVER 15', INSTALL EXPANSION JOINT AT THE CENTERLINE

No.	DATE	REVISIONS	No.	DATE	REVISIONS
1	07/11/23	ADDED DRIVEWAY CROSSING DETAIL	6		
2	03/27/23	CHANGED DEPTH OF TRENCH TO "VARIES"	5		
3	03/31/16	NEW SHEET	4		



DES: STORM  
DRN: STORM  
CKD:  
DATE:

**CITY of TAMPA**  
Mobility Department  
Stormwater Engineering Division

**RESIDENTIAL DRIVEWAY  
TRENCH DRAIN EXAMPLES**





NOTE:  
TRENCH DRAIN LENGTH DOES NOT INCLUDE MES LENGTH



**CONCRETE ENDWALL WITH 45° WINGS FOR TRENCH DRAINS**

**GENERAL NOTES**

1. Winged concrete endwalls are intended for use outside the clear zone.
2. Chamfer all exposed edges 3/4".
3. Concrete shall be Class I, except ASTM C478 (4000 psi) Concrete may be substituted for precast items manufactured in plants meeting the requirements of Section 449 of the Specifications.
4. Endwall to be paid for under the contract unit price for Class I Concrete.
5. Sodding to be in accordance with Index No. 281, and paid for under the contract unit price for Performance Turf, SY.
6. Refer to FDOT Index 430-040 for specifications.




No.	DATE	REVISIONS	No.	DATE	REVISIONS
3	07/18/23	REVISED TRENCH DEPTH TO REFLECT "VARIES"	6		
2	07/11/23	ADDED TRENCH DRAIN, MITERED-END DETAIL, AND SECTIONS	5		
1	05/21/18	NEW SHEET	4		

DES: STORM  
DRN: STORM  
CKD:  
DATE: 05/18



**CITY of TAMPA**  
Mobility Department  
Stormwater Engineering Division

**MODIFIED HEADWALL / MITERED END FOR TRENCH DRAIN**



PAY ITEMS  
 DRIVEWAY RESORATION:  
 ASPHALT  
 CONCRETE  
 TRENCH DRAIN

NOTE:  
 ALL PAY ITEMS ARE  
 BASED ON A 70'  
 TYPICAL LOT WIDTH



No.	DATE	REVISIONS	No.	DATE	REVISIONS
3			6		
2			5		
1	12/09/04	NEW SHEET	4		

DES: STORM  
 DRN: STORM  
 CKD:  
 DATE: 12/04

**CITY of TAMPA**  
 Mobility Department  
 Stormwater Engineering Division

**VALLEY DRIVEWAY TO FLAT DRIVEWAY - NO PIPE**  
**RELIC DITCH SYSTEMS**