



Section C

Stormwater Service Assessment Program Report

Tampa City Council Update No. 15 - August 2020

Maintenance activities are reported based on service level frequency. Below is a list of the primary maintenance categories that are tracked. Along with service level cycle times, we have also provided maintenance statistics for the quarter.

Operations and Maintenance Activities	Pre Fee Service Levels	Fee Target Service Levels	3 rd Quarter FY20 & Year-to-Date Service Levels
Ditches	10-Year Cycle	7-Year Cycle	15-Year Cycle (3 rd Qtr.) 7.3-Year Cycle (Y.T.D)
Ponds	Minimal	3-Year Cycle	3-Year Cycle (3 rd Qtr.) 3-Year Cycle (Y.T.D)
Pipes	10-Year Cycle	7-Year Cycle	6.3-Year Cycle (3 rd Qtr.) 8.1-Year Cycle (Y.T.D)
Outfalls	15-Year Cycle	5-Year Cycle	N/A-Year Cycle (3 rd Qtr.) 2.3-Year Cycle (Y.T.D)
Pumps	Low Preventative Maintenance	Annual Preventative Maintenance	1-Year Cycle
Street Sweeping	90-Day Cycle	60-Day Cycle	51-Day Cycle (3 rd Qtr.) 54-Day Cycle (Y.T.D)
Operations and Maintenance Activities	3 rd Quarter Maintenance Statistics		
Ditches	16,550 linear feet of ditches maintained with 3,738 tons removed, 17 fallen trees removed, 441,765 linear feet of ditch mowed monthly with 7.9 tons of trash removed.		
Ponds	4.5 tons of trash and illegal dumping have been disposed of, there have been 114 herbicide treatments to various ponds, 126 stormwater ponds mowed monthly. 1,421 linear feet of pond fencing replaced.		
Pipes	109,602 linear feet of storm drain pipe inspected and maintained, 3,094 storm drain inlets and manholes inspected and maintained with 307 tons of debris removed. 21 cave-ins and 48 inlet tops repaired.		
Outfalls	Outfall inspections and maintenance were suspended due to high tides. Our year to date cycle of inspections and maintenance are still at an acceptable level.		
Pumps	Preventative Maintenance provided to all thirteen (13) stormwater pump stations. Continuous monitoring is ongoing with proactive maintenance and inspections.		
Street Sweeping	5,474 curb miles were swept, approximately 1,024 tons of debris removed. 2,617 linear feet of curbing replaced.		

Hamilton ROW Ditch

Before



After



Lois Alley Ditch South of Gandy

Before



After



Bayshore Seawall Just South of El Prado

Before



After



Davis Islands – Erie Ave. at West Davis Blvd.

Before



After

